Subject: CONSTRUCTION MEMORANDUM 02-55

Placement of Bituminous Mixtures Article 406.15

Effective: May 31, 2002

Expires: Indefinite

This Construction Memorandum supersedes Construction Memorandum No. 96-55, dated April 16, 1996

Quality in bituminous construction can be achieved if field personnel have a full understanding of the mixtures being produced, the specification requirements for each mixture, the tests that are required to be taken, and how to identify and correct problems as they develop.

The purpose of this memorandum is to present to District field personnel many of the tools and procedures with which they need to be familiar to properly supervise the placement of bituminous mixtures.

REFERENCES

Prior to the start of work, the Resident and staff should review the following documents:

- Bituminous pay item references in the Standard and Supplemental Specifications, special provisions, plan details and Construction Manual
- Manual of Test Procedures for Materials
- Bureau of Materials and Physical Research Policy Memoranda:
 - 01-18 Storage of Bituminous Mixes
 - 01-02 Approval of Hot-Mix Bituminous Plants and Equipment

ASPHALT CONTENT & DENSITY

It is important that the Contractor, Resident, and Proportioning Technician know the percentage of asphalt to be used in each bituminous mixture included in any particular project.

START-UP TEAM

The day prior to the bituminous laydown, a meeting should be held with the Supervising Field Engineer, Resident and Contractor to discuss the procedures, guidelines and equipment to be used and to ensure that the rollers meet the Specifications.

If the test strip evaluation indicates changes need to be made in the mix, another test strip may be required. If the evaluation shows the mix to be satisfactory, the roller pattern will then be established.

Less compactive effort is not a proper answer to too much density. A mix with excess density potential, as identified by a growth curve, should not be used. Data associated with development of the growth curve should be recorded on a form.

PAVER SPEED

The bituminous construction industry has recognized that continuous paver speed is essential to a smooth riding surface. Paver speed must be coordinated with both roller speed and plant production. Frequent start-stop operation of the paver should not be permitted. The Resident should check the speed of the paver and limit its maximum speed to that which is allowed by the Standard Specifications.

Bursts of paver speed to empty waiting truckloads of material makes it difficult to cover the mat with the established roller pattern. Usually, the faster the paver runs the lower the mat density will be behind the paver with a given rolling pattern/speed. Therefore, if a paver is permitted to run faster, additional compactive effort will be needed to achieve density.

AUTOMATIC GRADE CONTROL

The present Specifications (Article 406.15) for automatic grade control for bituminous pavers are based upon research which shows that a 9 m (30-foot) or longer ski provides a riding quality <u>superior</u> to that of the reference surface, a 3 m (10 ft) ski provides a riding quality <u>equal</u> to that of the reference surface, and a 150 mm (6 in) joint matching shoe provides a riding quality <u>substantially poorer</u> than that of the reference surface.

The Specifications reflect the results of the research data by requiring a minimum 9 m (30 ft) long ski on all lifts and passes except a 3 m (10 ft) long ski is permitted when placing the surface course adjacent to a previously-placed surface course and when traffic interference or sharp curves make the minimum 9 m (30-foot) ski impractical. While the use of a ski is mandatory, there are areas where it is impractical and/or impossible to use a ski. The Contractor may then be permitted to use manual grade control or a matching shoe. Such areas would include turn lanes, matching curb and gutter with good vertical alignment, short-length low-speed intersection improvements, side street returns, variable widths and depths of pavement, entrances, and other miscellaneous areas where the Resident determines that neither length ski can be practically used.

When placing bituminous mixtures within 60 m (200 ft) of a bridge abutment, Article 406.15 requires that the automatic grade control be operated from a present grade control stringline. This requirement should be strictly followed to ensure a smooth transition between pavement and bridge deck.

ROLLERS

Prior to the start of laydown operations, each roller shall be checked for compliance with its certificate of approval and the Specifications. Otherwise, the roller will have to be re-approved. Roller patterns shall be established during start-up operations on all bituminous mixtures. On Class I work, the breakdown roller should be kept reasonably close to the paver. When bituminous shoulders are placed simultaneously with the adjacent lane compaction on both the pavement and shoulder must be considered when establishing the rolling pattern. An additional roller may be required on the shoulder to obtain density at the paver's operating speed.

Vibratory roller speed and frequency of vibration must be matched to prevent transverse ridges which result from widely-spaced impacts. A vibratory roller operated at excessive speeds, producing impacts less than 30 blows per meter (I0 blows per foot), results in a rough choppy surface.

Maximum vibratory roller speed can be calculated using the following formula:

Max. Roller Speed=m/min. (ft/min) =

V.P.M. (Frequency measured in field by reed tachometer)

30 impacts/meter (10 impacts/foot)

Pneumatic-tired rollers should have a <u>uniform</u> tire pressure of not less than 550 kPa (80 p.s.i.)

DENSITY TESTS

We now recognize that over densification is one major cause of bituminous problems. Mixtures with densities in excess of 97% of a voidless mixture will likely result in channeling and flushing under traffic. Fortunately, a nuclear density device can give us a quick indication of mix problems.

BITUMINOUS SHOULDERS

The top lift of bituminous shoulders does not receive the kneading action of wheel loads to keep them "live." The durability of the top lift of bituminous aggregate mixture is increased by adding 0.5% additional asphalt to the asphalt content used in the lower lift as required by the Specifications.

If a flushed condition is observed after the increase in asphalt content, the asphalt content shall be promptly lowered by 0.2% from the flushed condition. Coordination between the Resident and QC/QA personnel is needed to assure the top lift contains the required amount of asphalt. The provision of the Specification for Bituminous Shoulders (Article 482.05) for increasing the asphalt content should be followed on all projects when bituminous aggregate mixture is used in Bituminous Shoulders.

The Contractor has the option of using higher type Class I Binder and Surface Course mixtures in lieu of bituminous aggregate mixture for resurfacing of shoulders. The 0.5% increase in asphalt content for the top lift is not required if the higher type Class I mixture is used.

Shoulder resurfacing widths of 2 m (6 ft) or less may be placed, at the Contractor's option, simultaneously with the adjacent traffic lane for both the binder and surface

courses provided the specified density, thickness and cross slope can be satisfactorily constructed. The paver shall operate with both tracks/drive wheels on the traffic lane. Shoulder resurfacing widths greater than 2 m (6 ft) shall be placed in a separate operation.

The quantity of bituminous mixture placed on the traffic lane will be limited to a calculated tonnage based upon actual mat width and length, plan thickness and design mix weight per millimeter (inch) of thickness. The difference between the total actual tonnage placed and the calculated tonnage used on the traffic lane will be paid for as Bituminous Shoulders. Separately-placed Class I mixtures will be permitted in all courses of shoulder construction.

Gary Gould

Engineer of Construction

Gay Gould

Example Construction Company

SAMPLE NOTIFICATION LETTER

101 Example Street Example, Illinois 00000
Gentlemen:
On, the bituminous mixture produced by your company had an asphalt content of percent and/or a density of percent. This does not meet the specification requirements contained in your contract.
Please bring this matter to the attention of the supervisory personnel of your company who are involved in the manufacture or placement of this material. Compliance with the contract requirements is the responsibility of your company and it is therefore important that your company take corrective action at the earliest possible moment.
Failure to take corrective action could result in suspension of the work, removal of the deficient material, or a reduction in contract price for the material in accordance with Article 105.03 of the Standard Specifications for Road and Bridge Construction.
We will cooperate with you in every way possible to eliminate this problem.
Very truly yours,
DISTRICT ENGINEER
By:
cc: (As applicable): District Construction Engineer

District Construction Engineer
Resident Engineer
Proportioning Technician
Supervising Field Engineer
District Materials Engineer
District Mixtures Control Engineer
District Laboratory Technician