

BRIDGE SECTION

131. Contract No. 68420 Peoria County District 4

Section D4 JOINT REPAIR 2005

FAP Route 317 (US 24 & IL 9)

This project consists of removing and replacing three bridge joints, the waterproofing membrane, and the bituminous wearing surface on the structure carrying U.S. Route 24/IL Route 9 over Toledo, Peoria & Western Railway and Wheeler Road located one mile east of Mapleton in Peoria County; includes 1,516 sq yds bituminous concrete removal (deck); 23 cu yds concrete superstructure; 3,655 lbs reinforcement bars, epoxy coated; 1,516 sq yds waterproofing membrane system; 3,330 ft pavement marking tape; 240 sq ft work zone pavement marking removal; 1,476 ft thermoplastic pavement marking line; 119 tons bituminous concrete surface course, SUPERPAVE, N50; 202 ft strip seal expansion joint assembly; 38 bar splicers; 200 sq yds protective shield; railroad protective liability; mobilization; traffic control and protection. (25 Working Days) (Job No. C-94-001-05) (4-40715-0007) (SUPERPAVE PROJECT) (0.00% DBE)