

## Letting Item Descriptions

Paving

Bridge

Electrical

Miscellaneous

5P for Review and Inspection

6P and 7P

Division of Aeronautics

IDNR Land Reclamation

**PAVEMENT SECTION**

1. Contract No. 62584 Cook County District 1  
Section (2323.6-2P&2324.6-1P)K  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-94-3(358)54  
1.68 miles of ramp reconstruction (northbound) from 31st Street to 39th Street and temporary shoulders from 31st Street to 47th Street all located along I-94/90 (Dan Ryan Expressway) in Chicago; includes 14,978 cu yds earth excavation; 4,843 cu yds removal and disposal of unsuitable material; 242 cu yds trench backfill; 19,939 sq yds topsoil; 4.25 acres seeding; 8,616 sq yds subbase granular material; 2,518 sq yds stabilized subbase; 3,364 sq yds concrete base course; 2,518 sq yds concrete pavement (jointed); 5,782 sq yds milling; 8,227 sq yds pavement removal; 214 sq yds bituminous shoulders, SUPERPAVE; removal of 2 existing structures; 292 cu yds concrete removal; 933 cu yds structure excavation; 504 cu yds concrete; 6,037 sq ft rustification finish; 20,460 lbs reinforcement bars; 62,850 lbs epoxy coated reinforcement bars; 6,735 sq ft temporary sheet piling; 425 ft steel plate beam guardrail; 6 traffic barrier terminals; 170 cu yds non-special waste disposal; 125 sq ft sign panel; 37.5 ft overhead sign structure-cantilever; 34,251 ft epoxy pavement marking; 1,512 ft conduit in trench; 4,431 ft trench and backfill; 353 ft drilled shafts in soil; 4,696 ft concrete curb and gutter; 2,518 sq yds whitewashing for concrete pavement; 1,184 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 5,907 sq ft concrete median surface; mobilization; traffic control and protection. (Completion Date: December 23, 2005 plus 5 working days) (Job No. C-91-086-03) (1-74823-0517) (SUPERPAVE) (25.00% DBE)
2. Contract No. 62585 Cook County District 1  
Section (2323.6-2P&2324.6-1P)K-1  
FAI Route 94/90 (SB) (DAN RYAN EXPRESSWAY) Project IM-94-3(359)54  
1.93 miles of reconstruction of the southbound ramps along I-94/90 (Dan Ryan Expressway) from 31st Street to 39th Street and temporary shoulders from 31st Street to 47th Street in Chicago; includes 16,061 cu yds earth excavation; 11,050 cu yds removal and disposal of unsuitable material; 704 cu yds porous granular embankment; 22,207 sq yds topsoil; 4.75 acres seeding; 8,796 sq yds subbase granular material; 2,394 sq yds stabilized subbase; 3,777 sq yds concrete base course; 2,394 sq yds concrete pavement (jointed); 4,762 sq yds milling; 7,491 sq yds pavement removal; removal of 2 existing structures; 368 cu yds concrete removal; 1,581 cu yds structure excavation; 768 cu yds concrete; 9,558 sq ft rustification finish; 7,810 lbs reinforcement bars; 84,390 lbs epoxy coated reinforcement bars; 8,011 sq ft temporary sheet piling; 40 sq ft sign panel; 41,861 ft epoxy pavement marking; 4,643 ft conduit in trench; 611 ft storm sewer; 2,394 sq yds whitewashing for concrete pavement; 9,883 sq yds temporary pavement; 1,164 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 7,707 ft concrete curb and gutter; 675 sq yds concrete shoulders; 24 ft fluted kneewall; 135 ft drilled shafts in soil; mobilization; traffic control and protection. (Completion Date: December 23, 2005) (Job No. C-91-087-03) (1-77085-0002) (SUPERPAVE) (23.00% DBE)
3. Contract No. 62586 Cook County District 1  
Section (2021-922PT1,2&2122-921PT1)R-4  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-BHI-94-3(357)60  
6.08 miles of reconstruction of frontage roads, construction of retaining walls, bridge rehabilitation of the existing structure carrying 57th Street over I-94/90 and ramps all located along I-94/90 (Dan Ryan Expressway) between 57th Street and 47th Street in Chicago; includes 23,760 ft temporary fence; 29,052 cu yds earth excavation; 6,441 cu yds removal and disposal of unsuitable material; 83,784 cu yds porous granular embankment; 5,296 cu yds trench backfill; 44,634 sq yds topsoil; 9 acres seeding; 832 sq yds sodding; 10,311 sq yds stabilized subbase; 39,444 sq yds concrete pavement (jointed); 932 sq yds bridge approach pavement; 3,695 sq ft concrete sidewalk; 62,659 sq yds pavement removal; 1,619 sq yds patching; 814 sq yds bituminous shoulders, SUPERPAVE; 2,333 sq yds concrete shoulders; removal of 19 existing structures; 472 cu yds concrete removal; 99,601 cu yds structure excavation; 31,737 cu yds concrete; 1,830 sq yds bridge deck grooving; 51,131 sq ft rustification finish; erecting 692,750 lbs structural steel; 14,402 stud shear connectors; 6,098 sq ft untreated timber lagging; 5,705 ft soldier piles; 67,100 lbs reinforcement bars; 3,889,128 lbs epoxy coated reinforcement bars; 44,424 ft metal pile shells; 106 cu ft grout slurry; 5,510 ft storm sewers; 50 ft water main; 228 sq ft bridge seat sealer; 23,096 ft concrete curb and gutter; 650 ft steel plate beam guardrail; 10 traffic barrier terminals; 268 sq ft sign panel; 59,885 ft epoxy pavement marking; 17,072 ft conduit in trench; 11,441 ft trench and backfill; 11,280 ft conduit encased; maintain existing lighting system; 9,153 ft trench and backfill with screenings; 2,080 ft aerial cable; 9 luminaires; 9 steel mast arms; 18 electric manholes; 16 weeks maintain existing traffic signal installation; 7,091 ft tracer cable; 536 sq ft high performance, enhance shotcrete; 803 ft storm sewer (water main requirements); 132 pile extractions; 595 ft drilled shaft in soil; 5 ft drilled shaft in rock; 2,160 sq yds protective shield; 47,324 sq yds subbase granular material; 584 ft steel piles HP 10 X 42; 22,475 sq ft temporary sheet piling; mobilization; traffic control and protection. (Completion Date: December 13, 2005 Plus 10 Working Days) (Job No. C-91-088-03) (1-74823-0800, 1-73557-0100) (17.00% DBE)

4.	<p>In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.</p> <p>Contract No. 68387                      Marshall-Peoria Counties                      District 4  Section 3RS-4;(4,6)RS-2;5RS-1  FAP Route 318 (IL 29)  7.5 miles of 26 ft width coldmilling and resurfacing on IL Route 29 from Gail Street in Chillicothe to IL Route 17 in Sparland; includes 593 sq yds bituminous surface removal-butt joint; 151,199 sq yds bituminous surface removal; 771 sq yds patching; 722 tons aggregate shoulders; 9,816 tons bituminous concrete surface course, SUPERPAVE, Mix D; 2,941 tons bituminous concrete surface course, SUPERPAVE, (low esal); 17,040 ft epoxy pavement marking line; 95,537 ft paint pavement marking line; 613 raised reflective pavement marker; 912 raised reflective pavement marker removals; mobilization; traffic control and protection. (35 Working Days) (Job No. C-94-030-04) (4-14090-0300) (SUPERPAVE) (8.00% DBE)</p>
5.	<p>In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.</p> <p>Contract No. 68388                      Warren County                      District 4  Section 4RS-3  FAP Route 313 (US 34)  2.1 miles of 41' width bituminous overlay on U.S. Route 34 from 1 mile east of Kirkwood to 2 miles west of U.S. Route 67 south of Monmouth; includes 213 sq yds bituminous surface removal-butt joint; 36 sq yds temporary ramp; 53 tons incidental bituminous surfacing; 39,834 sq yds bituminous surface removal; 369 sq yds class D patches; 417 tons aggregate shoulders; 3,369 ft short-term pavement marking; 27,007 ft temporary pavement marking; 374 sq ft work zone pavement marking removal; 27,007 ft paint pavement marking; 140 raised reflective pavement markers; 3,354 tons bituminous concrete surface course, SUPERPAVE, MIX D; mobilization; traffic control and protection. (15 Working Days) (Job No. C-94-031-04) (4-50401-1008) (SUPERPAVE) (3.00% DBE)</p>
6.	<p>Contract No. 72068                      Hancock County                      District 6  Section 34-3(3HB)  FAP Route 315/302 (US 136/IL 336) Project ACNHF-000S(443)  5.32 miles of grading and new construction of 2 @ 24' and variable width pavement new interchange and construction of a 202'-6" back to back abutments, precast, prestressed reinforced concrete, I-beam bridge carrying U.S. Route 136/T.R. 186 over IL Route 336, all located from 3.0 miles south of Carthage to 2.0 miles east of Carthage; includes 184,349 cu yds earth excavation; 9.7 acres tree removal; 1,440 units tree removal; 33,284 tons subbase granular material; 887,172 cu yds borrow excavation; 300 cu yds trench backfill; 65,712 cu yds topsoil; 162 acres seeding; 20 acres interseeding; 19,219 tons stone dumped riprap; 289,162 sq yds processing lime modified soils; 9,269 tons aggregate base course; 1,717 sq yds preparation of base; 23 tons aggregate base repair; 4,827 tons aggregate surface course; 440 sq yds bridge approach pavement; 18,580 sq yds milling; 36,649 sq yds pavement removal; 692 sq yds patching; 24,985 tons aggregate shoulders; 85,888 sq yds bituminous shoulders, SUPERPAVE; removal of 5 existing structures; 648 cu yds concrete; 1,283 sq yds bridge deck grooving; 2,010 ft precast, prestressed concrete I-beams; 121 lbs reinforcement bars; 130,900 lbs epoxy coated reinforcement bars; 3,382 ft metal pile shells; 1,963 ft precast concrete box culvert; 552 ft water service line; 1,309 ft concrete curb and gutter; 35,000 ft exploration trench; 525 ft steel plate beam guardrail; 12 traffic barrier terminals; 83,923 ft shoulder rumble strip; 4,833 sq ft sign panel; 174,837 ft polyurea pavement marking; 10,540 ft trench and backfill; 11,030 ft unit duct; 1,900 ft aerial cable; 47 luminaires; 29 steel light poles; 8,900 cu yds earth excavation (rockfill); 9,860 sq yds bituminous base course, SUPERPAVE; 2,222 sq yds bituminous base course widening, SUPERPAVE; 183,785 sq yds bituminous concrete pavement (full-depth) SUPERPAVE; 6,129 tons bituminous concrete binder and surface course, SUPERPAVE, MIX C; 2,297 ft concrete curb and gutter; 15,900 sq yds biaxial geogrid; removal of 19 buildings; 5,000 tons rockfill-embankment; 2,250 tons rockfill-foundation; 12,500 tons rockfill-subgrade; sealing 6 abandoned water wells; 416 ft sanitary sewer; mobilization; traffic control and protection. (Completion Date: November 01, 2006) (Job No. C-96-507-05) (6-66000-0100) (10.00% DBE)</p>
7.	<p>In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.</p> <p>Contract No. 72907                      Logan County                      District 6  Section 110RS-4,111RS  FAS Route 1774 (OLD IL 121)  2.10 miles of 26 ft width milling and bituminous concrete surface on Old IL Route 121 from 2.0 miles south of Bell Station to just north of Hartsburg; includes 102 sq yds preparation of base; 33,225 sq yds milling; 416 sq yds patching; 922 tons aggregate shoulders; 24,225 ft paint pavement marking; 4,186 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; mobilization; traffic control and protection. (30 Working Days) (Job No. C-96-002-05) (0-00845-6004) (SUPERPAVE) (4.00% DBE)</p>

8. Contract No. 72918 Adams County District 6  
Section 53RS-8  
FAP Route 502 (IL 57)  
0.25 mile of 52' to 60' width milling and bituminous concrete surface on IL Route 57 in Quincy; includes 10,202 sq yds milling; 200 sq yds patching; 9,340 ft thermoplastic pavement marking; 857 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, MIX D; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-004-05) (0-00845-6003) (SUPERPAVE) (0.00% DBE)
9. Contract No. 72929 Logan County District 6  
Section (20,21)Q-1;22Q-4  
FAS Route 1773 (FR I-55 WEST)  
2.63 miles of bituminous surface treatment (oil and chip) and leveling binder on FAS Route 1773 (FR I-55 W) from 3.3 miles northeast of I-55 to Arch Street in Atlanta; includes 14 sq yds temporary ramp; 380 sq yds patching; 3,470 ft paint pavement marking; 14,795 gals bituminous materials (cover & seal coats); 555 tons seal coat aggregate; 1,553 tons leveling binder (machine method), SUPERPAVE; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-006-05) (0-00845-6027) (SUPERPAVE) (0.00% DBE)
10. Contract No. 72930 Schuyler County District 6  
Section (45,46)Q  
FAS Route 2582 (OLD US 67)  
6.21 miles of 18 ft width bituminous surface treatment and binder on Old U.S. Route 67 from 2.0 miles east of U.S. Route 67 at Rushville to 0.7 mile north of IL Route 100; includes 28 sq yds temporary ramp; 660 sq yds pavement patching; 65,607 sq yds bituminous surface treatment (preventative maintenance); 660 tons bituminous concrete binder course, SUPERPAVE; 30,250 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-007-05) (0-00845-6015) (SUPERPAVE) (0.00% DBE)
11. Contract No. 83684 Cook County District 1  
Section 96-00075-00-RS (LAGRANGE)  
FAU Route 3782 (HILLGROVE AVENUE) Project M-CMM-7003(604)  
Project consists of 0.77 mile of pavement reconstruction, sidewalk construction, drainage improvements and lighting on Hillgrove Avenue from Gilbert Avenue to Kensington Avenue in LaGrange; includes 65 trees; 300 shrubs; 665 tree removals; 135 kg fertilizer nutrients; 7,839 sq m subbase granular material; 5,668 m tons bituminous concrete binder course; 2,636 m tons bituminous concrete surface course; 405 sq m PCC driveway; 285 m storm sewers, rubber gasket; 426 m pipe underdrains; 4,881 m thermoplastic pavement marking; 31,270 m electric cable in conduit; (120 Working Days) (Job No. C-91-163-98) (1-10083-0000) (11.00% DBE)
12. Contract No. 83750 Lake County District 1  
Section 00-00113-13-CH  
FAU Route 191 (FAIRFIELD ROAD) Project M-TE-D1(569)  
0.45 mile intersection reconstruction of Fairfield Road and Ivanhoe Road near Wauconda consisting of pavement widening turn lanes, pedestrian underpass, minor landscaping and removal and replacement of drainage and curb and gutter; includes 878 units tree removal; 9,685 cu yds earth excavation; 15,780 sq yds topsoil; 3.75 acre seeding; 676 lbs fertilizer nutrient; 945 sq yds aggregate base course; 12,636 sq yds pavement removal; 105,890 lbs reinforcement bars; 1,765 ft storm sewers; 4,812 ft pipe underdrains; 2,319 ft concrete curb and gutter; 1,126 ft chain link fence; 43,079 ft pavement marking; 229 ft temporary concrete barrier; 1,598 ft electric cable in conduit; 18 underpass luminaires; 7,656 tons bituminous concrete, SUPERPAVE; 2 trainees; traffic control and protection. (60 Working Days) (Job No. C-91-406-00) (1-10087-0000) (SUPERPAVE) (12.00% DBE)
13. Contract No. 83758 DuPage County District 1  
Section 02-00072-00-RS (BARTLETT)  
FAU Route 1396 & FAU Route 2405 (SCHICK RD.&PROSPECT AVE.) Project M-8003(429)  
Removal of existing bituminous surface, resurfacing, pavement marking, curb and gutter, sidewalks and minor landscaping, 0.38 mile on Schick Road from Gerber Road to the Chicago Central Railroad and 0.49 mile on Prospect Avenue from Devon Avenue to Wilcox Avenue all in Bartlett; includes 260 sq yds top soil and sodding; 210 sq yds subbase granular material; 3,360 gals bituminous material; 17,095 sq yds bituminous surface removal; 765 sq yds pavement patching; 16,755 sq yds area reflective crack control; 480 ft combination concrete curb and gutter removal and replacement; 721 sq ft thermoplastic pavement marking; 11,430 ft thermoplastic pavement marking; 2,100 sq ft sidewalk removal and replacement; 259 raised reflective pavement markers; 1,580 tons bituminous concrete surface, SUPERPAVE; 1,925 tons bituminous concrete binder, SUPERPAVE; 660 tons leveling binder; 15 units watering; traffic control and protection. (Completion Date: October 15, 2004) (Job No. C-91-279-04) (1-10977-0000) (SUPERPAVE) (12.00% DBE)

14. Contract No. 83761 McHenry County District 1  
Section 04-00018-00-RS (FOX RIVER GROVE)  
FAU Route 3878 & FAU Route 3879 (ALGONQUIN RD&PLUM TREE RD) Project M-8003(430)  
Project consists of bituminous resurfacing, shoulder repair, pavement markings and all other incidental and collateral work necessary to complete the improvement on Algonquin Road from Lexington Drive to U.S. Route 14 and Crescent Parkway to Elder Lane, Plum Tree Road from Old Hunt Road east to Village limits in Fox River Grove; includes 1,801 gals bituminous materials; 1,649 sq yds Class D patches; 1,000 tons bituminous concrete surface course; 285 tons bituminous concrete binder course; 519 tons polymerized leveling binder; 11,556 ft thermoplastic pavement marking; railroad protective liability insurance. (20 Working Days) (Job No. C-91-300-04) (1-10975-0000) (12.00% DBE)
15. Contract No. 83764 Cook County District 1  
Section 04-00045-00-RS (FLOSSMOOR)  
FAU Route 1626 (FLOSSMOOR ROAD) Project M-8003(434)  
Project consists of 0.53 mile of resurfacing, curb and gutter replacement, sidewalk replacement and the replacement of existing pozzolamic subbase with bituminous base course on Flossmoor Road from Governors Highway to Sterling Avenue in Flossmoor; includes 3,914 sq yds bituminous base course; 959 tons bituminous concrete surface course; 450 tons bituminous concrete binder course; 7,506 sq yds bituminous surface removal; 3,914 sq yds pavement removal; 11,422 sq yds area reflective crack control treatment; 25 manholes to be adjusted; 948 ft combination concrete curb and gutter; 6,317 ft paint pavement marking. (30 Working Days) (Job No. C-91-304-04) (1-10973-0000) (12.00% DBE)
16. Contract No. 83767 DuPage County District 1  
Section 04-00078-00-FP (VILLA PARK)  
FAU Route 2651 (SOUTH ARDMORE AVENUE) Project M-8003(435)  
1.01 miles milling, full depth patching, bituminous resurfacing, replace curb and gutter and pavement marking on FAU Route 2651 (South Ardmore Avenue) from Madison Street to St. Charles Road in Villa Park; includes 1,200 gals bituminous materials; 1,100 tons leveling binder; 2,200 tons bituminous concrete surface, SUPERPAVE; 19,200 sq yds bituminous surface removal; 200 ft remove and replace combination curb and gutter; 200 sq yds full depth pavement patching; 19,000 sq yds area reflective crack control treatment; 1,200 ft short-term pavement marking; 120 sq ft polyurea pavement marking; 6,520 ft polyurea pavement marking; 600 ft detector loop replacement; 65 frame & grate to be adjusted; 20 frame and lids; traffic control and protection. (30 Working Days) (Job No. C-91-310-04) (1-10972-0000) (SUPERPAVE) (12.00% DBE)
17. Contract No. 87258 McLean County District 3  
Section 00-00205-00-RP (NORMAL)  
FAU Route 6375 (NORTHTOWN ROAD) Project ACM-5227(38)  
1.2 miles of pavement construction on Northtown Road from Towanda Avenue to Pipeline Road including curb and gutter and storm sewer construction in Normal; includes 111 units tree removal; 19,568 cu yds earth excavation; 6,000 ft exploration trench; 1,440 lbs nitrogen, phosphorus and potassium fertilizer; 34,200 sq yds processing lime modified soils; 1,650 tons aggregate base course; 42,790 sq ft PCC sidewalk; 11 cu yds concrete structures; 1,670 lbs reinforcement bars; 6,915 ft storm sewers; 11,190 ft combination concrete curb and gutter; 20,635 ft pavement marking; 220 ft electric cable; 33,200 sq yds PCC pavement; 559 ft pipe culvert removal; 390 tons bituminous concrete surface course, SUPERPAVE; 2 trainees; 61 trees and shrubs. (120 Working Days) (Job No. C-93-056-00) (3-10031-0000) (SUPERPAVE) (6.00% DBE)
18. Contract No. 87279 LaSalle County District 3  
Section 04-00154-00-RS/04-00155-00-RS (OTTAWA)  
FAU Route 6028/FAU Route 6023 (OTTAWA AVE./W.MARQUETTE ST) Project ACM-5052(22)  
Project consists of bituminous surface removal, bituminous resurfacing, constructing bituminous shoulders, installing curb and gutter to improve drainage and other related and miscellaneous construction on West Marquette Street from Chestnut Street to Ottawa Avenue and on Ottawa Avenue from Boyce Memorial Drive extending westerly to the city limits; includes 316 cu yds earth excavation. 25 cu yds trench backfill; 108 lbs fertilizer nutrients; 20 tons aggregate base course; 2,582 gals bituminous materials; 35 tons aggregate (prime coat); 9,988 sq yds bituminous surface removal; 165 tons aggregate shoulders; 6 inlets; 3,750 ft thermoplastic pavement marking; 1,376 tons bituminous concrete surface course; 1,114 tons leveling binder. (30 Working Days) (Job No. C-93-086-04) (3-10047-0000) (5.00% DBE)
19. Contract No. 87285 Kankakee County District 3  
Section 02-00062-02-RS  
FAS Route 1299 (CH 7) Project ACRS-1299(108)  
Construction consists of 3.05 miles of bituminous concrete resurfacing with aggregate shoulders on FAS Route 1299, County Highway 7 from County Highway 9 northerly to the Will County Line; includes 2,568 tons bituminous concrete surface course; 2,002 tons leveling binder (machine method); 103 tons aggregate base course; 2,036 tons aggregate shoulders; traffic control and protection. (10 Working Days) (Job No. C-93-082-04) (3-10160-0000) (4.00% DBE)

20. Contract No. 87286 Kankakee County District 3  
Section 02-00104-01-RS  
FAS Route 1322 (CH 37) Project ACRS-1322(122)  
Construction consists of 4.05 miles of bituminous concrete resurfacing with aggregate shoulders on FAS Route 1322, County Highway 37 extending from 7000 W to 3000 W to Chebanse; includes 4,035 tons bituminous concrete surface course; 2,660 tons leveling binder (machine method); 61 tons aggregate base course; 2,595 tons aggregate shoulders; traffic control and protection. (15 Working Days) (Job No. C-93-083-04) (3-10152-0000) (8.00% DBE)
21. Contract No. 89317 Peoria County District 4  
Section 01-00237-04-RP (PEORIA)  
FAU Route 6653 (FORREST HILL AVENUE) Project ACM-5093(115)  
1.074 km concrete pavement with integral curb, storm sewer, PCC sidewalk, PCC driveway pavement, various removal items, stripping, traffic signals and lighting on West Forrest Hill Avenue from east of Sterling Avenue to west of Gale Avenue in Peoria; includes 423 tree removals; 69 inlets; 7,938 sq m sodding; 923 m tons aggregate; 1,953 sq m PCC driveway pavement; 3,710 sq m PCC sidewalk; 19,767 sq m pavement removal; 2,230.2 m storm sewers; 665.6 m storm sewer removal; 12,423 m pavement marking; 873.8 m temporary concrete barrier; 24,633 sq m PCC pavement with integral curb; 31,744.4 m conduit in trench; 3,260.3 m trench and backfill; 8,128.7 m electric cable in conduit; 47 signal heads; 313 m tons bituminous, SUPERPAVE; 160 m temporary fence; traffic control and protection. (Completion Date: October 28, 2005) (Job No. C-94-104-03) (4-10108-0000) (SUPERPAVE) (15.00% DBE)
22. Contract No. 89328 Knox County District 4  
Section 02-00500-18-RS (GALESBURG)  
FAU Route 6800 (WEST MAIN STREET) Project ACM-5025(35)  
Construction consists of 0.063 mile resurfacing, sidewalk, curb and gutter on FAU Route 6800, Main Street from Edwards Avenue to Olive Street in the City of Galesburg; includes 1,177 sq ft PCC sidewalk; 14,788 sq yds bituminous surface removal; 2,686 ft combination curb and gutter removal; 9 inlets to be adjusted; 2,686 ft combination concrete curb and gutter; 6,550 ft thermoplastic pavement marking-line; 1,755 tons bituminous concrete surface course; 877 tons leveling binder; 581 sq yds bituminous concrete base course widening; traffic control and protection. (40 Working Days) (Job No. C-94-045-04) (4-10162-0000) (9.00% DBE)
23. Contract No. 93379 Pike County District 6  
Section 02-00078-00-RP  
FAS Route 602 (CH 21) Project ACSR-602(104)  
Construction consists of 0.518 mile of widening and resurfacing FAS Route 602 from IL Route 104 south 0.5 mile to Central Stone Quarry entrance; includes 1,408 cu yds earth excavation; 1.6 acres seeding; 51 temporary ditch checks; 11 inlets and pipe protection; 78 tons aggregate base course; 1,411 sq yds preparation of base; 49 tons aggregate, surface course; 643 sq yds PCC pavement 8"; 579 tons aggregate shoulders; 240 ft pipe culverts; 318 ft storm sewers; 6 manholes; 604 ft combination concrete curb and gutter; 9,457 ft paint pavement marking-line 4"; 594 tons bituminous concrete surface course; 2,565 tons bituminous concrete binder course; construction layout; traffic control complete. (30 Working Days) (Job No. C-96-222-04) (6-10166-0000) (4.00% DBE)
24. Contract No. 93381 Cass County District 6  
Section 97-00061-00-RS  
FAS Route 580 (CH 9) Project ACSR-580(103)  
Construction consists of 1.188 miles of bituminous concrete resurfacing with aggregate and bituminous shoulders on FAS Route 580, County Highway 9 from the Morgan/Cass County Line to 190 feet west of County Highway 8 in Arenzville; includes 64 tons aggregate surface course; 781 tons aggregate shoulders; 125 tons bituminous shoulders, SUPERPAVE; 775 ft steel plate beam guardrail; 16 traffic barrier terminals; 23,755 ft temporary pavement marking - line 4"; 23,755 ft thermoplastic pavement marking - line 4"; 1,441 tons bituminous concrete surface course; 2,022 tons bituminous concrete binder course; construction layout; traffic control complete. (20 Working Days) (Job No. C-96-221-99) (6-10131-0000) (5.00% DBE)
25. Contract No. 95412 White County District 7  
Section 00-00093-00-RS  
FAS Route 884 (CH 1) Project ACRS-884(104)  
Construction consists of repairing the existing base, placing a 20' asphalt surface with aggregate shoulders on FAS Route 884, County Highway 1 from 5 miles north of Carmi to 2 miles north of Carmi; includes 2,673 tons leveling binder (machine method); 2,593 tons bituminous concrete binder course; 34,427 sq yds bituminous surface removal; 1,996 tons aggregate shoulders; 43,725 ft paint pavement marking-line 4"; 418 tons pavement removal and replacement. (25 Working Days) (Job No. C-97-083-04) (7-10070-0000) (0.00% DBE)

26. Contract No. 97226 St. Clair County District 8  
Section 97-00009-00-FP (SAUGET)  
FAU Route 9212 (SAUGET BUSINESS BOULEVARD) Project HPD-1443(2)  
0.91 mile of new roadway including excavating, grading, paving, shoulders, drainage ditch, traffic control and pavement marking for Sauget Business Boulevard south of IL Route 64 between IL Route 3 and I-255 in Sauget; includes 31,689 cu yds earth excavation; 8.7 acres seeding; 820 sq yds stone riprap; 33,650 sq yds processing lime modified soils; 463 tons aggregate base course; 21,490 sq yds bituminous base course, SUPERPAVE; 2,854 tons bituminous concrete surface, SUPERPAVE; 530 sq yds PCC driveway pavement; 4,380 sq yds pavement and driveway removal; 9,915 sq yds bituminous shoulders, SUPERPAVE; 286 ft precast concrete box culvert; 367 ft pipe culverts; 806 ft pipe culvert removal; 150 ft combination concrete curb and gutter; 36,875 ft pavement marking; traffic control and protection. (100 Working Days) (Job No. C-98-089-97) (8-89274-0100) (SUPERPAVE) (12.00% DBE)
27. Contract No. 99147 Jackson County District 9  
Section 99-00100-00-FP (CARBONDALE)  
FAU Route 9715 (NEW ERA ROAD) Project HPD-1363(3)  
Construction consists of 1.92 miles of widening and realignment with bituminous resurfacing, drainage, curb & gutter, storm sewers and inlets on FAU Route 9715, New Era Road from state Route 13 to Gleen Road in Carbondale; includes 3,187 tons bituminous concrete surface course; 4,969 tons bituminous concrete base course; 730 tree removal; 8,405 cu yds earth excavation; 4,209 cu yds furnished excavation; 2,317 cu yds trench backfill; 5.8 acre seeding; 4,379 ft perimeter erosion barrier; 14,907 tons aggregate base course; 7,741 ft storm sewer 12"-36"; 80 inlets; 19,476 ft combination concrete curb & gutter; 1,027 ft woven wire fence; 22,290 ft thermoplastic pavement marking line 4". (250 Working Days) (Job No. C-99-029-01) (9-99500-0000) (8.00% DBE)
28. Contract No. 99187 Franklin County District 9  
Section 98-00049-00-RP (WEST FRANKFORT)  
FAU Route 9477 (CLEVELAND STREET) Project ACM-5071(10)  
0.32 mile of reconstruction of PCC pavement, integral curb and gutter, new storm sewer, sidewalks and miscellaneous work required to complete the project on Cleveland Street from just east of the intersection with Van Buren Street extending easterly to the intersection with Cherry Road in West Frankfort; includes 737 tree removal; 1,296.30 cu yds trench backfill; 30 tons stone dumped riprap; 1,600 tons subbase granular material; 100 lbs reinforcement bars; 3,249 ft storm sewers; 792 ft storm sewer removal; 10 manholes; 631 ft paint pavement marking; 6,025 sq yds PCC pavement; 2,200 ft detection wire. (105 Working Days) (Job No. C-99-508-03) (9-10128-0000) (6.00% DBE)
29. Contract No. 99200 Perry County District 9  
Section 02-00105-00-RS  
FAS Route 1881 (CH 7) Project ACRS-1881(113)  
Construction consists of 1.35 miles of bituminous concrete binder and surface courses with aggregate shoulders on FAS Route 1881, County Highway 7 from 3 miles east of DuQuoin to Franklin County Line; includes 1,575 tons bituminous concrete surface course; 1,600 tons bituminous concrete binder course; 900 tons aggregate shoulders; 22,518 feet paint pavement marking-line 4". (10 Working Days) (Job No. C-99-527-04) (9-10175-0000) (0.00% DBE)
30. Contract No. 99201 Jackson County District 9  
Section 02-00132-00-RS  
FAS Route 1916 (ELKVILLE ROAD) Project ACRS-1916(111)  
Construction consists of bituminous concrete resurfacing of FAS Route 1916, Elkhaville Road, from the Village of Elkhaville west 13,262 feet; includes 3,900 tons bituminous concrete surface course; railroad protective liability insurance; 2,460 sq yds bituminous surface removal; 33,130 ft paint pavement marking-line 4"; 191 raised reflective pavement markers. (20 Working Days) (Job No. C-99-519-03) (9-10145-0000) (3.00% DBE)  
[SEE MORE PAVEMENT](#)

#### **BRIDGE SECTION**

31. Contract No. 64A34 Henry County District 2  
Section D2 MRS 2005-1  
FAS Route 1192 (ATKINSON ROAD)  
1.8 miles of intermittent bituminous surfacing on Atkinson Road between U.S. Route 6 and IL Route 92 in the town of Atkinson; includes 439 sq yds bituminous surface removal-butt joint; 74 sq yds temporary ramp 41 tons incidental bituminous surfacing; 792 tons aggregate shoulders; 2,972 ft short term pavement marking; 331 sq ft work zone pavement marking removal; 49,468 ft paint pavement marking; 1,485 tons bituminous concrete surface course, SUPERPAVE, Mix C; 20 tons leveling binder, hand method, SUPERPAVE; 1,189 tons leveling binder, machine method, SUPERPAVE; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-122-04) (0-00844-2047) (SUPERPAVE) (0.00% DBE)

In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.			
32.	Contract No. 62727 Section 26HB-1-R FAI Route 55 (I-55)	Will County	District 1
0.25 mile of approach pavement removal and replacement, bridge raising, beam replacement and ramp resurfacing for the existing structure carrying IL Route 59 over I-55 in Shorewood; includes 9 cu yds earth excavation; 110 cu yds furnished excavation; 0.85 acre seeding; 5,478 sq yds sodding; 215 sq yds bridge approach pavement; 3,685 sq yds milling; 230 sq yds patching; 480 sq yds aggregate shoulders; 19.3 cu yds concrete removal; 12 removal of existing bearings; 32.3 cu yds concrete; 37,430 lbs structural steel; 4,200 lbs epoxy coated reinforcement bars; 280 sq ft bridge seat sealer; 190 ft concrete curb; 1,500 ft concrete gutter; 2,030 ft thermoplastic pavement marking; 11.2 cu ft polymer concrete; 900 sq yds protective shield (permanent); 1,545 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; temporary shoring and cribbing; temporary slab support system; jacking existing superstructure; 9 sq ft formed concrete repair; mobilization; traffic control and protection. (Completion Date: November 12, 2004 Plus 05 Working Days) (Job No. C-91-155-04) (0-00845-1027) (SUPERPAVE) (11.00% DBE)			
In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.			
33.	Contract No. 66453 Section (36B,CS)I FAP Route 653 (IL 18 (EB))	LaSalle County	District 3
Improvements consist of repairs to the existing superstructure carrying Illinois Route 18 over the Vermillion River in Streator; includes 190 sq yds stone riprap; 190 sq yds filter fabric for use with riprap; 203 sq ft rubbed finish; 8 elastomeric bearing assembly; 8 jack and remove existing bearings; 80 ft silicone joint sealer; 203 sq ft formed concrete repair; 1,850 lbs furnishing and erecting structural steel; 21 sq yds deck slab repair (full depth); 780 lbs reinforcement bars, epoxy coated; 227 sq yds deck slab repair (partial); mobilization; traffic control and protection. (45 Working Days) (Job No. C-93-071-04) (0-00845-3002) (0.00% DBE)			
34.	Contract No. 66497 Section (1-HB-1)BR FAU Route 6087 (7TH STREET)	LaSalle County	District 3
Rehabilitation of the structure carrying 7th Street over IL Route 251 in Peru; includes 19 cu yds concrete removal; 19 cu yds concrete; 4,950 lbs structural steel removal; 2,500 lbs reinforcement bars, epoxy coated; 88 ft silicone joint sealer; 154 sq ft high performance-enhanced shotcrete; 368 sq yds concrete bridge deck scarification; 67 sq yds bituminous pavement replacement; 368 sq yds bridge deck thin polymer overlay; 42 sq yds deck slab repair; 46 sq yds protective shield; 42 ft saw cut and seal new joints; mobilization; traffic control and protection. (30 Working Days) (Job No. C-93-140-04) (0-00845-3003) (SUPERPAVE) (0.00% DBE)			
35.	Contract No. 66498 Section (105BR-1)RS FAP Route 68 (IL 23)	Livingston County	District 3
Removal and replacement of the existing bituminous wearing surface, waterproofing and keyway repair of the structure carrying IL Route 23 over Wolf Creek, 0.67 mile north of Interstate 55 (near Pontiac); includes 412 sq yds bituminous concrete removal (deck); 412 sq yds waterproofing membrane system; 58 tons bituminous concrete surface course, SUPERPAVE, Mix C; 412 sq yds waterproofing membrane special; 48 bearing pad adjustments; 958 ft keyway repair; mobilization; traffic control and protection. (15 Working Days) (Job No. C-93-141-04) (0-00845-3004) (SUPERPAVE) (0.00% DBE)			
In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.			
36.	Contract No. 68407 Section (105B)I FAP Route 542 (IL 61)	McDonough County	District 4
Removal and replacement of the damaged deck beams on the structure carrying IL Route 61 over the LaMoine River, 1 mile south of Colmar; includes 209 cu yds earth excavation (widening); 1,252 sq yds bituminous base course; 1,550 sq ft concrete deck beams; 221 sq yds waterproofing membrane system; 912 ft concrete mortar fairing course; 253 sq ft work zone pavement marking removal; 37 tons bituminous surface course, SUPERPAVE, Mix D; 1,582 sq ft removal of existing concrete deck beams; 7 asbestos bearing pad removal; mobilization; traffic control and protection. (20 Working Days) (Job No. C-94-083-04) (0-01044-4002) (SUPERPAVE) (0.00% DBE)			



In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.

37. Contract No. 76755 Clinton County District 8  
Section 14-14HB-I  
FAP Route 327 (US 50)  
Rehabilitation of the structure carrying St. Rose Road over U.S. Route 50 located 7 miles east of Trenton; includes 22 tons incidental bituminous surfacing; 220 sq yds bituminous surface removal; 941 sq yds bridge deck grooving; 350 ft guardrail removal; 1,100 ft remove and re-erect steel plate beam guardrail; 1,345 ft paint pavement marking line; 214 sq ft pavement marking removal; 1,006 sq yds bridge deck microsilica concrete overlay; 1,006 sq yds concrete bridge deck scarification; 47 sq yds deck slab repair (partial); 514 ft retrofit concrete parapet; mobilization; traffic control and protection. (40 Working Days) (Job No. C-98-029-04) (0-00845-8003) (5.00% DBE)
38. Contract No. 83701 Cook County District 1  
Section 89-00047-01-GS (FRANKLIN PARK)  
FAU Route 1376 (GRAND AVENUE) Project HD-CMM-M-8003(148)  
Project consists of constructing a new grade separated structure carrying three tracks over Grand Avenue, relocating two railroad tracks, roadway reconstruction, removal of pavement, sewers and water lines, removal of buildings and asbestos, construct a temporary road runaround, new storm sewers, sanitary sewers and water lines, PCC curb and gutter, sidewalks, traffic signals, lighting and landscaping at Grand Avenue/Canadian National Railway in Franklin Park; includes 313 trees removed; 59,089 cu yds earth excavation; 17,313 cu yds borrow excavation; 10,553 sq yds aggregate base course; 35,773 sq yds PCC base course; 4,094 sq yds PCC pavement; 46,887 sq ft PCC sidewalk; 2,870 tons bituminous surface course, SUPERPAVE, Mix D, N 50; 1,103 tons polymerized bituminous surface course, SUPERPAVE, Mix F, N 90; 3,624 tons bituminous binder course, SUPERPAVE, IL-19, N 50; 1,418 tons polymerized binder course, SUPERPAVE, IL-19, N 90; 31,325 sq yds pavement removal; 9,473 ft curb and gutter removal; 26,206 ft sidewalk removal; 1,025 cu yds concrete structures; 1,580 cu yds structure excavation; 640,000 lbs furnish and erect structural steel; 857,656 lbs reinforcement bars; 117,600 lbs reinforcement bars, epoxy coated; 21,850 sq ft temporary sheet piling; 310 ft precast concrete box culvert 12' X 6'; 7,371 ft storm sewers; 1,371 ft 12" water main; 429 ft 2" water service line; 5,850 ft pipe underdrains, fabric lined; 63 catch basins; 15,629 ft combination concrete curb and gutter; 50 ft steel plate beam guardrail; 7,174 cu yds special waste disposal; 2,000 ft temporary concrete barrier; 24,010 ft thermoplastic pavement marking line; 2,522 ft conduit in trench, galvanized steel; 972 ft conduit pushed, galvanized steel; 684 ft conduit embedded in structure, PVC; 11,549 ft trench and backfill for electrical work; 10,921 ft unit duct, polyethylene; 14,587 ft electric cable in conduit; 71 luminaires, sodium vapor, horizontal mount; 71 light poles; 1,180 ft fiber optic cable in conduit; 4 steel mast arm assemblies and poles; 20 signal heads; 1,083 ft detector loop; 178 trees, balled and burlapped; 65 shrubs; 46 evergreens, balled and burlapped; 32,381 sq yds topsoil furnish and place; 5 acres seeding; 1,235 lbs fertilizer; 22,361 sq yds sodding salt tolerant; 4,969 sq yds temporary pavement; 2 buildings removed; 1,025 bar splices; 9,992 ft drilled shaft in soil; 5 removal and displacements of asbestos; 8,917 cu yds sub-ballast; 10,200 ft railroad track removal; 2,000 ft track installation. (Completion Date: October 31, 2006) (Job No. C-91-524-01) (1-10343-0000) (SUPERPAVE) (13.00% DBE)
39. Contract No. 85317 Winnebago County District 2  
Section 93-P4000-02-BT (ROCKFORD PARK DISTRICT)  
TINKER SWISS COTTAGE Project TE-D2(34)  
Construct a historic replication of a pedestrian suspension bridge over Kent Creek with approach pathways, sidewalks and pavement, including a gravel turnaround at the east end of the bridge and a flagstone sidewalk on the west all in the Tinker Swiss Cottage Museum Historic Site in Rockford; includes 225 cu yds earth excavation; 55 sq ft sidewalk removal and replacement; remove existing structure; 58.7 cu yds concrete structures; 35,400 lbs furnish and erect structural steel; 5,440 lbs reinforcement bars; 80 ft furnish steel piles; 760 ft chain link fence; 300 ft steel edging; 295 ft stone curb; 575 sq ft flagstone sidewalk; 1,180 lbs rock anchor; 115 sq yds aggregate bicycle path; 787 sq ft cut stone; 130 sq yds incidental bituminous surface; 1,875 sq ft modular concrete pavers; remove and reinstall historic landscaping; remove and reinstall rock garden; remove and reinstall 2 stone stairways; traffic control and protection. (Completion Date: June 01, 2005) (Job No. C-92-138-93) (0-00904-0000) (5.00% DBE)
40. Contract No. 85340 Lee County District 2  
Section 96-00137-00-BR (DIXON)  
FAU Route 5497 (PEORIA AVENUE) Project BRM-5018(14)  
Construction consists of a five span structure with sidewalk and bike path carrying FAU Route 5497, Peoria Avenue over Rock River in Dixon; includes 305 cu yds porous granular embankment; 382 cu yds trench backfill; removal of existing structures; 1,332 cu yds concrete structures; 1,363 cu yds concrete superstructure; 6,154 sq yds protective coating; 1,707,650 lbs furnishing and erection structural steel; 12,231 stud shear connectors; 613,130 lbs reinforcement bars, epoxy coated; 1,104 ft driving steel piles; 12 calendar months engineer's field office; 2,800 ft conduit embedded in structure; 7,400 ft electric cable in conduit; 1,692 sq ft precast modular retaining wall; 4 underwater structure excavation protections; 10 decorative style light units, twin unit complete; 3,051 bar splices; construction layout; 358 ft drilled shaft in rock 42"; 1,313 ft parapet railing; 1,000 hours trainees; 7,814 sq ft form liner parapet surfaces; mobilization. (Completion Date: December 16, 2005) (Job No. C-92-097-03) (2-20990-0100) (8.00% DBE)

41. Contract No. 85342 Bureau County District 2  
Section 04-08120-00-BR  
TR 10 Project BROS-11(66)  
This project consists of the removal of a single span truss bridge and replacing it with a three span precast, prestressed concrete deck beam bridge (21' depth) over Hickory Smith Ditch, 2 miles North of Mineral; includes 698 cu yds earth excavation; 1,600 cu yds furnished excavation; 1.13 acres seeding; 929 tons aggregate surface course; 3,049 sq ft precast, prestressed concrete deck beams (21" depth); 9,720 lbs reinforcement bars, epoxy coated; 952 ft furnishing and driving metal pile shells; 403 ft pipe culverts special. (55 Working Days) (Job No. C-92-071-04) (2-10066-0000) (5.00% DBE)
42. Contract No. 87249 Kankakee County District 3  
Section 02-00268-00-BR (KANKAKEE)  
FAU Route 6195 (FIFTH AVENUE) Project BRM-5034(14)  
Removal of existing structure and construction of a precast prestressed concrete deck beam bridge (17" depth) measuring 32' face to face of abutment over Soldier Creek in the city of Kankakee; includes 45 lbs fertilizer nutrients; 1,060 tons porous granular embankment; 564 sq yds subbase granular material; 483 sq yds bituminous base course; 1,652 sq ft PCC sidewalk; 1,577 sq ft precast prestressed concrete deck beams (17" depth); 21,240 lbs reinforcement bars, epoxy coated; 3 precast reinforced concrete flared end sections; 99 ft storm sewers; 286 ft combination concrete curb and gutter; 55 tons bituminous concrete surface course; 33 tons leveling binder (machine method); traffic control and protection. (40 Working Days) (Job No. C-93-115-03) (3-10162-0000) (10.00% DBE)
43. Contract No. 87271 Woodford County District 3  
Section 97-00091-01-BR  
FAS Route 364 (CH 13) Project RS-364(106)  
Remove box culvert carrying FAS Route 364 (CH 13) over a tributary to the West Branch of Panther Creek 2 1/2 miles south of Roanoke and replace with a single span precast, prestressed deck structure and approaches; includes 3,937 cu yds earth and channel excavation; 808 cu yds furnished excavation; 1.5 acres seeding; 405 lbs fertilizer nutrient; 1.5 acres mulch method; 150 sq yds fabric formed concrete revetment mats; 2,655 tons aggregate base; 763 tons aggregate shoulders; 1,976 gals bituminous materials; 26.5 cu yds concrete structures; 1,451 sq ft precast prestressed concrete deck beams; 2,790 lbs reinforcement bars, epoxy coated; 91 ft steel bridge rail; 442 ft furnish and drive steel piles; 136 ft pipe culverts; 350 ft steel plate beam guardrail; 8 traffic barrier terminals; 421 tons bituminous concrete surface, SUPERPAVE; 1,030 tons bituminous concrete binder, SUPERPAVE. (40 Working Days) (Job No. C-93-018-04) (3-10087-0000) (SUPERPAVE) (6.00% DBE)
44. Contract No. 87281 LaSalle County District 3  
Section 04-00620-00-BR  
FAS Route 1271 (CH 32) Project BRS-1271(108)  
Construction consists of a precast, prestressed concrete deck beam bridge, 1 @ 78'-7 7/8" on pile bent spill through abutments carrying FAS Route 1271 over Roods Creek, southwest of Newark; includes 567 cu yds furnished excavation; 1,033 sq yds topsoil furnish and place 4"; 446 tons stone dumped riprap; 160 tons incidental bituminous surfacing; 66 tons aggregate shoulders; removal of existing structures; 34.4 cu yds concrete structures; 2,640 sq ft precast, prestressed concrete deck beams; 2,640 lbs reinforcement bars, epoxy coated; 408 ft driving and filling shells; 300 ft steel plate beam guardrail; 4 traffic barrier terminals; traffic control and protection. (50 Working Days) (Job No. C-93-093-04) (3-10045-0000) (5.00% DBE)
45. Contract No. 87291 Ford County District 3  
Section 03-00103-00-BR  
FAS Route 335 (CH 2) Project BRS-335(112)  
Removal of existing structure and construction of a three span continuous reinforced concrete slab bridge to carry CH 2 over a tributary to Big Fur drainage ditch; includes 495 cu yds earth and channel excavation; 210 cu yds furnished excavation; 50 tons porous granular embankment; 210 tons dumped riprap; 610 tons aggregate base course; 320 gals bituminous materials; 292 sq yds protective coat; 34,000 lbs reinforcement bars; 880 ft furnishing and driving metal pile shells; 310 ft pipe drains; 70 tons bituminous concrete surface course; 95 tons bituminous concrete binder course; 8 traffic barrier terminals. (45 Working Days) (Job No. C-93-062-04) (3-10041-0000) (7.00% DBE)
46. Contract No. 89297 Tazewell County District 4  
Section 02-17138-00-BR  
TR 173 (SPRING LAKE ROAD) Project BROS-179(22)  
The project consists of the removal of an existing bridge and replace with a single span, precast, prestressed, concrete deck beam bridge and incidental related work on Spring Lake Road over Hickory Grove Drainage Ditch two miles northeast of Manito; includes 60 cu yds porous granular embankment; 21.6 lbs fertilizer nutrients; 90 sq yds stone riprap; 282 sq yds aggregate base course; 7.5 tons aggregate surface course; 26.7 tons aggregate shoulders; 1,197.5 sq ft precast concrete bridge slab; 2,730 lbs furnishing and erecting structural steel; 4,580 lbs reinforcement bars, epoxy coated; 54 tons bituminous concrete surface course; 58 tons bituminous concrete binder course; (30 Working Days) (Job No. C-94-083-03) (4-10180-0000) (9.00% DBE)

47. Contract No. 89320 Knox County District 4  
Section 99-00451-07-BR (GALESBURG)  
CHERRY STREET Project BRM-5025(34)  
Remove existing bridge superstructure and replace with precast, prestressed concrete deck beams and bituminous concrete overlay, modifications to existing abutments and 0.03 mile approach roadway on Cherry Street over Cedar Creek in Galesburg; includes 9.9 cu yds trench backfill; 96 sq yds PCC driveway pavement removal and replacement; 657 sq ft PCC sidewalk; 257 ft combination curb and gutter removal and replacement; 63.7 cu yds structure excavation; 59.9 cu yds concrete structures; 49.8 cu yds concrete superstructure; 2,421 sq ft precast, prestressed concrete deck beams; 12,330 lbs reinforcement bars; 101 ft pipe handrail; 284 expansion bolts; 38 ft storm sewers; 5 temporary accesses; 201.8 tons bituminous concrete, SUPERPAVE; 225 sq ft remove and relay brick sidewalk; 100 cu yds controlled low-strength material; 20 sq yds slope wall repair. (30 Working Days) (Job No. C-94-106-03) (4-10010-0000) (SUPERPAVE) (8.00% DBE)
48. Contract No. 93380 Adams County District 6  
Section 04-00185-00-BR  
FAS Route 1588 (CH 48) Project ACRS-1588(106)  
Project consists of the removal and replacement of the reinforced concrete bridge deck on the existing steel beams and necessary bridge approach adjustments, located 6.5 miles northeast of Liberty over McKee Creek; includes 65 gals bituminous materials (prime coat); 63 ft preformed joint seal; 148.6 cu yds concrete superstructure; 12 elastomeric bearing assemblies; 34,370 lbs reinforcement bars, epoxy coated; 200 ft steel plate beam guardrail; 4 traffic barrier terminals; 75 tons bituminous concrete surface course, SUPERPAVE; 15 tons leveling binder (machine method); traffic control and protection. (55 Working Days) (Job No. C-96-228-04) (6-10201-0000) (SUPERPAVE) (10.00% DBE)
49. Contract No. 95384 Jasper County District 7  
Section 00-10125-00-BR  
TR 139 Project BROS-79(32)  
Construction consists of a three span, 3 @ 72'-9" precast, prestressed concrete deck beam bridge carrying TR 139 over Embarras River, 4 miles north of Newton; includes 18 trees, 1 3/4" caliper, balled and burlapped; 8 traffic barrier terminals; 14 setting piles in rock; 240 tree removals; 715 cu yds earth and channel excavation; 1,000 cu yds furnished excavation; 430 tons granular backfill; 510 tons stone dumped riprap; 405 tons aggregate surface course; removal of existing structures; 135 cu yds concrete structures; 5,893 sq ft precast prestressed concrete deck beams; 10,820 lbs reinforcement bars; 320 ft driving steel piles. (95 Working Days) (Job No. C-97-059-00) (7-10083-0000) (5.00% DBE)
50. Contract No. 97237 Madison County District 8  
Section 99-00089-02-BR  
FAS Route 778 (ST. ROSE ROAD) Project BRS-119(65)  
Remove existing superstructure and replace with a reinforced concrete deck on wide flange beams and removal and replacement of portions of approach pavements. Also includes earthwork, seeding, riprap and guardrail on St. Rose Road over Sugar Creek east of Highland; includes 380 cu yds channel excavation; 0.8 acre seeding and mulch; 216 lbs fertilizer nutrient; 988 sq yds stone riprap; 267 sq yds bridge approach pavement; 84 cu yds structure excavation; 148.5 cu yds concrete superstructure; 58,750 lbs furnish and erect structural steel; 39,950 lbs reinforcement bars, epoxy coated; 100 tons bituminous shoulders SUPERPAVE; 439 ft furnish and drive steel piles; 250 ft steel plate beam guardrail; 8 traffic barrier terminals; 360 ft temporary concrete barrier; underwater structure excavation protection; 509 bar splicers; traffic control surveillance; traffic control and protection. (80 Working Days) (Job No. C-98-352-04) (8-10211-0000) (SUPERPAVE) (12.00% DBE)
51. Contract No. 99198 Saline County District 9  
Section 03-00135-00-BR  
FAS Route 900 (CH 18) Project BRS-900(102)  
Construction consists of replacement of two structures with two single span precast, prestressed concrete deck beam bridges carrying FAS Route 900 over tributary to south fork of Saline River, 1 1/2 miles southeast of Carrier Mills; includes 71 tree removals; 990 cu yds channel and borrow excavation; 0.5 acre seeding; 320 tons stone dumped riprap; 164 tons aggregate surface course; 2 removal of existing structures; 46.4 cu yds concrete structures; 3,080 sq ft precast, prestressed concrete deck beams; 4,754 lbs reinforcement bars; 785 ft driving steel piles; 184.5 ft steel plate beam guardrail; 12 traffic barrier terminals; 535 ft guardrail removal. (60 Working Days) (Job No. C-99-523-04) (9-10168-0000) (0.00% DBE)
52. Contract No. 99202 Johnson County District 9  
Section 03-00059-00-BR  
FAS Route 929 (CH 5) Project BRS-929(118)  
Construction consists of a single span, 1 @ 68'-0" precast, prestressed concrete deck beam bridge carrying FAS Route 929, County Highway 5 over McCorkle Creek east of Vienna; includes 30 tree removals; 485 cu yds earth and channel excavation; 0.3 acre seeding; 225 tons riprap, special; 385 tons aggregate base course; removal of existing structures; 22.9 cu yds concrete structures; 2,040 sq ft precast, prestressed concrete deck beams; 3,750 lbs reinforcement bars; 280 ft driving steel piles; 288 ft steel plate beam guardrail; 8 traffic barrier terminals. (20 Working Days) (Job No. C-99-528-04) (9-10034-0000) (8.00% DBE)  
[SEE MORE BRIDGE](#)

**ELECTRICAL SECTION**

53. Contract No. 62801 Cook County District 1  
Section 2004-062TS  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-94-3(361)57  
Traffic signal modernization and street lighting along I-94/90 (Dan Ryan Expressway) at 57th Street and Wentworth Avenue/Wells Street in Chicago; includes maintain existing lighting system; 2 service installations; 3 ground rods; 1,192 ft PVC conduit in trench; 295 ft galvanized steel conduit in trench; 896 ft trench and backfill with screenings; 2,333 ft electric cable; 1,924 ft triplexed cable in conduit; 4 controllers; 16 luminaires; 5 conventional street lighting units; 17 steel mast arms; 18 signal heads; 8 fiber optic message signs; 10 ft rod and clean duct in conduit; 10 ft repair and replace damaged conduit; mobilization; traffic control and protection. (Completion Date: November 15, 2005) (Job No. C-91-286-04) (1-74823-1204) (10.00% DBE)
54. Contract No. 83747 Cook County District 1  
Section 01-00100-00-TL (FOREST PARK)  
FAU Route 2759 (DES PLAINES AVENUE) Project CMM-8003(155)  
0.34 mile fiber optic interconnection of three traffic signals on Des Plaines Avenue in the Village of Forest Park with modernized signals at Harrison Street, CTA Entrance and Jackson Boulevard. Also minor radius widening, sidewalk replacement and pavement markings all between Harrison Street and Jackson Boulevard in Forest Park; includes 300 sq yds sodding; 2,002 sq ft sidewalk; 2,002 sq ft sidewalk removal; 500 ft combination concrete curb and gutter; 191 sq ft sign panel; 220 ft metal post; 7,700 ft pavement marking; 2,350 ft conduit in trench; 1,958 ft conduit pushed; 2,650 ft trench and backfill; 25,050 ft electric cable in conduit; 10 traffic signal posts; 12 steel mast arm assemblies and poles; 172 ft concrete foundation; 46 signal heads; 5,595 ft remove electric cable from conduit; 8 relocate existing emergency vehicle priority systems; traffic control and protection. (90 Working Days) (Job No. C-91-527-01) (1-11000-0000) (13.00% DBE)
55. Contract No. 83748 Will County District 1  
Section 01-00170-27-TL  
FAP Route 856 (WEBER ROAD) Project CMM-8003(395)  
Project consists of 6.7 miles of fiber optic signal interconnection of 20 signal locations on Weber Road from Division Street to Lily Cache Lane; includes 963 ft conduit pushed; 20,379 ft trench and backfill for electrical work; 38,246 ft electric cable in conduit; 158 signal heads, LED; 11 pedestrian signal heads; 75 inductive loop detectors; 11,546 ft remove electric cable from conduit; remove existing traffic signal system; traffic control and protection. (95 Working Days) (Job No. C-91-182-04) (1-11000-0000) (12.00% DBE)
56. Contract No. 83756 Cook County District 1  
Section 02-00047-00-LT (GLENWOOD)  
FAU Route 1628 (HOLBROOK ROAD) Project M-8003(424)  
Construction consists of 0.34 mile new roadway lighting on FAU Route 1628, Holbrook Road from Halsted Street to Chicago Heights/Glenwood Road in the Village of Glenwood; includes 100 ft exploration trench 48" depth; 623 sq yds sodding, salt tolerant; 10 ground rod, 5/8 inches X 10 ft; 276 ft conduit pushed; 1,916 ft trench and backfill for electrical work; 2,196 ft unit duct with 3-1/c No. 6 and 1/c No.8 ground, 600V; 9 luminaires, sodium vapor, horizontal mount; 9 light poles, aluminum, 35 ft M.H.; traffic control and protection. (15 Working Days) (Job No. C-91-258-04) (1-10974-0000) (0.00% DBE)  
[SEE MORE ELECTRICAL](#)

**MISCELLANEOUS SECTION**

57. Contract No. 62798 Cook County District 1  
Section 2004-059SG  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-94-3(362)57  
1.52 miles of installation of signing along I 94/90 (Dan Ryan Expressway) for the frontage road between 59th Street and 47th Street in Chicago; includes 984 sq ft sign panel; 9 remove sign panel assemblies; 248 sq ft remove sign panel; 9 sq ft relocate sign panel; 964 ft metal post; 186 remove, stockpile and replace sign panel and sign panel assemblies; mobilization; traffic control and protection. (Completion Date: December 27, 2005) (Job No. C-91-283-04) (1-74823-1201) (0.00% DBE)
58. Contract No. 62800 Cook County District 1  
Section 2004-061DTR  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-94-3(360)57  
Tree removal along 3.1 miles of FAI Route 94/90 between 59th Street and 47th Street in Chicago; includes 1,082 units tree removal; 5 lbs temporary erosion control seeding; 38 cu yds topsoil; mobilization; traffic control and protection. (20 Working Days) (Job No. C-91-285-04) (1-74823-1202) (0.00% DBE)

59. Contract No. 62805 Cook County District 1  
Section 2004-066T  
FAI Route 94/90 (DAN RYAN EXPRESSWAY) Project IM-94-3(363)57  
Sewer televising along 3.04 miles of I-94/90 (Dan Ryan Expressway) between 59th Street and 47th Street in Chicago; includes 2,750 ft cleaning existing sanitary sewers; 29,743 ft video taping of sewers; mobilization; traffic control and protection. (Completion Date: December 7, 2005) (Job No. C-91-290-04) (1-74823-1203) (0.00% DBE)

**In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.**

60. Contract No. 68256 Warren County District 4  
Section D4 SLIDE REPAIR 2004-1  
FAP Route 313 (US 34)  
Improvement consists of repairing 425 ft of earth backslope slides and sloughs along U.S. Route 34, 2 miles east of the Cameron interchange; includes 7,665 cu yds earth excavation; 1,631 sq yds top soil furnish and place; 4,268 sq yds stone riprap; 4,268 sq yds filter fabric for use with riprap; mobilization; traffic control and protection. (20 Working Days) (Job No. C-94-078-02) (0-00845-4002) (6.00% DBE)

**In accordance with the requirements of the Governor's Executive Order #2003-13, this project contains a Project Labor Agreement.**

61. Contract No. 72917 Adams County District 6  
Section (1-5,1-6)  
FAI Route 172/FAS Route 1604/TR 349 (I-172/COLUMBUS ROAD)  
4.44 miles of pavement patching and longitudinal joint repairs along I-172/Columbus Road from IL Route 104 junction to U.S. Route 24 north of Quincy; includes 1,127 sq yds patching; 186 sq yds patching reinforcement; 6,547 ft saw cuts; 4,250 ft longitudinal joint repair; 2,412 dowel bars; 70 tie bars; mobilization; traffic control and protection. (25 Working Days) (Job No. C-96-003-05) (0-00845-6002) (0.00% DBE)

62. Contract No. 76769 St. Clair County District 8  
Section 82-3HB-1HDF-2  
FAI Route 64 (I-64)  
Bridge repairs on the existing structure carrying IL Route 111 over I-64 (westbound) at Washington Park; includes 1,210 lbs structural steel repair; 180 ft temporary concrete barrier (state-owned); 180 ft temporary paint pavement marking; beam straightening; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-080-04) (MCHD) (0.00% DBE)

63. Contract No. 83760 McHenry County District 1  
Section 02-02121-00-SW  
FAP Route 305 (U.S. ROUTE 14) Project CMF-305(22)  
The project consists of 1.15 miles of earth excavation, PCC sidewalk installation, land bridge installation, parapet wall installation, pedestrian signal head and push button installation, pavement markings and all other incidental work to complete the project on U.S. Route 14 from IL Route 22 to Main Street; includes 75 cu yds porous granular embankment; 156 lbs fertilizer nutrients; 2,802 sq yds aggregate base course; 24,895 sq ft PCC sidewalk; 511 sq yds bituminous concrete removal; 25,785 lbs reinforcement bars; 2 inlets; 467 ft combination concrete curb and gutter, type B-6.24; 6 traffic barrier terminals; 1,622 ft preformed plastic pavement marking; 25 raised reflective pavement markers; 1,436 ft electric cable in conduit; 40 sediment control, drainage structure, inlet filters and cleaning. (50 Working Days) (Job No. C-91-255-02) (1-11001-0000) (13.00% DBE)

64. Contract No. 85335 Lee County District 2  
Section 01-P4000-00-BT (DIXON PARK DISTRICT)  
LOWELL TRAIL Project TE-D2(115)  
Construction consists of seal coating an existing street, a bike trail and parking lot along the Rock River in Dixon; includes 146 tree removals; 1,060 cu yds earth excavation; 123 sq yds stone riprap; 1,041 tons aggregate base course; 9,062 gals bituminous material cover and seal coat; 179 sq ft PCC sidewalk 5"; 73.8 cu yds concrete structures; 10,450 lbs reinforcement bars, epoxy coated; 220 sq ft steel sheet piling; 425 ft combination concrete curb and gutter; 185.45 sq ft sign panel, type 1; 168 ft conduit in trench; 918 sq ft segmental concrete block wall; 429 sq yds brick surface course. (Completion Date: August 15, 2005) (Job No. C-92-100-02) (0-00904-0000) (5.00% DBE)

**PREQUALIFICATION – Any contractor wishing to submit a bid on this project must be pre-qualified with the Capital Development Board of the State of Illinois and provide proof of pre-qualification to the Department of Transportation. Proof of pre-qualification must be received prior to 4:30 p.m. November 6, 2002.**

65. Contract No. 97239 Madison County District 8  
Section 00-00010-01-HP (GODFREY)  
FAP Route 304 (ILLINOIS ROUTE 100) Project SBIL-3(2)  
Construction consists of a public restroom facility in Clifton Terrace Park on FAP Route 304 in the Village of Godfrey; includes comfort station; mobilization. (65 Working Days) (Job No. C-98-005-01) (0-05034-0000) (10.00% DBE)  
[SEE MORE MISCELLANEOUS](#)



**PAVEMENT SECTION**

66. Contract No. 64630 Ogle County District 2  
Section 4RS-5  
FAP Route 316 (IL 26) Project NHF-316(27)  
Reconstruction of 1.1 miles of IL Route 26 including pavement removal and replacement, earthwork, culvert replacement, and bituminous shoulders. Also, 3.7 miles of IL Route 26 will be patched and resurfaced, aggregate shoulders, and construction one foot of safety shoulder from Willow Street in Forreston to IL Route 64 (W); includes 426 units tree removal; 70,176 cu yds earth excavation; 12,353 cu yds topsoil excavation; 37,210 sq yds erosion control blanket; 463 sq yds stone riprap; 22,744 tons subbase granular material; 858 tons aggregate base course; 847 tons aggregate surface course; 667 sq yds bituminous surface removal-butt joint; 561 tons bituminous replacement over patches; 492 tons incidental bituminous surfacing; 1,845 sq yds bituminous surface removal; 27,216 sq yds pavement removal; 1,002 sq yds bituminous removal over patches; 265 sq yds patching; 50,897 sq yds crack control treatment; 10,071 tons aggregate shoulders; 7,758 sq yds bituminous shoulders, SUPERPAVE; 1,023 ft pipe culverts; 690 ft sewer; 157 right of way markers; 3,314 ft thermoplastic pavement marking line; 163,722 ft paint pavement marking line; 526 pavement markers; 17 trees; 23,099 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; 1,157 ft concrete curb and gutter; 3,474 tons breaker-run crushed stone; mobilization; traffic control and protection. (Completion Date: October 10, 2005) (Job No. C-92-061-04) (2-06440-0100) (SUPERPAVE) (7.00% DBE)
67. Contract No. 68294 Peoria County District 4  
Section 2RS-3  
FAS Route 1380 (IL 91) Project RS-1380(105)  
2.0 miles of 41 feet and variable width resurfacing on IL Route 91 from just south of the bridge over Fargo Run and continues through the Alta Lane intersection; includes 487 sq yds bituminous surface removal-butt joint; 33,237 sq yds bituminous surface removal; 21,599 ft strip reflective crack control treatment; 563 tons aggregate shoulders; 3,185 ft thermoplastic pavement marking line; 34,478 paint pavement marking line; 182 raised reflective pavement markers; 2,759 tons polymerized bituminous concrete surface course, SUPERPAVE, Mix E; 477 ft erosion control curb; 477 ft erosion control curb removal; mobilization; traffic control and protection. (15 Working Days) (Job No. C-94-122-02) (4-00031-0100) (SUPERPAVE) (3.00% DBE)
68. Contract No. 88796 Fulton-Schuyler Counties District 4  
Section 15W-1,RS-2,15BR-1  
FAP Route 317 (US 24) Project NHF-BRF-317(63)  
2.3 miles of 26 feet and variable width of bituminous concrete widening and resurfacing on U.S. Route 24 from TR 6 in Fulton County to 1.4 miles south of the Fulton/Schuyler County Line. Also included is the construction of a bridge over Sugar Creek near Astoria; includes 621 units tree removal; 225,550 cu yds earth excavation; 3,790 cu yds removal and disposal of unsuitable material; 134,424 sq yds topsoil; 11,021 sq yds erosion control blanket; 9,606 ft perimeter erosion barrier; 12,394 tons stone dumped riprap; 6,090 sq yds processing lime modified soils; 122 tons lime; 15,912 sq yds subbase granular material; 213 tons aggregate base course; 945 tons aggregate surface course; 173 sq yds bituminous surface removal-butt joint; 31,997 sq yds bituminous surface removal; 8,256 sq yds pavement removal; 11,780 ft gutter removal; 613 sq yds patches; 15,613 ft crack control treatment; 362 tons aggregate shoulders; 858 tons bituminous shoulders; 566 cu yds structure excavation; 768 cu yds concrete; 1,033 sq yds grooving; 376,120 lbs structural steel; 3,384 stud shear connectors; 11,490 lbs reinforcement bars; 110,330 lbs epoxy coated reinforcement bars; 400 ft steel piles; 694 ft precast concrete box culverts; 922 ft pipe culvert; 6,155 ft concrete gutter; 36,250 ft paint pavement marking line; 5,423 ft fence removal; 16,662 sq ft concrete slope wall removal; 13,069 sq yds bituminous concrete base course, widening, SUPERPAVE; 8,137 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 11,370 sq ft permanent steel sheet piling; mobilization; traffic control and protection. (Completion Date: November 30, 2005 Plus 15 Working Days) (Job No. C-94-366-96) (4-01580-0800, 4-01580-0900) (SUPERPAVE) (15.00% DBE)
69. Contract No. 68354 Peoria County District 4  
Section 130RS-3  
FAP Route 317 (US 150) Project F-317(64)  
3.0 miles of 39 feet and variable width bituminous surface course and pavement patching on U.S. Route 150 from the junction of IL Route 78 and U.S. Route 150 to just north of Interstate 74 near Laura; includes 128 tons aggregate (prime coat); 813 sq yds bituminous surface removal-butt joint; 63,122 sq yds bituminous surface removal; 532 sq yds Class D patches; 1,301 tons aggregate shoulders; 19,418 ft thermoplastic pavement marking-line; 46,271 ft paint pavement marking-line; 5,317 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (20 Working Days) (Job No. C-94-057-03) (4-00001-0000) (SUPERPAVE) (9.00% DBE)

70. Contract No. 72924 Morgan County District 6  
Section 124RS-7  
FAP Route 310 (US 67/IL 104)  
1.75 miles of 24 ft width milling and bituminous concrete surface on U.S. Route 67/IL Route 104 from west of Hart's Gravel Road to west of Dutch Lane East northwest of Bethel; includes 21.5 tons aggregate surface course; 365 sq yds preparation of base; 26,311 sq yds milling; 520 sq yds patching; 386 tons aggregate shoulders; 921 tons bituminous shoulders, SUPERPAVE; 16,650 ft paint pavement marking; 2,566 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; mobilization; traffic control and protection. (25 Working Days) (Job No. C-96-508-05) (0-00845-6005) (SUPERPAVE) (2.00% DBE)
71. Contract No. 84881 Henry County District 2  
Section 136R  
FAP Route 638 (IL 82) Project ACF-638(7)  
1.0 mile of 55 feet and various width of pavement reconstruction on IL Route 82 from 500 feet south of U.S. Route 6 to 1,000 feet south of Interstate 80 in the City of Geneseo; includes 280 units tree removal; 317 ft concrete box culvert; 463 ft pipe culverts; 3,704 ft storm sewers; 26,144 cu yds earth excavation; 22,432 tons subbase granular material; 20,045 sq yds geotechnical fabric for ground stabilization; 48,344 sq yds topsoil furnish and place; 25,313 sq yds sodding; 377 sq yds aggregate base course; 495 tons aggregate surface course; 1,602 sq yds concrete driveway pavement; 11,274 sq ft concrete sidewalk; 722 sq yds bituminous surface removal; 18,979 sq yds pavement removal; 797 ft combination curb and gutter removal; 656 sq yds pavement patching; 800 ft strip reflective crack control treatment; 378 tons aggregate shoulders; 1,371 sq yds bituminous shoulders; removal of four existing structures; 1,889 ft pipe underdrains; 81 inlets; 8,333 ft combination concrete curb and gutter; 10,037 sq ft concrete median; 1,230 sq ft corrugated median; 625 ft steel plate beam guardrail; 2,125 ft guardrail removal; 671 sq ft thermoplastic pavement marking-letters and symbols; 7,509 ft thermoplastic pavement marking line; 11,812 ft polyurea pavement marking; 953 ft storm sewer (water main requirements); removal of four bridge pier foundations; 3,626 ft water main; 175 tons bituminous concrete surface course, SUPERPAVE; 165 tons polymerized bituminous concrete surface course, SUPERPAVE; 166 tons bituminous concrete binder course, SUPERPAVE; 26,204 sq yds bituminous concrete pavement (full-depth), SUPERPAVE; 261 tons breaker-run crushed stone; 10,089 sq yds geotechnical reinforcement; 478 ft steel casings, in trench; mobilization; traffic control and protection. (Completion Date: November 18, 2005 Plus 10 Working Days) (Job No. C-92-114-03) (2-98040-0100) (SUPERPAVE) (8.00% DBE)
72. Contract No. 76618 Madison County District 8  
Section 60-(4,5)-1RS-3  
FAI Route 270 (I-270) Project NHI-270-6(98)7  
5.31 miles of 2 @ 36' and variable width milling, bituminous concrete surface, ramp reconstruction, pavement patching and bridge repairs along FAI Route 270 from east of I-255 to west of the 3-I Interchange (I-55/70/270) at Pontoon Beach; includes 361 cu yds earth excavation; 3,735 cu yds furnished excavation; 0.1 acre seeding; 3,169 sq yds stone riprap; 2,400 sq yds subbase granular material; 109,089 sq yds milling; 790 sq yds pavement removal; 574 sq yds bituminous concrete removal (deck); 9,271 sq yds pavement patching (partial depth); 1,945 tons aggregate shoulders; 12,124 tons bituminous shoulders, SUPERPAVE; 87 cu yds concrete removal; 88 cu yds concrete; 1,792 sq yds bridge deck grooving; 6,733 lbs structural steel; jack and removal 34 existing bearings; 11,204 lbs epoxy coated reinforcement bars; 445 ft steel bridge rail; 2,138 ft steel plate beam guardrail; 32 traffic barrier terminals; 65,843 ft shoulder rumble strip; 94,851 ft polyurea pavement marking; locating 1,000 ft underground cable; 945 ft trench and backfill; 573 ft silicone joint sealer; 80 sq ft polymer modified portland cement mortar; 20,149 tons material transfer device; 14,248 tons polymerized bituminous concrete surface course, Stone Matrix Asphalt, SUPERPAVE; 8,777 tons bituminous concrete binder course, SUPERPAVE; 1,921 sq yds bridge deck microsilica concrete overlay; 1,347 sq yds bridge deck hydro-scarification; 574 sq yds concrete bridge deck scarification; 210 sq yds deck slab repair; 897 sq yds protective shield; 27 cu yds slope wall slurry pumping; mobilization; traffic control and protection. (Completion Date: November 30, 2004 Plus 40 Working Days) (Job No. C-98-059-02) (8-82952-0000) (SUPERPAVE) (10.00% DBE)
73. Contract No. 76788 Greene County District 8  
Section (53,54,55)RS-3  
FAP Route 310 (US 67)  
This improvement consists of 1.1 miles of 32' width resurfacing and 1.3 miles of concrete patching on U.S. Route 67 from Township Road 237 near Carrollton to 0.6 miles south of Macoupin Creek; includes 15,488 sq yds bituminous surface removal; 926 sq yds pavement patching; 5,808 ft strip reflective crack control treatment; 289 tons bituminous shoulders SUPERPAVE; 15,272 ft thermoplastic pavement marking-line; 15,325 ft polyurea pavement marking-line; 1,301 tons bituminous concrete surface course, SUPERPAVE; 650 tons leveling binder (machine method), SUPERPAVE; mobilization; traffic control and protection. (45 Working Days) (Job No. C-98-060-04) (8-89403-0100) (SUPERPAVE) (5.00% DBE)

74. Contract No. 68315 McDonough County District 4  
Section 108RS-5  
FAP Route 315 (US 136) Project ACNHF-315(35)  
6.40 miles of 24 ft and variable width milling, patching, bituminous surface course and raised median removal along U.S. Route 136 from IL Route 41 near New Philadelphia to the Fulton County Line near Table Grove; includes 2,606 sq yds bituminous base course; 40 sq yds temporary ramp; 87,586 sq yds milling; 23,454 sq ft median removal (partial depth); 3,660 sq yds patching; 153 ft saw cuts; 1,459 tons aggregate shoulders; 875 sq yds bituminous shoulders, SUPERPAVE; 79,114 ft paint pavement marking; 11,309 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (40 Working Days) (Job No. C-94-008-03) (4-14070-0100) (SUPERPAVE) (6.00% DBE)
75. Contract No. 76768 Randolph County District 8  
Section DIST. 8 WSC 2005-1  
PARK ROADS  
This project consists of constructing bituminous roadways, campgrounds, and a 13-acre parking lot for IL Department of Natural Resources' proposed World Shooting Complex 3 miles north of Sparta on County Highway 18 west of IL Route 4; includes 421 units tree removal; 204,861 cu yds earth excavation; 1,087 cu yds channel excavation; 29,550 cu yds topsoil excavation and placement; 1,605 sq yds erosion control blanket; 31,112 ft perimeter erosion barrier; 304,007 sq yds aggregate base course; 15,143 tons aggregate surface course; 421 sq yds pavement removal; 7,038 sq yds aggregate shoulders; 42,540 lbs reinforcement bars; 1,250 ft pipe culverts; 748 ft concrete curb; 250 ft chain link fence; 5,212 ft woven wire fence; 343 sq ft sign panel; 315 ft metal post; 869 ft wood sign support; 345 sq ft paint pavement marking-letters and symbols; 35,224 ft paint pavement marking; 18,536 tons bituminous concrete surface course, SUPERPAVE; 18,536 tons leveling binder (machine method), SUPERPAVE; mobilization; traffic control and protection. (Completion Date: June 01, 2006) (Job No. C-98-044-04) (8-00086-0200) (SUPERPAVE) (5.00% DBE)
76. Contract No. 66504 Kendall County District 3  
Section (108)N  
FAP Route 326 (IL 47) Project ACHS-326(57)  
0.20 mile of variable width milling and bituminous concrete surface on IL Route 47 from south of River Street to north of Main Street in Yorkville; includes 78 sq yds temporary ramp; 4,600 sq yds milling; 298 sq yds bituminous base course, SUPERPAVE; 365 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, Mix E, N 90; 48 ft expansion joint rehabilitation; mobilization; traffic control and protection. (Completion Date: October 01, 2004) (Job No. C-93-147-04) (3-44280-0000) (SUPERPAVE) (0.00% DBE)
77. Contract No. 64A25 Whiteside County District 2  
Section 1M  
FAS Route 2187 (PILGRIM RD/COLETA SPUR)  
0.15 mile of 17 feet width of coldmilling bituminous shoulders, new curb and gutter, and driveway grade adjustments along Pilgrim Road 0.1 mile west of Main Street to 0.1 mile east of Main Street in Coleta; includes 64 cu yds earth excavation; 975 sq yds sodding; 139 sq yds aggregate base course; 312 sq yds concrete pavement; 292 sq yds bituminous surface removal; 265 sq yds driveway pavement removal; 1,353 ft combination curb and gutter removal; 1,357 ft combination curb and gutter; 113 tons bituminous concrete surface course, SUPERPAVE; 71 tons leveling binder (machine method), SUPERPAVE; mobilization; traffic control and protection. (20 Working Days) (Job No. C-92-118-04) (2-97625-0004) (SUPERPAVE) (0.00% DBE)
78. Contract No. 64275 Ogle County District 2  
Section 105RS-1  
FAP Route 17 (IL 64) Project F-17(116)  
1.10 miles of 26' and variable width widening and resurfacing, new curb & gutter, storm sewer separation, intersection improvements, introduction of right turn lanes on various roads, bi-directional left turn lanes throughout, signal modernization at 3rd and 4th Streets, new signal at 10th Street on Illinois Route 64 starting 500' north of Illinois Street and continues to 40' east of First Street in the City of Oregon; includes 49 trees; 912 units tree removal; 13,693 cu yds earth excavation; 16,282 sq yds topsoil; 12,110 sq yds erosion control blanket; 10,417 sq yds sodding; 5,427 tons subbase granular material; 4,082 tons aggregate base course; 1,724 sq yds concrete base course; 2,598 sq yds concrete driveway; 29,876 sq ft concrete sidewalk; 12,263 sq yds bituminous surface removal; 1,552 sq yds pavement removal; 1,284 sq yds driveway pavement removal; 2,101 ft gutter removal; 6,100 ft curb and gutter removal; 21,044 sq ft sidewalk removal; 2,023 sq yds patching; 1,444 ft saw cuts; 6,384 ft crack control treatment; 220 ft pipe culverts; 4,788 ft storm sewers; 20 manholes; 76 inlets; 12,256 ft curb and gutter; 38 right of way markers; 6,749 ft thermoplastic pavement marking line; 8,872 ft polyurea pavement marking line; 239 pavement marker; 7,026 ft conduit; 36,096 ft electric cable; 27 luminaires; 19 light pole foundations; 8 signal heads; 112 ft concrete foundation; 1,176 ft detector loop; 1,242 ft storm sewer(watermain requirements); 4,205 tons bituminous concrete binder and surface course, SUPERPAVE, MIX C; 5,488 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, MIX D; 19 signal heads; 900 dowel bars; 1,266 tie bars; mobilization; traffic control and protection. (95 Working Days) (Job No. C-92-068-03) (2-11170-0100) (SUPERPAVE PROJECT) (7.00% DBE)



79. Contract No. 76780 St. Clair County District 8  
Section (47,113)RS-3  
FAP Route 680 (IL 4)  
8.3 miles of 26 feet and variable width of milling, patching and resurfacing on IL Route 4 from south of IL Route 15 in St. Libory to IL Route 13 in Marissa; includes 899 sq yds concrete surface removal-butt joint; 125,547 sq yds bituminous surface removal; 346 sq yds Class D patches; 87,576 ft strip reflective crack control treatment; 426 tons aggregate shoulders; 1,893 tons bituminous shoulders, SUPERPAVE; 109,036 ft thermoplastic pavement marking line; 557 raised reflective pavement markers; 547 raised reflective pavement markers removal; 9,081 tons bituminous concrete surface course, SUPERPAVE; 4,541 tons leveling binder (machine method) SUPERPAVE; mobilization; traffic control and protection. (55 Working Days) (Job No. C-98-054-04) (8-00059-0000) (SUPERPAVE) (5.00% DBE)
80. Contract No. 64532 Stephenson County District 2  
Section 177-(3,4,4-1)1A&3HB,4HB-5,4B-4  
FAP Route 301 (US 20) Project NHF-301(29)  
6.36 miles of grading to add westbound lanes and Illinois Route 75 interchange, including (3) bridges: Tower Road over U.S. Route 20; westbound over Illinois Route 75; and U.S. Route 20 westbound over the Pecatonica River, East located from east of Illinois Route 26 to west of Springfield Road in Freeport; includes 2,187 units tree removal; 322,128 cu yds earth excavation; 106,636 cu yds rock excavation; 16,757 cu yds removal and disposal of unsuitable material; 16,399 tons subbase granular material; 56,823 cu yds borrow excavation; 8,707 cu yds topsoil excavation; 20,159 sq yds topsoil; 75,122 sq yds erosion control blanket; 6,959 ft perimeter erosion barrier; 4,601 sq yds stone riprap; 23,996 sq yds stabilized subbase; 20,660 tons aggregate base course; 12,967 sq yds concrete pavement; 22,467 sq yds pavement removal; 2,858 ft curb and gutter removal; 18,019 sq ft concrete median surface removal; 15,083 sq yds paved shoulder removal; 6,326 tons aggregate shoulders; 7,345 sq yds concrete shoulders; 701 cu yds structure excavation; 2,089 cu yds concrete; 5,423 sq yds bridge deck grooving; 30 elastomeric bearing assemblies; 1,315 ft concrete bulb T-beams; 16,200 stud shear connectors; 16,236 lbs reinforcement bars; 164,770 lbs epoxy coated reinforcement bars; 3,253 ft steel piles; 103 cu yds concrete box culvert; 6,926 ft pipe culverts; 7,242 ft pipe underdrains; 9,928 sq ft concrete median surface; 2,049 ft woven wire fence; 70 right of way markers; 10,729 ft epoxy pavement marking line; 8,199 ft polyurea pavement marking line; 340 ft conduit; 5,050 ft unit duct; 10 luminaires; 10 light poles; 293 trees; 50 shrubs; 3,717 tons bituminous concrete surface course, SUPERPAVE, Mix C; 1,482 ft curb and gutter; 6,101 sq ft concrete median; 100 ft storm sewer; 6,428 ft culverts to be cleaned; 38,745 tons shot rock; traffic control and protection; mobilization. (Completion Date: June 23, 2006 Plus 10 Working Days) (Job No. C-92-013-03) (2-06910-0200&0100) (SUPERPAVE) (8.00% DBE)
81. Contract No. 64646 Rock Island County District 2  
Section (33NRS)R-1  
FAU Route 5788 (AIRPORT ROAD)  
2.09 miles of bituminous concrete widening of the existing Milan Beltway to four lanes and its extension north of Airport Road, construction of the interchange at Airport Road east of Interstate 280 to east of Milan Beltway; includes 784 units tree removal; 136,185 cu yds earth excavation; 276,825 cu yds furnished excavation; 4,349 cu yds porous granular materials; 151,360 sq yds topsoil; 30 acres mowing; 52 acres seeding; 14,156 sq yds erosion control blanket; 7,022 ft perimeter erosion barrier; 1,938 sq yds stone riprap; 87,938 tons subbase granular material; 53,168 sq yds stabilized subbase; 29,237 tons aggregate base course; 267 sq yds concrete surface removal; 707 tons incidental bituminous surfacing; 83,252 sq yds concrete pavement; 30,058 sq yds pavement removal; 3,451 ft curb and gutter removal; 16,411 sq ft concrete median surface removal; 7,254 sq yds paved shoulder removal; 382 sq yds patching; 1,670 ft saw cuts; 1,665 ft crack control treatment; 5,369 tons aggregate shoulders; 4,524 sq yds bituminous shoulders, SUPERPAVE; 21,296 sq yds concrete shoulders; 2,424 cu yds structure excavation; 3,271 cu yds concrete; 5,691 sq yds bridge deck grooving; 48 elastomeric bearing assemblies; 3,469 ft concrete I-beams; 943,790 lbs structural steel; 8,460 stud shear connectors; 194,540 lbs reinforcement bars; 640,350 lbs epoxy coated reinforcement bars; 1,866 sq yds slope walls; 4,205 ft steel piles; 457 cu yds concrete box culverts; 2,608 ft pipe culverts; 5,299 ft storm sewers; 930 ft pipe drains; 8,705 ft pipe underdrains; 7 manholes; 48 inlets; 11,251 ft concrete curb and gutter; 28,606 sq ft concrete surface median; 1,957 sq ft corrugated median; 13,551 ft chain link fence; 1,015 ft chain link fence to be removed and re-erected; 1,591 ft woven wire fence; 26 right of way markers; 81,231 ft polyurea pavement marking line; 10,368 ft conduit; 30 handholes; 24,412 ft trench and backfill; 22,527 ft unit ducts; 49,121 ft electrical cable; 123 luminaires; 75 light poles; 8 mast arm assemblies and poles; 154 ft concrete foundations; 3,034 ft detector loops; 4,307 trees; 6,575 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 9,007 tons breaker-run crushed stone; 1,194 bar splicers; removal of 4 buildings; 40 signal heads; traffic control and protection; mobilization. (Completion Date: October 13, 2006 Plus 30 Working Days) (Job No. C-92-124-03) (2-95140-0300) (SUPERPAVE) (8.00% DBE)

82. Contract No. 76693 St. Clair County District 8  
Section 27-1R-1  
FAP Route 103 (IL 13/15) Project F-103(62)  
1.44 miles of 24 feet and variable width of bituminous concrete widening, resurfacing, intersection relocation and traffic signals on Illinois Route 13/15 from Rodgers Drive to just south of the Illinois Route 13/15 split in Freesburg; includes 230 sq yds pavement patching; 29,414 sq yds bituminous surface removal; 1,646 sq yds paved shoulder removal; 4,611 sq yds curb and gutter removal; 1,777 sq yds pavement removal; 22,684 sq ft sidewalk removal; 19,005 cu yds earth excavation; 8,380 ft concrete curb and gutter; 8,137 tons subbase granular material; 2,189 sq yds bituminous concrete pavement (full-depth); 1,019 sq yds bituminous base course widening; 9,852 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 4,500 ft crack control treatment; 703 tons incidental bituminous surfacing; 3,733 sq yds bituminous shoulders, SUPERPAVE; 28,752 sq ft concrete sidewalk; 83 ft concrete culvert; 823 ft pipe culverts; 6,699 ft storm sewers; 48,000 ft thermoplastic pavement marking line; 11,334 sq yds sodding; traffic control and protection; mobilization. (105 Working Days) (Job No. C-98-090-03) (8-88970-0107) (SUPERPAVE) (10.00% DBE)
83. Contract No. 72513 Adams County District 6  
Section (101,102)RS-4  
FAP Route 518 (IL 94) Project F-518(3)  
8.98 miles of 26 ft width milling and bituminous concrete surface on Illinois Route 94 from the Illinois Route 94/62 junction, 4.5 miles east of Big Neck to U.S. Route 24; includes 15 units excavating and grading existing shoulder; 47 cu yds trench backfill; 140,947 sq yds milling; 2,610 sq yds patching; 20 lbs joint or crack filling; 1,869 tons aggregate shoulders; 92 tons bituminous shoulders, SUPERPAVE; 869 cu yds structure excavation; 213 cu yds concrete; 8,740 lbs reinforcement bars; 18,110 lbs epoxy coated reinforcement bars; 508 ft concrete gutter; 4 traffic barrier terminals; 120,650 ft paint pavement marking; 11,777 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C, N50; traffic control and protection; mobilization. (50 Working Days) (Job No. C-96-521-04) (6-76320-0000, 6-72500-0000) (SUPERPAVE) (4.00% DBE)
84. Contract No. 94629 Effingham County District 7  
Section 107Z,R,PB  
FAP Route 774 (IL 32/33) Project ACF-ACTE-774(22)  
The project consists of 3.7 lane miles of PCC pavement, pavement removal, earthwork, lime modification, curb and gutter, storm sewer, traffic signals, bridge deck overlays, pedestrian bridge, highway lighting, interchange signing, retaining wall, culverts, sodding and seeding on IL Route 32/33 (Kellar Drive) at the interchange with FAI Route 70 in Effingham; includes 1,420 units tree removal; 56,100 cu yds earth excavation; 2,690 cu yds removal and disposal of unsuitable material; 46,734 sq yds topsoil furnish and place; 33,700 sq yds processing lime modified soils; 20,106 sq yds subbase granular material; 21,418 sq yds stabilized subbase; 36,190 sq yds jointed PCC pavement; 436 sq yds bridge approach pavement; 1,126 sq yds continuously reinforced PCC pavement; 33,534 sq ft PCC sidewalk; 27,925 sq yds pavement removal; 10,925 ft combination curb and gutter removal; 980 sq yds bituminous concrete removal (deck); 11,037 sq ft median surface removal; 40,389 sq yds PCC shoulders; 383 cu yds structure excavation; 153 cu yds concrete structures; 236 cu yds concrete superstructures; 120,513 lbs structural steel; 1,008 stud shear connectors; 68,867 lbs epoxy coated reinforcement bars; 374 ft steel piles, HP 12 X 53; 23 cu yds concrete box culverts; 5,773 ft storm sewers; 13,304 ft combination concrete curb and gutter; 575 ft steel plate beam guardrail; 8 traffic barrier terminals; 1,363 ft guardrail removal; 11,070 ft paint pavement marking line; 18,489 ft polyurea pavement marking line; 322 raised reflective pavement markers; 4,493 ft conduit in trench; 848 sq yds bridge deck thin polymer overlay; 1,645 sq yds bituminous base course, SUPERPAVE; 23,824 ft electric cable in conduit; 11 steel combination mast arm assemblies and poles; 48 shade trees; 43 signal heads; 958 sq yds bridge deck microsilica concrete overlay; 5 building removals; 184 sq yds deck slab repair; mobilization; traffic control and protection. (Completion Date: September 01, 2006 Plus 15 Working Days) (Job No. C-97-025-96) (7-77320-0100) (SUPERPAVE) (10.00% DBE)
85. Contract No. 94748 White County District 7  
Section 101R  
FAP Route 877 (IL 141) Project F-877(10)  
0.52 mile of vertical curve reconstruction on IL Route 141 at the intersection with Herald Road located 1 mile west of New Haven; includes 253 units tree removal; 39,675 cu yds earth excavation; 1,180 cu yds furnished excavation; 2,650 cu yds topsoil excavation and placement; 13,436 sq yds processing lime modified soils; 504 tons subbase granular material; 12,364 sq yds pavement removal; 1,399 ft gutter removal; 473 tons aggregate shoulders; 1,383 sq yds bituminous shoulders, SUPERPAVE; 7 ft precast concrete box culvert; 6,300 ft paint pavement marking line; 26 raised reflective pavement markers; 3 shade trees; 3 intermediate trees; 16 evergreens; 907 sq yds bituminous base course, SUPERPAVE; 6,731 sq yds bituminous concrete pavement (full-depth), SUPERPAVE, 9 1/2"; 5,533 sq yds bituminous concrete pavement (full-depth), SUPERPAVE, 14 1/4"; 134 tons incidental bituminous surfacing, SUPERPAVE, N50; traffic control and protection; mobilization. (70 Working Days) (Job No. C-97-070-98) (7-79680-0100) (SUPERPAVE) (4.00% DBE)

86. Contract No. 62794 Cook County District 1  
Section 0102.5-I  
FAI Route 90 (I-90 (KENNEDY EXPRESSWAY))  
0.47 mile of ramp repairs consisting of milling, patching, bituminous concrete surface and drainage structures to be cleaned along FAI Route 90 (Kennedy Expressway) westbound from East River Road to Cumberland Avenue in Chicago; includes 1,475 cu yds earth excavation; 12,730 sq yds topsoil; 2.6 acres seeding; 3,500 sq yds subbase granular material; 1,320 sq yds concrete base course widening; 17,000 sq yds milling; 128 sq yds patching; 255 tons aggregate shoulders; 2,180 sq yds bituminous shoulders, SUPERPAVE; 2,501 sq ft sign panel; 100 ft storm sewers to be cleaned; 4 traffic barrier terminals; 7,500 ft thermoplastic pavement marking; 3,386 tons material transfer device; 3,386 tons Stone Matrix Asphalt binder and surface course; 327 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (Completion Date: October 28, 2004 Plus 05 Working Days) (Job No. C-91-277-04) (1-77065-0100) (SUPERPAVE) (13.00% DBE)  
[SEE MORE PAVEMENT](#)

#### **BRIDGE SECTION**

87. Contract No. 97240 Bond County District 8  
Section 03-00076-00-BR  
FAS Route 777 (CH 18) Project BRS-777(112)  
Construction consists of a bridge removal and replacement carrying FAS Route 777, County Highway 18 over tributary to Shoal Creek 5 miles north of Greenville; includes 0.2 acre tree removal; 946 cu yds earth excavation; 2,548 cu yds furnished excavation; 1.5 acres seeding; 150 tons stone riprap; 996 tons aggregate surface course; 63 tons cover and seal coat aggregate; 197 tons aggregate shoulders; 46.3 cu yds concrete structures; 70 ft three sided precast concrete structure 24' X 11'; precast concrete substructure; 200 ft paved ditch; traffic control and protection. (35 Working Days) (Job No. C-98-358-04) (8-10039-0000) (8.00% DBE)
88. Contract No. 70343 Moultrie County District 5  
Section (105BR-3)BR  
FAP Route 320 (IL 121) Project BHF-320(27)  
0.09 mile of superstructure replacement on the existing bridge carrying IL Route 121 over Crabapple Creek located 4 miles northwest of Mattoon; includes 23 cu yds furnished excavation; 78 sq yds temporary ramp; 240 sq yds bridge approach pavement; 85 sq yds pavement removal; 107 sq yds approach slab removal; 21 tons aggregate shoulders; removal of existing superstructure; 3.8 cu yds concrete removal; 6.2 cu yds concrete; 251 sq yds bridge deck grooving; 252 sq yds concrete wearing surface; 2,368 sq ft precast, prestressed concrete deck beams; 5,620 lbs epoxy coated reinforcement bars; 132 ft steel bridge rail; 400 ft steel plate beam guardrail; 8 traffic barrier terminals; 51 ft paint pavement marking; 72 ft bridge joint system (expansion); 240 sq yds pavement grooving; 51 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; mobilization; traffic control and protection. (Completion Date: October 15, 2004 Plus 05 Working Days) (Job No. C-95-109-03) (5-51970-0000) (SUPERPAVE) (12.00% DBE)
89. Contract No. 84914 Rock Island County District 2  
Section 117R,117BR-1,117BR-2,F-BR-1  
FAU Route 5797 (US 150) Project ACM-ACBRM-5797(3)  
Removing the existing 2 lane pavement and replacing it with a 3 lane section with full depth bituminous. Also included is curb & gutter, sidewalks, storm sewer, and entrances. The intersections of U.S. 150 with West 3rd Street and 1st Street will be signalized. There are two bridges over Coal Creek that will be replaced with bridges and one bridge over Wilson Creek which will be replaced with a triple 3.0 m x 2.4 m box culvert. A 145 m long soldier pile retaining wall will be constructed from the Library Entrance to Wilson Creek. Located on U.S. 150 in Coal Valley from West 102nd Street to East 3rd Street; includes 2,628 stud sheer connectors; 59 inlets; 8 luminaires; 889 bar splicers; 663 m furnishing soldier piles; 171 trees; 100 shrub; 3,861 tree removal; 49,150 cu m earth excavation; 902 cu m removal and disposal of unsuitable material; 1,068 cu m porous granular embankment; 13,038 sq m topsoil; 13,037 sq m sodding; 1,540 sq m stone riprap; 19,640 sq m subbase granular material; 11,682 m tons aggregate base course; 942 m tons aggregate surface course; 1,922 sq m concrete driveway; 1,927 sq m concrete sidewalk; 14,007 sq m pavement removal; 472 sq m sidewalk removal; 478 sq m paved shoulder removal; 442 cu m structure excavation; 595 cu yds concrete; 83,360 kg structural steel; 24,980 kg reinforcement bars; 58,300 kg epoxy coated reinforcement bars; 131 m steel piles; 183 cu m concrete box culverts; 815 m storm sewers; 15 manholes; 2,554 m concrete curb and gutter; 6,812 m thermoplastic pavement marking line; 622 m conduit; 4,405 m electric cable; 8 mast arm assemblies and poles; 551 m detector loops; 751 m storm sewer (water main requirements); 283 m water service line; 238 cu m drilling and setting soldier piles; 903 sq m aggregate ditch; 1,642 m tons bituminous concrete binder and surface course, SUPERPAVE, MIX C; 12,635 sq m polymerized bituminous concrete pavement (full depth), SUPERPAVE; 20 signal heads; mobilization; traffic control and protection. (Completion Date: November 24, 2005 Plus 20 Working Days) (Job No. C-92-134-02) (2-06540-0100) (SUPERPAVE PROJECT) (6.00% DBE)

90. Contract No. 98868 Pulaski County District 9  
Section D-9 CONT. MAINT. FY05-2  
FAI Route 57/FAP Route 322 (I-57/US 51)  
Proposed work consists of floor drain extension, floor drain elimination, and concrete repair on the underside of the deck around the drains on the structures carrying Interstate Route 57 and U.S. Route 51 over Unmarked F.A.S. 2936 in Pulaski County, near the Alexander County Line. The total length of Structure Number 1 is 1,013 feet and Number 2 is 1,085 feet; includes 353 floor drain extensions; 247 plug existing deck drains; 227 sq ft polymer modified cement mortar; mobilization; traffic control and protection. (50 Working Days) (Job No. C-99-028-04) (0-00845-9010) (0.00% DBE)

#### **ELECTRICAL SECTION**

91. Contract No. 72916 Sangamon County District 6  
Section ((107Z-6,X-5)(107Z-7,X-6))TS-6  
FAP Route 67 (IL 97)  
Traffic signal upgrades along Illinois Route 97 at the intersections of Madison Street, Jefferson Street and MacArthur Boulevard in Springfield; includes 4 illuminated signs (special); remove existing traffic signal equipment; traffic control and protection; mobilization. (Completion Date: August 29, 2004) (Job No. C-96-001-05) (0-00845-6001) (0.00% DBE)

#### **MISCELLANEOUS SECTION**

92. Contract No. 87255 Kendall County District 3  
Section 00-00028-00-BT (OSWEGO)  
WAUBONSIE CREEK BIKE PATH Project TE-D3(45)  
Construction consists of a bike path from the Oswego Public Library at Main Street and Jefferson Street to the Hudson Crossing Park at Harrison Street and Jefferson Street along the shoreline of Waubonsie Creek in the Village of Oswego; includes 112 trees removed; 78 cu yds rock excavation; 294 cu yds furnished excavation; 2,400 sq yds topsoil furnish and place 4"; 2,400 sq yds sodding; 960 sq yds aggregate base course; 1,566 ft concrete curb; 700 ft trench and backfill for electrical work; 13 trees, 2 1/2" caliper, balled and burlapped; 6,000 vines English ivy and Japanese spurge, 2" pot; 3,000 vines, periwinkle, 3" pot; 55 bollards; 166 tons bituminous concrete surface course; modify existing lighting controller; railroad flagman; 634 ft ornamental metal fence; 10 light poles, aluminum 14 ft; 739 sq ft cast in place concrete wall; 8,640 sq ft surface street print; traffic control and protection. (Completion Date: August 20, 2004) (Job No. C-93-156-03) (0-00904-0000) (4.00% DBE)
93. Contract No. 68413 Stark County District 4  
Section D4 SURFACE REPAIR 2005  
FAS Route 1379 & FAS Route 2244 (IL 91 & OSCEOLA ROAD)  
8 miles of 20 feet width of slurry seal at locations: Location Number 1 on Osceola Road north of IL Route 93, Location Number 2 on IL Route 91 from IL Route 93 to IL Route 17; includes 122,418 ft paint pavement marking line; 101,664 sq yds asphaltic emulsion slurry seal; mobilization; traffic control and protection. (15 Working Days) (Job No. C-94-096-04) (0-00845-4011) (3.00% DBE)
94. Contract No. 68416 Knox County District 4  
Section D4 SURFACE REPAIR 2005-1  
FAS Route 2400 (US 150)  
5.2 miles of 24 feet and variable width micro-seal on U.S. Route 150 from the Spoon River to the Knox/Peoria County Line; includes 73,539 sq yds micro-surfacing, 2 passes; 67,931 ft paint pavement marking line; mobilization; traffic control and protection. (15 Working Days) (Job No. C-94-102-04) (0-00845-4012) (3.00% DBE)
95. Contract No. 68410 Various Counties District 4  
Section D4 MCDR (2005/2006)  
Various Routes (VARIOUS)  
The work consists of removing damaged guardrail and/or fence and components and replacing with new material on a call out basis at various locations throughout the western part of District Four; includes 100 furnish and install guardrail blocks; 37 traffic barrier terminals; 300 ft chain link fence; 400 ft woven wire fence; 125 ft furnishing and installing radius panels; 160 ft erect salvaged rail elements (hit and run only); 1,000 ft furnishing and installing rail element plates; 150 ft furnishing and installing tubular thrie beam; 100 furnishing and setting steel posts; 50 removing and resetting posts; 21 repair traffic barrier terminals; traffic control and protection. (Completion Date: June 30, 2005) (Job No. C-94-087-04) (0-00845-4009 & MCHD) (0.00% DBE)

96. Contract No. 68411 Various Counties District 4  
Section D4 MCDR (2005/2006)-1  
Various Routes (VARIOUS)  
The work consists of removing damaged guardrail and/or fence components and replacing with new material on a call out basis at various locations throughout the eastern part of District Four; includes 100 furnish and install guardrail blocks; 18 traffic barrier terminals; 200 ft vertical adjustment of guardrail; 300 ft chain link fence; 160 ft erect salvaged rail elements (hit and run only); 125 ft furnishing and installing radius panels; 1,000 ft furnishing and installing rail element plates; 150 ft furnishing and installing tubular thrie beam; 100 furnishing and setting steel posts; 50 removing and resetting posts; 21 repair traffic barrier terminals; traffic control and protection. (Completion Date: June 30, 2005) (Job No. C-94-088-04) (0-00845-4009 & MCHD) (0.00% DBE)
97. Contract No. 64A31 Boone County District 2  
Section (6,15,14)R-RS-1  
FAP Route 525 (US 20 (EB))  
2.0 miles of 24 feet width micro-surfacing along eastbound U.S. Route 20 from east of Irene Road to west of Pearl Street in Belvidere; includes 578 sq yds bituminous surface removal; 27,740 sq yds micro-surfacing, 2 passes; 46,482 ft paint pavement marking line; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-136-04) (0-00845-2037) (0.00% DBE)
98. Contract No. 62820 Will County District 1  
Section 2004-079I  
FAI Route 55 (I-55 WEST FRONTAGE ROAD)  
1.19 miles of pavement preservation consisting of 28 ft width micro-surfacing on the I-55 West Frontage Road from U.S. Route 6 (Eames Street) to Bluff Road in Channahon; includes 95 units grading and shaping shoulders; 19,550 sq yds micro-surfacing, 2 passes; 5,032 lbs crack filling; 157 tons aggregate shoulders; 3,330 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-91-335-04) (0-00845-1001) (0.00% DBE)
99. Contract No. 70435 Clark County District 5  
Section D-5 LANDSCAPING 2004-1  
FAI Route 70 (I-70)  
9.9 miles of landscaping along Interstate 70 from IL Route 1 to the Indiana State Line which consists of furnishing all equipment, labor, and materials necessary to complete the work; includes 88 trees; mobilization. (15 Working Days) (Job No. C-95-079-04) (5-91184-0004) (0.00% DBE)
100. Contract No. 74065 Effingham County District 7  
Section D-7 PAVT. PATCHING 2005-1  
FAI Route 57 (I-57)  
Pavement patching along 4.0 miles of I-57 from the Shelby/Effingham County Line south to just north of Teutopolis; includes 435 sq yds concrete patching; 453 sq yds patching reinforcement; 2,532 ft saw cuts; 54 tie bars; mobilization; traffic control and protection. (25 Working Days) (Job No. C-97-086-04) (0-00845-7001) (0.00% DBE)
101. Contract No. 64A33 Henry County District 2  
Section (117)RS  
FAS Route 1188 (US 150)  
2.0 miles of 24 feet width micro-surfacing on U.S. Route 150 from north of County Road 1200N near Orion to north of IL Route 81; includes 694 sq yds bituminous surface removal; 31,477 sq yds micro-surfacing; 71,412 ft paint pavement marking-line; 148 raised reflective pavement markers; 148 raised reflective pavement markers removal; 5 tons leveling binder (hand method), SUPERPAVE; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-137-04) (0-00845-2039) (SUPERPAVE) (0.00% DBE)
102. Contract No. 62821 Will County District 1  
Section 2004-080I  
FAI Route 55 (I-55 EAST FRONTAGE ROAD)  
1.25 mile of pavement preservation consisting of 28 ft width micro-surfacing on the I-55 East Frontage Road from U.S. Route 6 (Eames Street) to Bluff Road in Channahon; includes 100 units grading and shaping shoulders; 20,570 sq yds micro-surfacing, 2 passes; 5,288 lbs crack filling; 166 tons aggregate shoulders; 2,893 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-91-336-04) (0-00845-1002) (0.00% DBE)
103. Contract No. 64968 Bureau County District 2  
Section ORCB-LIT/VID  
TR 246 (OLD DAD JOE TRAIL) Project NHCB-00D2(121)  
Provide video monitoring and supplemental lighting at the Historic Red Covered Bridge on Old Dad Joe Trail (Township Road 246) over Bureau Creek, one-half mile west of Illinois Route 26, northwest of Princeton; includes 1,185 ft conduit; 155 ft trench and backfill; 500 ft electric cable in conduit; 19 ft light pole foundation; 4 luminaires; 19 ft light pole foundations; 2 light poles; video surveillance system complete; mobilization; traffic control and protection. (40 Working Days) (Job No. C-92-018-04) (2-09270-0200) (0.00% DBE)

104. Contract No. 64632 Ogle-DeKalb Counties District 2  
Section (123,124,125)RS-2  
FAP Route 17 (IL 64) Project F-17(115)  
18.76 miles of 26 feet and variable width of patching and bituminous resurfacing on Illinois Route 64 from Illinois Route 251 to Peace Road in Sycamore; includes 220 units tree removal; 37,038 cu yds earth excavation; 2,578 cu yds furnished excavation; 13,614 cu yds topsoil; 19,900 tons subbase granular material; 4,364 tons aggregate base course; 549 tons aggregate surface course; 2,385 sq yds bituminous surface removal-butt joint; 638 tons bituminous replacement over patches; 3,862 sq yds bituminous surface removal; 14,311 sq yds pavement removal; 2,147 sq yds bituminous removal over patches; 1,115 sq yds patching; 2,555 ft saw cuts; 252,928 sq yds crack control treatment; 27,539 tons aggregate shoulders; 6,463 sq yds bituminous shoulders, SUPERPAVE; 675 ft pipe culverts; 4,875 ft guardrail; 86 right of way markers; 2,460 ft thermoplastic pavement marking line; 460,050 ft paint pavement marking line; 1,222 pavement markers; 43,234 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 14,839 sq yds bituminous concrete pavement (full-depth) SUPERPAVE; 1,025 tons incidental bituminous surfacing, SUPERPAVE; 1,310 dowel bars; 388 sq yds granular subgrade replacement; mobilization; traffic control and protection. (Completion Date: October 03, 2005) (Job No. C-92-057-03) (2-98410-0100) (SUPERPAVE PROJECT) (6.00% DBE)
105. Contract No. 76825 Calhoun County District 8  
Section (5,6)RS-3  
FAP Route 304 (IL 96)  
8.7 miles of 22 feet width micro surfacing on IL Route 96 near Hamburg from Hamburg Road to the Pike County Line; includes 112,192 sq yds micro-surfacing; 3,548 tons aggregate shoulders; 155,287 ft paint pavement marking-line; 574 raised reflective pavement markers; 574 raised reflective pavement markers removal; mobilization; traffic control and protection. (30 Working Days) (Job No. C-98-091-04) (8-00118-0000) (0.00% DBE)
106. Contract No. 76828 Randolph County District 8  
Section (20-2,19)RS-2  
FAP Route 329 (IL 154)  
3.54 miles of micro surfacing on IL Route 154 from the Perry County Line to just 1.9 miles east of IL Route 153 near Eden; includes 230 pavement markers removal; 53,434 sq yds micro surfacing; 1,433 tons aggregate shoulders; 230 pavement markers; 86,580 ft paint pavement marking line; mobilization; traffic control and protection. (20 Working Days) (Job No. C-98-095-04) (8-00120-0000) (0.00% DBE)
107. Contract No. 66522 LaSalle County District 3  
Section (71,72)Q  
FAS Route 250 (IL 251)  
3.25 miles of 26 ft width pavement preservation on IL Route 251 from north of North 33rd Street to 0.5 mile north of I-80 at Troy Grove; includes 49,573 sq yds micro-surfacing, one pass; 39,942 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-93-172-04) (0-00845-3020) (0.00% DBE)
108. Contract No. 64999 Rock Island County District 2  
Section (81-3WS-1)X-1  
FAI Route 74/280 (I-74/I-280)  
Rehabilitation of the Weigh Station static scale platform including removal and replacement of the scale superstructure and structural steel, located at the Truck Weighing Station on eastbound Interstate 74 - Interstate 280, approximately two miles east of the Moline International Airport; includes removal of existing superstructure; 21 cu yds concrete; 31,870 lbs structural steel; 24 load cells; 6,740 lbs epoxy coated reinforcement bars; mobilization. (Completion Date: November 24, 2004) (Job No. C-92-065-04) (2-10860-0600) (0.00% DBE)
109. Contract No. 66524 LaSalle County District 3  
Section (3)Q-1  
FAP Route 68 (IL 23)  
4.02 miles of 24 foot width micro-surfacing, one-pass, removal and replacement of the raised reflective pavement markers and pavement striping located on IL Route 23, beginning at log mile 0.00 (U.S. Route 34) to log mile 4.05 (N. 41st Road) near Harding; includes 56,602 sq yds micro-surfacing; 47,757 ft paint pavement marking line; 265 pavement markers; mobilization; traffic control and protection. (15 Working Days) (Job No. C-93-174-04) (0-00845-3022) (0.00% DBE)
110. Contract No. 76826 Randolph County District 8  
Section 113RS-2  
FAS Route 1835 (IL 153)  
5.5 miles of 26 feet width of micro-surfacing on IL Route 153 from IL Route 13 in Coulterville to north of IL Route 154; includes 238 sq yds pavement patching; 86,580 sq yds micro-surfacing; 2,427 tons aggregate shoulders; 75,294 ft paint pavement marking; 366 raised reflective pavement markers; 366 raised reflective pavement markers removal; mobilization; traffic control and protection. (30 Working Days) (Job No. C-98-092-04) (8-00119-0000) (0.00% DBE)

111. Contract No. 76756 Madison County District 8  
Section 60-1HB-3I-1  
FAI Route 55 (I-55)  
Improvement consists of bridge deck scarification and microsilica overlay on the structure carrying Maple Road over Interstate 55 near Maple; includes 267 sq yds bituminous surface removal; 547 sq yds bridge deck grooving; 1,328 ft paint pavement marking-line; 214 sq ft pavement marking removal; 597 sq yds bridge deck microsilica concrete overlay; 597 sq yds concrete bridge deck scarification; 31 sq yds deck slab repair; mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-030-04) (0-00845-8004) (0.00% DBE)
112. Contract No. 66523 LaSalle County District 3  
Section (3)Q  
FAP Route 68 (IL 23)  
3.1 miles of 30 foot width micro-surfacing on IL Route 23 from U.S. Route 52 to SN 050-0045 north of Interstate 80 near Wedron; includes 53,856 sq yds micro-surfacing; 37,631 ft paint pavement marking line; 202 raised reflective pavement markers; 202 raised reflective pavement markers removal; mobilization; traffic control and protection. (15 Working Days) (Job No. C-93-173-04) (0-00845-3021) (0.00% DBE)
113. Contract No. 62819 Will County District 1  
Section 2004-078I  
FAI Route 55 (I-55 WEST FRONTAGE ROAD)  
1.40 miles of pavement preservation consisting of 20 ft width micro-surfacing on the I-55 West Frontage Road from Murphy Road to Lorenzo Road in Wilmington Township; includes 148 units grading and shaping shoulders; 16,503 sq yds micro-surfacing, 2 passes; 4,951 lbs crack filling; 268 tons aggregate shoulders; 2,410 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-91-334-04) (0-00845-1000) (0.00% DBE)
114. Contract No. 64A32 Ogle County District 2  
Section (38,39)RS-5  
FAP Route 742 (IL 2)  
1.98 miles of 24 ft and variable width micro-surfacing along IL Route 2 from Ogle Street in Grand Detour continuing north for 1.98 miles; includes 350 sq yds milling; 27,952 sq yds micro-surfacing; 10 tons leveling binder (machine method) SUPERPAVE; 60,174 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-141-04) (0-00845-2038) (SUPERPAVE) (0.00% DBE)
115. Contract No. 70440 Various Counties District 5  
Section D-5 PPP 2004-1  
Various Routes (VARIOUS)  
Bituminous cover and seal coat at various locations along various routes in the district; includes 62,863 gals bituminous materials (cover and seal coats); 3,143 tons seal coat aggregate; 282,682 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-95-086-04) (0-00845-5019) (0.00% DBE)
116. Contract No. 72931 Scott County District 6  
Section 19Q  
FAS Route 743 (HILLVIEW BLACKTOP)  
5.28 miles of bituminous surface treatment on Hillview Blacktop from IL Route 106 to 2 miles west of Glasgow; includes 26,840 gals bituminous materials (cover and seal coats); 1,007 tons seal coat aggregate; 37 sq yds temporary ramp; 782 tons leveling binder (machine method) SUPERPAVE; 660 sq yds patching; 20,963 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-008-05) (0-00845-6011) (SUPERPAVE) (0.00% DBE)
117. Contract No. 74066 Effingham-Marion Counties District 7  
Section D-7 PAVT. PRESERVATION 2005-1  
FAP Route 828 & FAS Route 2703 (MONTROSE & DIETERICH ETC.)  
Pavement preservation at 3 locations along Montrose Blacktop, Dieterich Blacktop and Kinmundy-Louisville Road from Marion to Jasper; includes 119,680 sq yds micro-surfacing, 1 pass; 114,505 ft paint pavement marking; mobilization; traffic control and protection. (30 Working Days) (Job No. C-97-087-04) (0-00845-7002, 0-00845-7003 & 0-00845-9014) (0.00% DBE)
118. Contract No. 98870 Pulaski-Jackson Counties District 9  
Section D-9 CONT. MAINT. FY05-3  
FAS Route 912 & FAP Route 726 (GORHAM SPUR ROAD & IL 37)  
Micro-surfacing at 2 locations on IL Route 37 southwest of Grand Chain and on Gorham Spur Road at Gorham; includes 84,411 sq yds micro-surfacing, 2 passes; 522 sq yds aggregate shoulders; 55,217 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-99-030-04) (0-00845-9005, 0-00845-9007 & 0-00845-9014) (3.00% DBE)

119. Contract No. 76750 Jersey-Calhoun-Greene Counties District 8  
Section 101I-5,19-I-1  
FAP Route 761 & FAS Route 754 (IL 108 & CH 1)  
Improvements consists of loading dock and entrance improvements to the Kampsville and Brussels Ferry. The improvements at Brussels include resurfacing, gates and pavement markings for the parking lot, and one new steel loading ramp. The improvements at the Kampsville Ferry include replacing two concrete pads and two new steel loading ramps. The projects are located at the Brussels Ferry 2.0 miles north of Grafton and the Kampsville Ferry in Kampsville; includes 75 sq yds patching; 168 sq yds bituminous surface removal butt-joint; 22 cu yds earth excavation; 82 ft guardrail removal; 2 sign removal; 5 relocate sign assembly; 115 sq ft median removal; 45 ft curb removal; 1,907 ft cable road guard removal; moving the light standard; 240 ft locating underground cable; 194 ft trench and backfill; 194 ft unit duct; 7 light pole foundation; 7 foundation removal; 20 ft expose and relocate ex cable; 645 tons bituminous binder course; 831 tons bituminous surface course; traffic barrier terminal; 1,550 ft cable road guard single strand; 4,115 ft thermoplastic pavement marking line; 2 concrete removal and boat ramp; 3 steel docks; 2 repair steel docks; mobilization. (35 Working Days) (Job No. C-98-025-04) (8-82614-0004) (0.00% DBE)
120. Contract No. 76773 Madison County District 8  
Section DIST 8 LS 2004-2  
FAP Route 310 (IL 255)  
Tree planting on Illinois Route 3 in Granite City from Bissell Road to Pontoon Road; includes planting of 150 trees; mobilization. (15 Working Days) (Job No. C98-046-04) (8-05100-1004) (10.00% DBE)
121. Contract No. 62613 Cook County District 1  
Section 1212-8-I  
FAU Route 2943 (BURNHAM AVENUE)  
Bridge joint repair on the existing structure carrying Burnham Avenue over State Street, Calument River, Baltimore & Ohio Railroad and Conrail/Indiana Harbor Belt Railroad in Burnham & Calument City; includes 88 cu yds concrete removal; 715 ft neoprene expansion joints; 11,860 lbs epoxy coated reinforcement bars; 184 ft paint pavement marking; 715 ft silicone joint sealer; 132 bar splicers; mobilization; traffic control and protection. (55 Working Days) (Job No. C-91-129-03) (0-00844-1043) x (0.00% DBE)  
[SEE MORE MISCELLANEOUS](#)



**RE-ADVERTISED SECTION**

Items 122 through 129 are being re-advertised for bids. Contractors and suppliers who requested plans and proposals for these items in connection with the previous advertisement should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for each CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)

**PAVEMENT SECTION**

- 122 Contract No. 97224 St. Clair County District 8  
Section 00-00006-00-PV (SHILOH)  
FAU Route 9266 (SOUTH MAIN STREET) Project M-CMM-5011(164)  
0.32 mile of widening, resurfacing, sidewalks, storm sewers and all other related work on South Main Street from just west of Shiloh Road to Selbert Road in Shiloh; includes 576 cu yds furnished excavation; 3.2 acre seeding; 864 lbs fertilizer nutrients; 3.2 acre mulch; 521 sq yds aggregate base course; 44 tons aggregate surface course; 1,308 gals bituminous materials; 22 tons aggregate; 694 sq yds PCC driveway pavement; 1,355 sq yds bituminous surface removal; 166 sq yds pavement patching; 3,267 ft storm sewers; 46 manholes; 25 inlets; 3,748 ft combination concrete curb and gutter; 8,189 ft temporary pavement marking; 11,198 ft thermoplastic pavement marking; 9 ft trench and backfill for electrical work; 100 tons aggregate for temporary access; 88 tons incidental bituminous surfacing, SUPERPAVE; 3,241 sq yds bituminous base course, SUPERPAVE 10"; 623 tons polymerized bituminous concrete surface course; 484 tons leveling binder (machine method); traffic control and protection; (85 Working Days) (Job No. C-98-332-03) (5-10028-0000) (10.00% DBE)

PREVIOUS LETTING: April 23, 2004 (Item 60)

- 123 Contract No. 74044 Richland-Lawrence Counties District 7  
Section INTERMT PAVT REHAB 2004-1  
FR 1327 & FR Route 000 (OLD US 50)  
Pavement rubblization and bituminous surface treatment at various locations along Old U.S. Route 50 from the U.S. Route 50/250 intersection east of Olney to just west of Sumner; includes 11,740 tons aggregate base course; 750 tons aggregate base repair; 144 tons aggregate surface course; 1,948 tons cover coat aggregate; 974 tons seal coat aggregate; 27 tons incidental bituminous surfacing; 76,733 sq yds rubblizing concrete pavement; 43,023 gals bituminous materials (prime coat); 38,721 gals bituminous materials (cover and seal coats); traffic control and protection; mobilization. (25 Working Days) (Job No. C-97-057-04) (0-00844-7013, 7-76904-0003) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 19)

- 124 Contract No. 94452 Jefferson County District 7  
Section 110Z,110Y,RS  
FAU Route 8736 (IL 37) Project ACM-8736(4)  
2.33 kilometers of pavement patching, bituminous surface removal, variable width bituminous base course widening, variable width bituminous concrete resurfacing, bituminous and aggregate shoulders, curb and gutter removal and replacement, sidewalks and traffic signal modernization of Illinois Route 37 in Mt. Vernon from Oakland Avenue northerly to Loop Road (TR 298) for the construction of a bi-directional left turn lane. Also included is the removal of a single span bridge (structure no. 041-0094) over a unnamed tributary to Casey Creek and the replacement with a 3.05m x 2.44m concrete box culvert; includes special waste plans and report; 6 betx-pnas soil analysis; 2 soil disposal analysis; 3 lead and ph soil analysis; 6 lead tcp soil analysis; 401 raised reflective pavement markers; full-actuated controller and cabinet; 33 shade trees; 50 intermediate trees; 1,249 unit tree removal; 23,617 cu m earth excavation; 725 cu m channel excavation; 13,788 sq m subbase granular material; 2,052 sq m aggregate base course; 1,172 sq m bituminous base course; 2,903 sq m PCC pavement; 7,300 sq m PCC driveway pavement; 3,174 sq m PCC sidewalk; 14,961 sq m bituminous surface removal; 4,226 sq m pavement removal; 11,244 sq m driveway pavement removal; 3,585 m gutter removal; 1,440 sq m sidewalk removal; 2,916 sq m paved shoulder removal; 1,178 sq m pavement patching; 1,718 sq m bituminous shoulders; 33 cu m concrete removal; 572 cu m structure excavation; 78 cu m concrete structures; 37,960 kg reinforcement bars; 49 sq m temporary sheet piling; 215 cu m concrete box culverts; 2,696 m storm sewers; 3,129 m combination concrete curb and gutter; 6,856 m thermoplastic pavement marking line; 1,383 m electric cable in conduit; 19 m concrete foundations; 10,052 sq m bituminous base course, SUPERPAVE; 2,596 m tons bituminous concrete surface course, SUPERPAVE, Mix D, N50; 1,033 m tons bituminous concrete binder course, SUPERPAVE, IL-19.0, N70; 1,113 m tons leveling binder, SUPERPAVE, N50; 9 signal heads; traffic control and protection; mobilization. (210 Working Days) (Job No. C-97-050-96) (7-01420-0100, 7-73890-0100) (SUPERPAVE) (3.00% DBE)

PREVIOUS LETTING: April 23, 2004 (Item 120)

PREVIOUS LETTING: June 11, 2004 (Item 205)

- 125      Contract No. 70394                      Macon-Moultrie-Piatt Counties                      District 5  
Section (139,140)RS-3  
FAP Route 323    (US 36)  
11.3 miles of 24 feet and variable width of bituminous resurfacing on U.S. Route 36 from Maryland Street in Decatur to 1.8 miles west of Illinois Route 32; includes 458 sq yds patching; 862 sq yds bituminous surface removal-butt joint; 149,424 sq yds bituminous surface removal; 11,657 tons bituminous concrete surface course, SUPERPAVE, Mix C; 984 sq yds bituminous shoulders; 451 tons incidental bituminous surfacing; 2,479 tons aggregate shoulders; 103,379 ft paint pavement marking line; 296 ft thermoplastic pavement marking line; 570 pavement markers; traffic control and protection; mobilization. (Completion Date: November 15, 2004 Plus 5 Working Days) (Job No. C-95-038-04) (5-52230-0000) (SUPERPAVE) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 120)

**MISCELLANEOUS SECTION**

- 126      Contract No. 93369                      Schuyler County                      District 6  
Section 02-00068-01-DR  
FAS Route 1581 / FAS Route 581    (CH 13 / CH 11)    Project ER-2-1(129)  
Construction consists of permanent restoration with stone riprap at two locations, Horney Branch Creek, 4.5 miles southeast of Rushville and Cedar Creek, 1.0 miles south of Huntsville; includes 0.54 acre seeding; 1,865 tons stone riprap, Class A4; 3,533 tons stone riprap, Class A6; 2,620 tons stone riprap, Class A7; traffic control; clearing and grubbing. (50 Working Days) (Job No. C-96-221-03) (6-10182-0000) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 104)

- 127      Contract No. 74022                      Lawrence County                      District 7  
Section 2T  
FAS Route 1806    (IL 250)  
Storm sewer removal and replacement along Illinois Route 250 in Bridgeport; includes 16 cu yds trench backfill; 1,176 ft grading and shaping ditches; 0.2 acre seeding; 7 temporary ditch checks; 4 inlet and pipe protection; 7.6 tons subbase granular material; 38 tons aggregate surface course; 13 tons aggregate shoulders; 1,233 ft storm sewer removal; 1,234 ft storm sewers; 2 inlets; traffic control and protection; mobilization. (30 Working Days) (Job No. C-97-025-04) (0-03514-7001) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 101)

- 128      Contract No. 72864                      Sangamon County                      District 6  
Section D-6 DRAINAGE CORRECTION 2004  
FAP Route 662    (IL 4)  
Drainage correction along Lick Creek located at the Panther Creek Country Club, from Mathers Gun Club Road to Panther Creek Drive in Springfield; includes 205 units tree removal; 7,944 ft temporary fence; 2,623 cu yds earth excavation; 621 lbs fertilizer; 2.3 acres seeding; 2.3 acres mulch; 4,950 ft perimeter erosion barrier; 15 inlets and piper protection; 150 sq ft concrete sidewalk; mobilization; traffic control complete. (Completion Date: February 28, 2005 Plus 10 Working Days) (Job No. C-96-564-04) (6-74670-0004) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 99)

- 129      Contract No. 76764                      St. Clair County                      District 8  
Section D-8 SUMP CLEANING 2004-1  
Various Routes    (VARIOUS)  
Cleaning the sump at the Pump Station located at Missouri Avenue and 25th Street in East Saint Louis; includes cleaning sump pumps at 2 locations; mobilization. (15 Working Days) (Job No. C-98-039-04) (0-03514-8001,0-03514-8002 & 0-03514-8004) (0.00% DBE)

PREVIOUS LETTING: June 11, 2004 (Item 180)

Item 5P is NOT included in the July 30, 2004 Letting but is expected to be included in an undetermined, future letting. It is being published to allow for review and inspection by potential bidders and suppliers. It is NOT for bidding purposes at this time

- 5P. Contract No. 76561 Madison County District 8  
Section 119BR  
FAU Route 9105 (SALISBURY STREET) Project HPD-1481(2)  
Reconstruction and rehabilitation of the McKinley Bridge across the Mississippi River in Venice; includes 36,546 sq yds geotechnical fabric; 20,066 tons course aggregate; 343 sq yds concrete removal; 1,709 cu yds earth excavation; 655 cu yds structure excavation; 498 cu yds cofferdam excavation; 687 cu yds porous granular embankment; 49,489 ft steel piles; 2,059,745 lbs epoxy coated reinforcement bars; 9,884 cu yds concrete; 7,279 sq yds bridge seat sealer; 125 floating bearings; 118 elastomeric bearing assemblies; 41,392 lbs erecting structural steel; 66,200 stud shear connectors; 226,008 lbs structural steel repairs; 7,453 rivet removal and replacement; 68 floor drains; 709 ft expansion joints; 43,282 sq yds composite grid deck system; 4,817 mechanical splicers; 16,645 sq yds bridge deck grooving; traffic control protection; mobilization. (265 Working Days) (Job No. C-98-023-02) (8-86080-0200) (15.00% DBE)

Items 6P and 7P were previously advertised as Review and Inspection projects only. Bids are now being accepted on Items 6P and 7P for the July 30, 2004 Letting.

**NOTICE – PRE-QUALIFICATION WAIVER**

Pre-qualification of bidder with the Department of Transportation is not required on the BELOW item; however, prospective bidders must comply with Paragraph 3d of the Invitation For Bid in the Transportation Bulletin

- 6P. Contract No. 68231 Peoria-Tazewell Counties District 4  
Section D4 I-74 SUPPLY CONTRACT 2005  
FAI Route 74 (I-74) Project IM-74-4(144)89  
Supplying high mast poles for lighting located along Interstate 74 from west of Sterling Avenue to east of Washington Street in Peoria; includes 164 High Mast Light Towers (material only). (Completion Date: October 31, 2006) (Job No. C-94-042-02) (4-00022-1300) (15.00% DBE)

**NOTICE – PRE-QUALIFICATION WAIVER**

Pre-qualification of bidder with the Department of Transportation is not required on the BELOW item; however, prospective bidders must comply with Paragraph 3d of the Invitation For Bid in the Transportation Bulletin

- 7P. Contract No. 68408 Peoria-Tazewell Counties District 4  
Section D4 I-74 SUPPLY CONTRACT 2005-1  
FAI Route 74 (I-74) Project IM-74-4(147)89  
Supply luminaires for lighting along Interstate 74 from west of Sterling Avenue to east of Washington Street in Peoria; includes 958 high mast luminaires, 400w high pressure sodium; 272 underpass luminaires, 100w high pressure sodium; 486 tunnel luminaires, 400w high pressure sodium; 29 tunnel luminaires, 100w high pressure sodium; (Completion Date: October 31, 2006) (Job No. C-94-084-04) (4-00022-1200) (15.00% DBE)

STATE OF ILLINOIS  
Department of Transportation  
Division of Aeronautics

---

This Bulletin constitutes official notification to Contractors of the intention to receive bids for Airport related work. The Transportation Bulletin is available on the Department's Internet website at <http://www.dot.state.il.us>. The following phone numbers and e-mail address are available if assistance is needed:  
Phone: 217/782-7806; Fax: 217/785-1141; TDD: 217/524-4875;  
E-mail: [duncanjr@nt.dot.state.il.us](mailto:duncanjr@nt.dot.state.il.us).

INVITATION FOR BIDS

1. TIME AND PLACE OF OPENING PROPOSALS: Sealed bids, subject to the conditions contained herein, will be received by the Department of Transportation at the Auditorium in the Harry R. Hanley Building, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois, until 10:00 A.M. prevailing time, July 30, 2004. These bids will, at that time, be publicly opened and read for furnishing all labor and materials, and performing all work for the Project(s) listed and defined in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics.
2. INSTRUCTIONS TO BIDDERS:
  - a. Plans and Contract Documents. Plans and Contract Documents for those Project(s) specified in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics may be examined and reviewed at the following offices:
    - (1) Department of Transportation, Division of Aeronautics, One Langhorne Bond Drive, Capital Airport, Springfield, Illinois.
    - (2) Department of Transportation, Harry R. Hanley Building, Plans and Contracts Office, Room 323, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois.
    - (3) Office of the consulting engineer(s).
  - b. PLANS AND CONTRACT DOCUMENTS MAY BE OBTAINED FROM THE DEPARTMENT OF TRANSPORTATION, BUREAU OF DESIGN AND ENVIRONMENT, HARRY R. HANLEY BUILDING, SPRINGFIELD, ILLINOIS. PLANS AND CONTRACT DOCUMENTS CANNOT BE OBTAINED THROUGH THE DIVISION OF AERONAUTICS. A charge of \$35.00 (nonrefundable) is required in the form of a Check (currency will not be accepted) made payable to the Treasurer, State of Illinois, for each section of work for the requested Plans and Contract Documents. No refunds will be made for Plans and Contract Documents returned.

Contractors wanting to bid must submit the properly completed "Request for Authorization to Bid/or Not for Bid Status" (BD 124INT) and the properly completed ORIGINAL "Affidavit of Availability" (BC 57) to Room 322 or 323 no later than 4:30 p.m. prevailing time, three (3) days prior to letting date. The Authorization to Bid request cut-off date is 4:30 p.m. prevailing time, July 27, 2004.

- c. Each bid shall be accompanied by one (1) copy of a Bid Bond on Form BD 356B in the amount, which is not less than five (5) percent of the aggregate amount of the bid.
- d. Pre-Qualification Rating. The Illinois Department of Transportation pre-qualification ratings and other applicable evidence of competency of bidders to perform the work contemplated will be utilized for all Service Bulletin items. This pre-qualification rating will be established on the basis of a Financial Statement and Experience Questionnaire.
- e. Requirements for Corporations outside the State of Illinois. Before any Contract is executed, a Corporation from another State must conform to the Statutes of the State of Illinois, and may be asked to furnish a copy of the certificate from the Secretary of State, State of Illinois, showing that such foreign corporation is authorized to do business in the State of Illinois.
- f. Civil Rights Act of 1964. The Illinois Department of Transportation, Division of Aeronautics, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-assisted programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds or race, color, or national origin in consideration for an award.

In a case in which a bidder or prospective contractor or proposed subcontractor who has participated in a previous contract or subcontract subject to the equal opportunity clause has not filed a compliance report due under applicable instructions, such bidder, prospective contractor, or proposed subcontractor shall submit a compliance report prior to the award of the proposed contract or subcontract. When a determination has been made to award a contract to a specific contractor, such contractor shall prior to award, furnish such other pertinent information regarding his own employment policies and practices as well as those of his proposed subcontractors as the Sponsor, or the Executive Vice Chairman of the President's Committee may require.

For any contract or subcontract for \$50,000.00 or more, and having 50 or more employees, the contractor or subcontractor will be required to maintain a written Affirmative Action Plan.

g. Special Requirements.

- (1) Payment to Labor. The successful bidder will be required to pay to the laborers, workmen, mechanics, and other employees for the work under the contracts, not less than the general prevailing wage for each craft, trade or occupation, and not less than the minimum wage rates as shall be established by the U. S. Secretary of Labor for federally assisted projects and by the Illinois Department of Labor for state/local projects.
- (2) Affirmative Action Requirements - Equal Employment Opportunity. Various contractor, union and minority organizations have prepared specific plans for Equal Employment Opportunity. Should such a plan or plans apply to the proposed project(s) listed below, the Bid Conditions will be included in the Contract Document for that project, and all bidder's, prospective contractors and/or subcontractors shall be required to comply with any and all provisions set forth therein.

- h. Specifications. The proposed work is to be constructed in accordance with the requirements of the Illinois Standard Specifications for Construction of Airports, dated January, 1985, and the Special Provisions specified in the proposal. Copies of the Illinois Standard Specifications for Construction of Airports may be obtained by applying to the Department of Transportation, Division of Aeronautics, Bureau of Engineering, Design Section, and Capital Airport/One Langhorne Bond Drive, Springfield, Illinois 62707-8415. The order should be accompanied by a check made payable to the Division of Aeronautics in the amount of \$10.00 for each copy ordered.

3. Proposed Work:

1A Rantoul National Aviation Center

Rantoul, Illinois

Champaign County

Ill. Proj. TIP-3310

Contract No. RA012

Install Runway 9/27 PLASI and REILs; Install Runway 18/36 Windcones and Supplemental Windcones; Install Guidance Signs and Beacon - which includes the following major work items: 3 Each L-806 Wind Cone 8' Lighted; 25,100 L.F. UG Cable in UD; 1 Each Vault Modifications; 1 Each 15 KW Regulator Style 1; 2,400 L.F. 4" Directional Bore; 8 Each Taxi Guidance Sign; 2 Pair REILs; 2 Each PLASI; 3 Each Electrical Handhole 4'; 1 Each Segmented Circle; 0.5 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 0.0%)

2A Pontiac Municipal Airport

Pontiac, Illinois

Livingston County

Ill. Proj. PNT-3301

AIP No. 3-17-0148-B5

Contract No. PO014

Construct a 3-Inch Bituminous Overlay on Runway 6/24 - which includes the following major work items: 76 Each Adjust Stake Mounted Light; 18 Each Adjust Base Mounted Light; 2 Each Adjust PLASI; 1,700 C.Y. Shoulder Adjustment; 8,235 Ton Bituminous Surface Course; 26,032 S.F. Pavement Marking-Waterborne; 7 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 10.0%)

- 3A Lake in the Hills Airport  
Lake in the Hills, Illinois  
McHenry County  
Ill. Proj. 3CK-3234  
AIP No. 3-17-0112-B5  
Contract No. LK003  
Install Perimeter Fence - Phase 1 - which includes the following major work items: 19 Each Clearing Trees 0-2.5' Butt Dia.; 4.1 Acre Clearing & Grubbing; 4,361 C.Y. Unclassified Excavation; 2,236 L.F. Silt Fence; 2,279 S.Y. Riprap Gradation No.4; 8,062 L.F. Class E Fence 8'; 5 Each Class E Gate 20'  
Pre-Bid meeting: N/A  
(DBE 0.0%)
- 4A St. Louis Downtown Airport  
Sauget, Illinois  
St. Clair County  
Ill. Proj. CPS-3328  
AIP No. 3-17-0039-B15  
Contract No. SD045  
Reconstruct Taxiway Alpha - which includes the following major work items: 1,400 L.F. 1/C #8 5KV UG Cable in UD; 4 Each MITL-Stake Mounted; 11 Each Relocate Base Mounted Light; 1 L.S. Haul Route; 497 C.Y. Unclassified Excavation; 3,780 S.Y. Shoulder Adjustment; 4,692 S.Y. Soil Processing-12"; 1,213 Ton Crushed Aggregate Base; 4,692 S.Y. 10" PC Concrete Pavement; 3,880 S.F. Pavement Marking-Waterborne; 73 Ton Lime Slurry; 7,270 S.Y. Existing Pavement Removal; 1.3 Acre Seeding  
Pre-Bid meeting: N/A  
(DBE 8.0%)
- 6A Coles County Memorial Airport  
Mattoon, Illinois  
Coles County  
Ill. Proj. MTO-3113  
Contract No. CO050  
Install Perimeter Fence - which includes the following major work items: 0.28 Acre Clearing & Grubbing; 6,190 L.F. Remove Class C Fence; 6,240 L.F. Class E Fence 10'; 2 Each Class E Gate 24'; 1 Each Electric Gate 16'; 0.3 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 0.0%)

7A Casey Municipal Airport

Casey, Illinois

Clark County

Ill. Proj. 1H8-3383

AIP No. 3-17-0014-B7

Contract No. CS001

Overlay Airport Entrance Road - which includes the following major work items: 1,166 Ton Bituminous Surface Course; 2,028 Gal Bituminous Prime Coat; 1 L.S. Pavement Preparation; 133 S.Y. Butt Joint Construction; 195 Ton Aggregate Shoulders; 320 S.F. Pavement Marking

Pre-Bid meeting: N/A

(DBE 2.0%)

8A Greater Rockford Airport

Rockford, Illinois

Winnebago County

Ill. Proj. RFD-3307

Contract No. RO006

Expand Terminal Parking Lot, Phase II - which includes the following major work items: 9 Each Type A Area Light Pole w/4 Fixtures; 1,460 L.F. 2" Steel Duct, Direct Bury; 7,545 C.Y. Unclassified Excavation; 15,138 S.Y. Separation Fabric; 15,100 S.Y. Crushed Aggregate Base Course; 3,905 Ton Bituminous Surface Course; 4,542 Gal Bituminous Prime Coat; 3,855 S.F. Pavement Marking-Waterborne; 6 Each Manhole 6'; 575 L.F. 12" RCP, Class IV; 1 L.S. Box Culvert Grating; 8,910 S.Y. Tar Emulsion Seal Coat

Pre-Bid meeting: N/A

(DBE 3.0%)

9A Galesburg Municipal Airport

Galesburg, Illinois

Knox County

Ill. Proj. GBG-3384

AIP No. 3-17-0047-B7

Contract No. GA003

Apply Porous Friction Course to Runway 3/21 - which includes the following major work items: 99,808 S.Y. Porous Friction Course; 2,375 S.Y. Butt Joint Construction; 25,000 L.F. Bituminous Crack Repair; 29,943 Gal Bituminous Tack Coat; 110,000 S.F. Pavement Marking; 100 S.Y. Sodding; 1 L.S. Traffic Maintenance; 1 L.S. Pavement Preparation; 966 S.Y. Shoulder Restoration

Pre-Bid meeting: N/A

(DBE 11.3%)



10A Mt. Sterling Municipal Airport

Mt. Sterling, Illinois

Brown County

Ill. Proj. I63-3192

AIP No. 3-17-0147-B2

Contract No. MS001

Construct, Light and Mark a 1,905' Runway 18/36 Extension - which includes the following major work items: 5,220 L.F. 1/C #8 5KV UG Cable in UD; 1 L.S. Install Electrical Equipment; 16 Each MIRL, Stake Mounted; 10.4 Acre Clearing & Grubbing; 78,000 C.Y. Unclassified Excavation; 524 Ton By Product Lime; 18,825 S.Y. Lime Modified Subgrade 12"; 36 Each Ditch Check; 10,410 L.F. Class C Fence; 12,899 L.F. Remove Class C Fence; 2,769 Ton Bituminous Base Course; 6,478 Ton Crushed Aggregate Base Course; 1,640 Ton Bituminous Surface Course; 12,811 Gal Bituminous Material; 13,855 S.F. Pavement Marking Removal; 891 L.F. RCP, Class IV; 4,069 L.F. 6" Perforated Underdrain w/Sock; 28.2 Acre Seeding & Mulching  
Pre-Bid meeting: Airport Managers Office on July 21, 2004, at 10:00am  
(DBE 10.0%)

11A Whiteside County Airport

Sterling, Illinois

Whiteside County

Ill. Proj. SQI-3382

Contract No. WH005

Construct T-Hangar Access Taxiway, Phase II - which includes the following major work items: 3,580 C.Y. Unclassified Excavation; 5,370 S.Y. Separation Fabric; 530 L.F. Class E Fence 4'; 1,790 C.Y. Porous Granular Embankment; 5,370 S.Y. Crushed Aggregate Base Course 8"; 680 Ton Bituminous Surface Course; 200 L.F. 12" RCP, Class IV; 460 L.F. 6" Perforated Underdrain w/Sock; 3 Each Inlet-Type A; 0.50 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 7.0%)

12A Kewanee Municipal Airport

Kewanee, Illinois

Henry County

Ill. Proj. EZI-3363

Contract No. KE006

Snow Removal Equipment Building Sitework - which includes the following major work items: 1,283 C.Y. Unclassified Excavation; 266 Ton Oversize Aggregate; 177 Ton Crushed Aggregate Base Course; 667 S.Y. 7" PCC Pavement; 287 L.F. 4" Perforated Underdrain w/Sock; 0.94 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 4.0%)

13A Mt. Carmel Municipal Airport

Mt. Carmel, Illinois

Lawrence County

Ill. Proj. AJG-3324

AIP No. 3-17-0073-B11

Contract No. MC020

Construct Corporate Hangar Taxiway - which includes the following major work items: 980 L.F. #8 5KV UG Cable in UD; 185 L.F. 2 Way Concrete Encased Duct; 6 Each MITL-Stake Mounted; 700 C.Y. Unclassified Excavation; 3,400 S.Y. Soil Processing 12"; 100 L.F. Class E Fence 4'; 1 Each Class E Gate 20'; 450 Ton Bituminous Base Course; 1,300 Ton Crushed Aggregate Base Course; 270 Ton Bituminous Surface Course; 64 L.F. 12" RCP, Class IV; 1,091 L.F. 4" Perforated Underdrain w/Sock; 1 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 6.0%)

14A Southern Illinois Airport

Carbondale, Illinois

Jackson County

Ill. Proj. MDH-3370

Contract No. SO073

Construct Maintenance Ramp Expansion - which includes the following major work items: 8 Each MITL-Stake Mounted; 1,600 C.Y. Unclassified Excavation; 8,380 S.Y. Soil Processing 12"; 2,175 Ton Bituminous Base Course; 3,400 Ton Crushed Aggregate Base Course; 730 Ton Bituminous Surface Course; 45 Each Tie Down; 975 L.F. 4" Perforated Underdrain w/Sock; 0.9 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 6.5%)

15A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3354

Contract No. QU088

FBO/Tower Road Reconstruction - which includes the following major work items: 383 C.Y. Unclassified Excavation; 550 Ton Crushed Aggregate Base Course; 1,362 S.Y. 7" PCC Pavement; 1,484 S.Y. Remove PCC Pavement; 1,096 L.F. 4" Perforated Underdrain w/Sock; 0.25 Acre Seeding  
Pre-Bid meeting: N/A  
(DBE 13.0%)

29A Decatur Airport  
Decatur, Illinois  
Macon County  
Ill. Proj. DEC-3315  
Contract No. DE064

Reconstruction of the South Perimeter Road - which includes the following major work items: 313 L.F. Sand Mix Crack Repair; 405 Ton Bituminous Surface Course; 2,310 S.Y. Porous Friction Course 5/8"; 809 Gal Bituminous Tack Coat; 2,310 S.Y. Tar Emulsion Seal Coat; 100 C.Y. Topsoiling (From Off Site); 0.4 Acre Seeding  
Pre-Bid meeting: N/A  
(DBE 10.0%)

NOTE: The following projects (5A, 16A, 17A, 18A, 19A, 20A, 21A, 22A, 23A, 24A, 25A, 27A & 28A) are currently unfunded but are actively seeking federal discretionary funding. The award period for these projects is 75 days and expires on October 13, 2004. At that point, the contractor may request, in writing, an award extension of 86 days, which will expire on January 7, 2005. At this point, the contractor may request a second and final award extension, in writing, of 131 days which will expire on May 18, 2005. There is no guarantee that any or all of these projects will be awarded.

5A Palwaukee Municipal Airport  
Prospect Heights, Illinois  
Cook County  
Ill. Proj. PWK-2792  
AIP No. 3-17-0018-B34  
Contract No. PA045

Reconstruct and Widen Runway 12/30 - which includes the following major work items: 56,000 L.F. Cable; 22,625 L.F. Duct/Conduit; 42 Each MITL-Base Mounted; 36 Each MIRL-Base Mounted; 14 Each Taxi Guidance Sign; 2 Pair REILS; 1 Each PAPI (L-880 System); 47,866 C.Y. Unclassified Excavation; 6,745 C.Y. Porous Granular Embankment; 18,650 S.Y. Crushed Aggregate Base Course-7"; 10,555 Ton Bituminous Surface Course; 17,000 S.Y. Pavement Milling/Removal; 64,450 S.F. Pavement Marking-Waterborne; 4,900 L.F. Storm Sewer; 12,950 L.F. 6" Perforated Underdrain w/Sock; 53 Each Storm Sewer/Underdrain Structure; 1 L.S. Building Demolition-Site A  
Pre-Bid meeting: N/A  
(DBE 11.5%)

16A Vermilion County Airport

Danville, Illinois

Vermilion County

Ill. Proj. DNV-3380

AIP No. 3-17-0032-B8

Contract No. VE043

Overlay Runway 3/21; Install HIRL - which includes the following major work items: 12,874 L.F. 1/C #8 5KV UG Cable in UD; 38 Each HIRL, Base Mounted; 42 Each Remove Base Mounted Light; 20 Each Relocate Base Mounted Light; 14,100 S.Y. Shoulder Adjustment; 12,800 L.F. Silt Fence; 7,000 L.F. Clean & Seal Bituminous Cracks; 400 Ton Oversize Aggregate; 14,910 Ton Bituminous Surface Course; 550 Ton Bituminous Surface Course-Jt. Rep.; 736 S.Y. Remove Bituminous Pavement; 72,605 S.Y. Porous Friction Course 5/8"; 26,300 Gal Bituminous Tack Coat; 87,000 S.F. Pavement Marking-Waterborne; 3 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 11.5%)

17A St. Louis Regional Airport

East Alton, Illinois

Madison County

Ill. Proj. ALN-3306

AIP No. 3-17-0002-XX

Contract No. SR082

Construct Access Taxiway and Expand Apron - which includes the following major work items: 14,355 L.F. 1/C #8 5KV UG Cable in UD; 469 L.F. 4-Way Concrete Encased Duct; 20 Each MITL-Stake Mounted; 5,951 C.Y. Unclassified Excavation; 13,067 S.Y. Separation Fabric; 4,166 Ton Oversize Aggregate; 3,659 Ton Crushed Aggregate Base Course; 12,871 S.Y. 14" PCC Pavement; 4,846 S.Y. Remove PCC Pavement; 32,083 S.F. Pavement Marking-Waterborne; 29,260 S.F. Pavement Marking Removal; 339 L.F. 18" RCP, Class IV; 1,480 L.F. 6" Perforated Underdrain w/Sock; 5 Acre Seeding & Mulching  
Pre-Bid meeting: N/A  
(DBE 6.0%)

**Note: Items 18A and 19A may be bid in Combination**

18A Quincy Regional Airport

Quincy, Illinois

Adams County

Ill. Proj. UIN-3338

AIP No. 3-17-0085-xx

Contract 1

Contract No. QI052

Realignment and Widening of Taxiway A - which includes the following major work items: 4,910 L.F. 1/C #8 5KV UG Cable in UD; 80 Each MITL-Stake Mounted; 16 Each MITL-Base Mounted; 12,533 C.Y. Unclassified Excavation; 523 Ton By Product Lime; 12,092 S.Y. Soil Processing 16"; 2,545 L.F. Silt Fence; 1,334 Ton Bituminous Base Course; 7,017 Ton Crushed Aggregate Base Course; 2,618 Ton Bituminous Surface Course; 11,726 S.Y. 10" PCC Pavement; 3,526 Gal Bituminous Tack Coat; 961 L.F. RCP, Class IV; 3 Each Inlet; 5 Each Manhole; 10,013 S.Y. Remove Pavement; 8 Acre Seeding & Mulching

Pre-Bid meeting: Airport Managers Office on July 22, 2004, at 2:00pm (DBE 6.0%)

19A Quincy Regional Airport

Quincy, Illinois

Adams County

Ill. Proj. UIN-3338

AIP No. 3-17-0085-xx

Contract 2

Contract No. QI053

Construction of Crossover Taxiway F - which includes the following major work items: 85 L.F. 4 Way Concrete Encased Duct; 18 Each MITL-Stake Mounted; 1,381 C.Y. Unclassified Excavation; 211 Ton By Product Lime; 4,921 S.Y. Soil Processing 16"; 1,165 Ton Bituminous Base Course; 1,378 Ton Crushed Aggregate Base Course; 4,731 S.Y. 10" PCC Pavement; 2 Each Inlet; 516 L.F. 15" RCP, Class IV; 1 Acre Seeding & Mulching

Pre-Bid meeting: Airport Managers Office on July 22, 2004, at 2:00pm (DBE 6.0%)

20A Capital Airport

Springfield, Illinois

Sangamon County

Ill. Proj. SPI-3345

AIP No. 3-17-0096-xx

Contract No. CA101

Rehabilitate the Air Carrier Ramp - which includes the following major work items: 6,500 L.F. 1/C #8 5KV UG Cable in UD; 800 L.F. 4 Way Concrete Encased Duct; 4 Each Electrical Handhole; 16 Each MITL-Base Mounted; 3,450 C.Y. Unclassified Excavation; 1,400 C.Y. Subgrade Undercut; 32,170 S.Y. Crushed Aggregate Base Course; 31,230 S.Y. PCC Pavement; 32,230 S.Y. Remove PCC Pavement; 785 L.F. RCP, Class IV; 2,400 L.F. 4" Perforated Underdrain w/Sock; 7 Each Inlet-Special; 3 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 5.0%)

21A Greater Peoria Regional Airport

Peoria, Illinois

Peoria County

Ill. Proj. PIA-3343

AIP No. 3-17-0080-xx

Contract No. PE083

Extend Taxiway A to Runway 13/31 (Phase 1); Expand Apron and Construct New Connecting Taxiway - which includes the following major work items: 14,420 L.F. 5 KV Cable in UD; 422 L.F. 4 Way Concrete Encased Duct; 89 Each MITL-Base Mounted; 13 Each Taxi Guidance Sign; 86 Each Remove Base Mounted Lights; 53,118 C.Y. Unclassified Excavation; 15,951 S.Y. Separation Fabric; 14,157 Ton Bituminous Base Course; 36,250 S.Y. Crushed Aggregate Base Course; 4,660 Ton Bituminous Surface Course; 18,609 S.Y. Remove Bituminous Pavement; 15,660 S.Y. 18" PCC Pavement; 12,811 Gal Bituminous Tack Coat; 16,273 S.F. Pavement Marking; 592 L.F. RCP, Class IV; 5,659 L.F. 4" Perforated Underdrain; 17 Acre Seeding & Mulching  
Pre-Bid meeting: Airport Managers Office on July 19, 2004, at 11:00am (DBE 5.0%)

22A Robinson Municipal Airport

Robinson, Illinois

Crawford County

Ill. Proj. RSV-3334

AIP No. 3-17-0086-B8

Contract No. RB013

Widen Runway 9/27 to 100' - which includes the following major work items: 61 Each Relocate Stake Mounted Light; 2 L.S. Relocate REILs; 2 Each Relocate PLASI; 6,019 C.Y. Unclassified Excavation; 3,342 C.Y. Off-Site Borrow Excavation; 666 Ton By Product Lime; 16,266 S.Y. Soil Processing 16"; 7,497 Ton Bituminous Base Course; 8,011 Ton Crushed Aggregate Base Course; 1,602 Ton Bituminous Surface Course; 6,675 Gal Bituminous Tack Coat; 38,605 S.F. Pavement Marking-Waterborne; 715 C.Y. Porous Backfill; 9,150 L.F. 4" Perforated Underdrain w/Sock; 12 Acre Seeding & Mulching  
Pre-Bid meeting: Airport Managers Office on July 20, 2004, at 2:00pm (DBE 8.0%)

23A Morris Municipal Airport

Morris, Illinois

Grundy County

Ill. Proj. C09-3358

AIP No. 3-17-0071-B11

Contract No. MR017

Construct Grading and Drainage for 1,000 ft. long Runway Extension - which includes the following major work items: 49,721 C.Y. Unclassified Excavation; 10,327 C.Y. Borrow Excavation; 1 L.S. Temporary Threshold; 14,770 S.Y. Crushed Aggregate Base Course 6"; 4,806 S.F. Pavement Marking-Waterborne; 104 L.F. 36" RCP, Class III; 4,810 L.F. 6" Perforated Underdrain w/Sock; 20.8 Acre Seeding & Mulching  
Pre-Bid meeting: N/A (DBE 11.0%)

24A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3339

AIP No. 3-17-0068-xx

Contract No. QU089

Construct East Side Perimeter Road - which includes the following major work items: 178 L.F. 1-Way Concrete Encased Duct; 8,636 C.Y. Unclassified Excavation; 26,707 S.Y. Separation Fabric; 583 L.F. Class E Fence 10'; 3,514 L.F. Temporary Fence; 3,911 Ton Bituminous Base Course; 13,050 Ton Crushed Aggregate Base Course; 2,347 Ton Bituminous Surface Course; 2,156 Remove Bituminous Pavement; 400 Ton Oversize Aggregate; 10,606 Gal Bituminous Prime Coat; 177 L.F. RCP; 613 S.Y. Remove Riprap; 10.7 Acre Seeding

Pre-Bid meeting: N/A

(DBE 5.0%)

25A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3348

AIP No. 3-17-0068-xx

Contract No. QU090

Construct Southeast Service/Perimeter Road - which includes the following major work items: 750 L.F. 1/C #2/0 600V UG Cable; 1,842 C.Y. Unclassified Excavation; 5,079 S.Y. Separation Fabric; 106 L.F. Class E Fence 10'; 1 Each Electric Gate 16'; 750 Ton Bituminous Base Course; 2,490 Ton Crushed Aggregate Base Course; 450 Ton Bituminous Surface Course; 2,032 Gal Bituminous Prime Coat; 1 L.S. Security Equipment; 2 Acre Seeding

Pre-Bid meeting: N/A

(DBE 5.0%)

27A DuPage Airport

West Chicago, Illinois

DuPage County

Ill. Proj. DPA-3332

AIP No. 3-17-0017-B16

Contract No. DU069

Taxiway Echo Rehabilitation - Including Overlay, Widening & Relocation of portions of Taxiway Echo - which includes the following major work items: 19,965 L.F. 1/C #8 5KV UG Cable in UD; 261 L.F. Concrete Encased Duct; 117 Each MITL-Base Mounted; 17 Each Taxi Guidance Sign; 113 Each Remove Base Mounted Light; 21,965 C.Y. Unclassified Excavation; 6,450 L.F. Silt Fence; 1,260 Ton Bituminous Base Course; 33,215 S.Y. Crushed Aggregate Base Course-4"; 4,975 S.Y. Crushed Aggregate Base Course-10"; 1,645 Ton Bituminous Surface Course; 31,350 S.Y. Remove Bituminous Pavement; 22,195 S.Y. 8" PCC Pavement; 10,060 S.Y. 10" PCC Pavement; 36,645 S.F. Pavement Marking-Waterborne; 36,845 S.F. Pavement Marking Removal; 2,500 RCP, Class IV; 8,815 L.F. 6" Perforated Underdrain w/Sock; 17,000 S.Y. Soil Guard; 4 Each Slope Box Inlet 15"; 575 Ton Temporary Bituminous Pavement; 17.5 Acre Seeding

Pre-Bid meeting: N/A

(DBE 11.6%)

28A Palwaukee Municipal Airport

Prospect Heights, Illinois

Cook County

Ill. Proj. PWK-2974

AIP No. 3-17-0018-B29

Contract No. PA044

Construct, Light & Mark Northwest Parallel Taxiway Lima to Runway 16/34 from Taxiway L2 to Taxiway N - which includes the following major work items: 1,435 L.F. 1/C #8 5KV UG Cable; 1,190 L.F. 2" PVC Duct, Direct Bury; 75 L.F. Concrete Encased Duct; 15 Each MITL-Base Mounted; 2,250 C.Y. Unclassified Excavation; 720 Ton Bituminous Base Course; 3,055 S.Y. Crushed Aggregate Base Course-4"; 2,980 S.Y. 8" PCC Pavement; 6,125 S.F. Pavement Marking; 259 L.F. RCP, Class IV; 865 L.F. 6" Perforated Underdrain; 1 Acre Seeding; 450 S.Y. Sodding  
Pre-Bid meeting: N/A  
(DBE 10.0%)

NOTE: The following project (26A) is to be funded, in part, with federal entitlement funds that have not yet been appropriated and, therefore, are not guaranteed to the state as of the date of this publication. It is expected that these funds will be received prior to the anticipated notice to proceed date found in the proposal documents. However, the Department will not award this project until it receives the federal funds.

26A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3309

AIP No. 3-17-0068-xx

Contract No. QU091

Runway End 5 Safety Area Improvements - which includes the following major work items: 1,850 L.F. 4" PVC Duct, Direct Bury; 1 L.S. Traffic Maintenance; 59,325 C.Y. Unclassified Excavation; 2,675 S.Y. Riprap-Gradation No.3; 5,750 Ton Crushed Aggregate Base Course; 11,065 S.Y. Geotextile Fabric; 730 Ton Bituminous Surface Course; 594 L.F. RCP; 309 L.F. RCEP Span 45 Rise 29; 4 Each Inlet-Special; 8 Each Precast Rein. Concrete FES 60"; 1,325 L.F. 12" Ductile Iron Water Main; 4 Each Tapping Valve & Sleeve; 2,250 L.F. 6" Force Main; 1 L.S. Sanitary Lift Station; 44 Acre Seeding  
Pre-Bid meeting: N/A  
(DBE 5.0%)



**ILLINOIS DEPARTMENT OF NATURAL RESOURCES**  
**LAND RECLAMATION**

- 1LR. Tazewell County  
AML-GTAE-0405  
RECLAMATION OF CRESENT COAL COMPANY NO. 2 GROUP  
The proposed reclamation project is located at three sites in Tazewell County. The first site is in Creve Coeur, the second in Marquette Heights, and the third is in North Pekin. The work includes approximately 4,150 cu yds of earth excavation; 458 cu yds of special excavation; 87 tons of riprap fill C-3; 94 tons of CA-1 fill; 25 tons of CA-6 fill; 500 sq yds of stone riprap A-4; 110 tons of aggregate surface course, type B, CA-6; 2,300 sq yds of erosion control blanket; and seeding, mulch, and soil amendments for approximately 5 acres. A Pre-Bid meeting will be held at 9:00 a.m., Friday, July 23, 2004 at the Route 98 Mine Opening Site. All prime contractors and DBE firms are encouraged to attend. (9.00% DBE)
- 2LR. Saline County  
AML-GSIE-0201  
RECLAMATION OF SAHAHA #6 MINE, PHASE IV  
The proposed reclamation project is located in T9S, R5E, Sections 29, 30 and 32, approximately two miles northwest of Carrier Mills. The work includes approximately 410,000 cu yds of earth excavation, 290,000 cu yds of mine refuse excavation, 65,000 cu yds of channel excavation, installation of 1,400 feet of pipe culverts, special clearing and seeding and soil amendments for approximately 100 acres, and 300 tons of aggregate surface course. A Pre-Bid meeting will be held at 10:00 a.m., Thursday, July 22, 2004 at the site. All prime contractors and DBE firms are encouraged to attend. (8.00% DBE)
- 3LR. Williamson County  
AML-GWME-0314  
RECLAMATION OF THE RUSSELL SLOPE MINE GROUP  
The proposed reclamation project consists of two mine sites, the Russell Slope mine and the B & L Mine. The Russell Slope Mine is located on Linck Road in Spillertown. The work includes approximately 24,000 cu yds of excavation; 53 tons of shot rock fill to close two drift entries, 1,200 sq yds of special excelsior blanket, special clearing of approximately 5 acres, and seeding and soil amendments for approximately 7 acres. The B&L Mine is located approximately 2 miles south of Pittsburg. The work includes approximately 2,500 cu yds of earth excavation, 22 tons of shot rock fill and 27 cu yds of class SI concrete plug to seal a slope shaft, special clearing of approximately 1 acre, and seeding and soil amendments for approximately 4 acres. (8.00% DBE)