

IMPORTANT NOTICE: TRANSPORTATION BULLETIN REVISIONS

Letting Date: August 4, 2006

The following revisions have been made to this Transportation Bulletin. If you downloaded the bulletin prior to the noted revision date, you should incorporate the revisions or download and use a new copy of the bulletin.

Revision date **July 24, 2006**

Revision No. 1: [Item No. 4](#) the description reads (Job No. C-93-011-05) (3-44040-0000, 3-140-0900). The description has been changed to read (Job No. C-93-011-05) (3-44040-0000).

Revision No. 2: [Item No. 16](#) the description reads (Job No. C-99-044-06) (00-00857-9004). The description has been changed to read (Job No. C-99-044-06) (0-00857-9004).

Revision No. 3: [Item No. 17](#) the description reads (Job No. C-99-046-06) (00-00857-9005). The description has been changed to read (Job No. C-99-044-06) (0-00857-9008 & 0-00857-9009).

Revision No. 4: [Item No. 19](#) the description reads (Job No. C-92-150-05) (00-00856-2040). The description has been changed to read (Job No. C-92-150-05) (0-00857-2032).

Revision No. 5: [Item No. 32](#) the description reads (Job No. C-91-392-06) (00-00857-1034). The description has been changed to read (Job No. C-91-392-06) (0-01047-1001).

Revision No. 6: [Item No. 34](#) the description reads (Job No. C-96-510-07) (6-60810-0000, 6-60803-0000, 6-60811-00). The description has been changed to read (Job No. C-96-510-07) (6-60810-0000, 6-60803-0000, 6-60811-0000 & 6-60812-0000).

Revision No. 7: [Item No. 35](#) the description reads (Job No. C-60-005-07) (00-00527-0000). The description has been changed to read (Job No. C-60-005-07) (0-00527-4001).

Revision No. 8: [Item No. 42](#) the Small Business Set-Aside has been removed from this job.

Revision No. 9: [Item No. 47](#) has been WITHDRAWN from the Letting.

Revisions No. 10: [Item No. 49](#) the description reads (0-0085-75004). The description has been changed to read (Job No. C-C-95-077-06) (0-00857-5004).

Revisions No. 11: [Item No. 50](#) the description reads (Job No. C-97-054-06) (00-00197-5001). The description has been changed to read (Job No. C-97-054-06) (0-00197-7001).

Revisions No. 12: [Item No. 51](#) the description reads (15.00 % DBE). The description has been changed to (5.00%).

Revision No. 13: [Item No. 64](#) reads (Job No. C-92-148-05) (0-00856-2036). The description has been changed to read (Job No. C-92-148-05) (0-00857-2031).

Revision No. 14: [Item No. 65](#) reads (Job No. C-93-017-06) (0-00856-3022). The description has been changed to read (Job No. C-93-017-06) (0-00857-3001).

Revision No. 15: [Item No. 68](#) reads (0.00% DBE). The description has been changed to read (7.00% DBE).

Revision No. 16: [Item No. 69](#) has been WITHDRAWN from the Letting.

Revision No. 17: [Item No. 84](#) reads (Completion Date: September 25, 2006 Plus 03 Working Days). The description has been changed to read (Completion Date: November 6, 2006).

Revision No. 18: [Item No. 90](#) reads (Job No. C-92-065-06) (2-97627-0001). The description has been changed to read (Job No. C-92-065-06) (2-97627-0001 & 2-97627-0002).

Revision No. 19: [Item 6A](#) has been WITHDRAWN from the Letting.

Revision No. 20: [Item 8A](#) has been moved to the "Unfunded" Section.

Revision No. 21: [Item 21A](#) be sure to check on the "NEWSFLASH" for this item that was published on July 14, 2006.

MANDATORY PRE-BID CONFERENCE

DISTRICT 1 – MANDATORY PRE-BID CONFERENCE

A pre-bid conference has been scheduled for **Friday, July 21, 2006, at 10:00 a.m.** This conference will be held at the University of Illinois at Chicago Campus located at 750 S. Halsted Street, Room 605, Chicago, Illinois 60609.

The primary objective of the pre bid conference will involve presenting a general overview of the southbound Dan Ryan Expressway outbound elevated bridge contract between 15th Street and 28th Street (shown below) with a general discussion of the scope of work, suggested traffic control & staging and the suggested construction schedule.

Contract # 62581 FAI 90/94 - Dan Ryan Expressway, Outbound southbound elevated bridge north of 15th Street to 28th Street: bridge deck repairs, bridge deck scarification and concrete overlay in the City of Chicago, Cook Co., IL.

Other District One contracts advertised on the August 4, 2006 letting will be briefly presented for information.

All prime contractors and DBE firms are encouraged to attend. This pre-bid conference is **MANDATORY** for all prime contractors who plan to submit bids on the Dan Ryan Expressway contract # 62581.

Attendance will be taken. Failure on the prime contractor's part to attend will cause the contractor's bid to be rejected. Members from the Small Business Enterprises and from District One IDOT will be on hand to answer any questions that you may have. This will be an opportunity for prime contractors and DBE firms to meet and discuss projects of mutual interest.

Both prime and DBE firms are encouraged to review the project hiring goals prior to this pre-bid conference. A short formal presentation will be given.

PRE-BID CONFERENCE

DISTRICT 4 –PRE- BID CONFERENCE

Plans and Special Provisions for all District 4 contracts for the Letting of August 4, 2006 will be available for your review at the District 4 Office, 6th Floor Training Room from 5: 30 p.m. to 7: 00 p.m. on Tuesday, July 25, 2006. The District 4 Office is located at 401 Main Street, Peoria, Illinois. All prime contractors and DBE firms are encouraged to attend. There will be members from Supportive Services and District 4 to answer any questions that you may have. This will be an opportunity for prime contractors to indicate projects on which they are interested in receiving quotations from DBE firms. Both prime contractors and DBE firms are encouraged to review the project goals prior to this pre-bid conference. This will be an open house format and no formal presentation will be given.

PRE-BID CONFERENCE

ILLINOIS DEPARTMENT OF NATURAL RESOURCES LAND RECLAMATION

2LR

A Pre-Bid Meeting is scheduled for this project at 10:30 AM, Wednesday, July 19, 2006.

All interested potential bidders are to meet at the site access along Netty Green Rd., approximately 1.5 miles east of Harco Road, and 0.5 miles west of Hickory Street, near Galatia.



Letting Item Descriptions

Paving

Bridge

Electrical

Miscellaneous

Department of Natural Resources – Land Reclamation

Review and Inspection

Division of Aeronautics

PAVEMENT SECTION

1. Contract No. 60660 Cook County District 1
Section 0304RS-3
FAU Route 1382 (FULLERTON AVE.)
0.53 mile of 32 ft to 40 ft width milling and bituminous concrete surface on Fullerton Avenue from IL Route 171 (Cumberland/First Avenue) to 80th Avenue in River Grove; includes 120 sq ft detectable warnings; 13,389 sq yds milling; 740 sq yds patching; 220 sq yds curb and gutter removal and replacement; 2,501 ft thermoplastic pavement marking; 686 ft detector loop replacement; 1,686 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (25 Working Days) (Job No. C-91-345-98) (0-00857-1027) (SUPERPAVE) (5.00% DBE)
- Item 1P was previously advertised as a Review and Inspection project only. Bids are now being accepted on Item 1P for the August 4, 2006 Letting. Contractors and suppliers who requested plans and proposals for these items in connection with the previous advertisement should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for each CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting).

1P. Contract No. 62581 Cook County District 1
Section 2003-0291
FAI Route 94/90 (I-94/90/DAN RYAN)
Bridge repairs to the elevated portion of southbound I-94/90/Dan Ryan Expressway from 15th Street to 28th Street (14 structures) including joint replacement and overlay along with other work, all located in Chicago; includes 875 sq yds sub-base granular material; 1,087 cu yds concrete removal; 1,205 cu yds concrete; 101,406 sq yds bridge deck grooving; 233,040 lbs structural steel; 39,930 lbs structural steel removal; 3,310 lbs structural steel repair; 171,670 lbs epoxy coated reinforcement bars; 9,974 ft modular glare screen system; 76,437 ft epoxy pavement marking; 128,261 ft polyurea pavement marking; 263 cleaning bridge scuppers and downspouts; 1,419 ft bridge joint system (expansion); 379 ft bridge joint system (fixed); 875 sq yds concrete shoulders; 102,774 sq yds bridge deck hydro-scarification; 102,774 sq yds bridge deck microsilica concrete overlay; 138 sq yds deck slab repair; 31,194 sq yds protective shield; 106 ft deck silicone joint sealer; 10,486 ft parapet silicone joint sealer; mobilization; traffic control and protection.
(Completion Date: October 31, 2007 Plus 05 Working Days) (Job No. C-91-083-03) (1-76073-0400) (5.00% DBE)
[MANDATORY PRE-BID CONFERENCE](#)
2. Contract No. 62923 Cook County District 1
Section 3098RS-4
FAU Route 1587 (MCCARTHY ROAD) Project ACHPP-HPP-F-1587(4)
3.31 miles of milling, bituminous concrete surface and drainage work along McCarthy Road from Bell Road to U.S. 45 (LaGrange Road) in Lemont and Palos Park; includes 75 cu yds trench backfill; 1,603 sq yds topsoil; 2,606 ft grading and shaping ditches; 2.2 acres seeding; 51 sq yds stone riprap; 3,324 sq yds patching; 1,276 tons aggregate shoulders; 900 sq yds bituminous shoulders, SUPERPAVE; 3,038 ft storm sewers; 12 manholes; 1,275 ft steel plate beam guardrail; 63,942 ft thermoplastic pavement marking; 350 ft detector loop replacement; 15,948 ft grading and shaping shoulders; 46,000 sq yds milling; 6,323 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection; Federally funded. (Completion Date: June 15, 2007 Plus 05 Working Days) (Job No. C-91-155-05) (1-76734-0000) (SUPERPAVE) (15.00% DBE)
3. Contract No. 64890 Winnebago County District 2
Section 104CS-RS-1
FAP Route 517 (US BUS 20) Project NHF-517(53)
1.19 miles of 48 feet and variable width bituminous concrete milling, resurfacing, patching, and inlet improvements on U.S. Business Route 20 from Winnebago Street to East State Street in Rockford; includes 1,057 tons bituminous replacement over patches; 14,898 sq yds bituminous removal; 548 ft combination curb and gutter removal and replacement; 460 sq yds pavement patching; 15 inlets to be reconstructed; 3,913 sq ft work zone pavement marking removal; 11,107 ft thermoplastic pavement marking-line; 20 raised reflective pavement markers; 19 traffic signal posts; 21 signal heads; 1,157 tons bituminous concrete surface and binder course, SUPERPAVE N50; 16,711 sq yds bituminous surface removal; construction layout; railroad protective liability insurance; mobilization; traffic control and protection; Federally funded. (60 Working Days) (Job No. C-92-091-06) (2-15240-0000) (SUPERPAVE) (6.00% DBE)

4. Contract No. 66535 Kendall County District 3
Section 1N & TS
FAP Route 311 (IL 71) Project F-HS-311(31)
This project consists of relocating and improving the IL Route 126 and IL Route 71 intersection just south of Yorkville; includes 21,816 cu yds earth excavation; 2,466 lbs fertilizer nutrient; 2,452 sq yds sodding; 1,020 sq yds erosion control blanket; 24 inlets and pipe protection; 12,793 sq yds pavement removal; 5,290 sq yds aggregate shoulders; 5,131 sq yds bituminous shoulders SUPERPAVE; removal of existing structures numbers 1 through 3; 3,130 lbs reinforcement bars; 224 ft precast concrete box culvert; 716 ft pipe culverts; 19 end sections; 150 pipe drains; 3,500 ft exploration trench; 300 ft storm sewers; 4 field tile junction vaults; 277 sq ft sign panel; 38,539 ft thermoplastic pavement marking line; 324 raised reflective pavement markers; 1 service installation; 2,583 ft conduit in trench; 2,257 ft trench and backfill for electrical work; 12,042 ft electric cable in conduit; 4 luminaires; 1 lighting controller photocell relay; 1 full actuated controller and cabinet; 4 steel combination mast arm assemblies and poles; 75 ft concrete foundation; 16 inductive loop detectors; 2,002 ft detector loop; 4 light detectors; 190 ft water main casing; 8,168 sq yds bituminous concrete base course, SUPERPAVE; 10,042 tons bituminous concrete binder and surface course; 2,015 sq yds bituminous surface removal; 258 ft combination concrete curb and gutter; 20 signal heads; construction layout; mobilization; traffic control and protection; Federally funded. (120 Working Days) (Job No. C-93-011-05) (3-44040-0000) (SUPERPAVE) (8.00% DBE)

5. Contract No. 66653 Ford County District 3
Section (27-38)I-1 & (27-1)I-2
FAI Route 57 (I-57)
This project consists of pavement patching, shoulder replacement, and pavement replacement on Interstate 57 from the Champaign County Line to the Iroquois County Line; includes 716 cu yds earth excavation; 781 sq yds continuously reinforced concrete pavement; 879 sq yds bituminous shoulder removal; 360 sq yds pavement patching; 2,604 ft saw cuts; 44 tons aggregate shoulders; 879 sq yds bituminous shoulders, SUPERPAVE; 819 ft pipe underdrains; 791 ft shoulder rumble strips; 3,380 ft epoxy pavement marking line; 819 ft pipe underdrain removal; traffic control and protection; mobilization. (35 Working Days) (Job No. C-93-073-06) (0-00857-3008) (SUPERPAVE) (3.00% DBE)

- 6. **Small Business Set-Aside.**
Contract No. 66656 Kankakee County District 3
Section (7R-1,10)I
FAP Route 332 (IL 1/17)
This project consists of pavement patching and widening at the intersection of Illinois Route 1 and Illinois Route 17 near Kankakee; includes 25 cu yds earth excavation (widening); 160 sq yds high-early-strength Portland cement concrete base course widening; 60 sq yds pavement removal; 90 ft curb removal; 731 sq yds pavement patching; 3,659 ft saw cuts; 228 ft strip reflective crack control treatment; 72 sq yds bituminous shoulders; 300 ft epoxy pavement marking line; 18 tons bituminous concrete surface course, SUPERPAVE; 1,854 dowel bars; mobilization; traffic control and protection. (25 Working Days) (Job No. C-93-076-06) (0-00857-3011) (SUPERPAVE) (0.00% DBE)

7. Contract No. 70558 Piatt County District 5
Section (74-68)MRS
FAI Route 72 (I-72)
0.53 miles of 24 feet width bituminous resurfacing on Interstate 72 at the Bridge Street interchange in Monticello; includes 105 sq yds patches; 606 ft saw cuts; 2,800 ft thermoplastic pavement marking line; 11 raised reflective pavement marker; 624 tons polymerized bituminous concrete surface and binder course; 3,423 sq yds bituminous surface removal; mobilization; traffic control and protection. (15 Working Days) (Job No. C-95-072-06) (0-00857-5002) (SUPERPAVE) (0.00% DBE)

8. Contract No. 74161 Richland County District 7
Section (123Z,124Z)TS-2,RS-3
FAP Route 116 (IL 130) Project F-HSIP-116(49)
1.08 miles of 52 ft and variable width milling and bituminous concrete surface on IL Route 130 from north of Ash Street to North Avenue in Olney; includes 995 sq ft concrete sidewalk; 35,919 sq yds milling; 262 sq yds patching; 66 ft concrete curb and gutter; 128 sq ft sign panel; 17,659 ft thermoplastic pavement marking; 530 ft trench and backfill; 8,273 ft electric cable; 5 luminaires; 1 controller; 5 steel mast arm assemblies and poles; 3 steel combination mast arm assemblies and poles; 1,643 ft detector loop; 1 video vehicle detection system; 5,109 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, Mix D; 42 signal heads; mobilization; traffic control and protection; Federally funded. (90 Working Days) (Job No. C-97-067-06) (7-83800-0000) (SUPERPAVE) (0.00% DBE)

9. Contract No. 74188 Fayette County District 7
Section D-7 BIT. RESURF. 2007-1
FAI Route 70 (I 70)
0.49 mile of resurfacing of the ramps located along I-70 at Brownstown Weigh Station; includes 4,676 sq yds milling; 803 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, Mix D; 5,638 ft thermoplastic pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-97-103-06) (0-00857-7002) (SUPERPAVE) (0.00% DBE)

10. Contract No. 76441 Madison County District 8
Section 34RS-2
FAP Route 600 (OLD IL ROUTE 159)
1.30 miles of 40 ft and variable width milling and bituminous concrete surface on Old IL Route 159 from north of Harvard Avenue to IL Route 143 in Edwardsville; includes 148 sq ft concrete sidewalk; 29,299 sq yds milling; 32 sq yds pavement removal; 1,610 sq yds patching; 77 tons bituminous shoulders, SUPERPAVE; 66 ft concrete curb and gutter; 2,526 ft detector loop replacement; 2,195 tons bituminous concrete surface course, SUPERPAVE, MIX D; 28,779 ft thermoplastic pavement marking; mobilization; traffic control and protection. (Completion Date: November 15, 2006)
(Job No. C-98-012-01) (8-86980-0105) (SUPERPAVE) (10.00% DBE)
11. Contract No. 76989 Greene County District 8
Section 501,502RS-1
FAS Route 739 (ELDRED-HILLVIEW)
3.8 miles of 22 ft width bituminous surface treatment (preventive maintenance) on Eldred-Hillview Road from IL Route 108 in Eldred to TR 50; includes 1,210 tons aggregate shoulders; 17,173 ft paint pavement marking; 49,045 sq yds bituminous surface treatment (preventive maintenance); 2,750 tons leveling binder (machine method); mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-016-06) (8-00160-0000) (3.00% DBE)
12. Contract No. 76992 Jersey County District 8
Section (259,47)RS-3
FAP Route 355 (US 67)
1.10 miles of milling and bituminous concrete surface on U.S. Route 67 from Indian Lakes Road in New Delhi to 0.6 mile north of Stage Coach Road; includes 16,385 sq yds milling; 140 sq yds patching; 50 tons aggregate shoulders; 19,519 ft paint pavement marking; 1,376 tons bituminous concrete surface course, SUPERPAVE, MIX C; mobilization; traffic control and protection. (20 Working Days) (Job No. C-98-019-06) (8-00163-0000) (7.00% DBE)
13. Contract No. 76993 Greene County District 8
Section (101,102)RS-1
FAP Route 761 (IL 108)
2.60 miles of 18 ft and variable width milling and bituminous concrete surface on IL Route 108 from the Illinois River near Kampsville to Eldred-Hillview Road in Eldred; includes 39,291 sq yds milling; 89 sq yds patching; 388 tons aggregate shoulders; 36,434 ft paint pavement marking; 3,319 tons bituminous concrete surface course, SUPERPAVE, Mix C; mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-020-06) (8-00164-0000) (SUPERPAVE) (5.00% DBE)
14. Contract No. 76995 Madison County District 8
Section 117-1RS-4
FAP Route 592 (IL 157)
0.44 mile of 62 ft and variable width milling and bituminous concrete surface on IL Route 157 from north of Horseshoe Lake Road, south to Collinsport Drive in Collinsville; includes 147 sq yds patching; 14,625 sq yds milling; 1,230 tons bituminous concrete surface course, SUPERPAVE, MIX C; 13,966 ft paint pavement marking; mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-022-06) (8-00166-0000) (SUPERPAVE) (5.00% DBE)
15. Contract No. 98942 Gallatin-Saline Counties District 9
Section (29,29X)RS-2
FAP Route 332 (US 45) Project NHF-332(82)
6.97 miles of 26 ft and variable width milling and bituminous concrete surface on U.S. Route 45 from north of IL Route 142 in Eldorado to the White County Line; includes 8,903 tons material transfer device; 8,903 tons polymerized bituminous concrete surface course, SUPERPAVE, MIX D; 637 sq yds aggregate base course; 4,087 tons leveling binder (machine method); 105,470 sq yds milling; 3,215 sq yds patching; 2,705 tons aggregate shoulders; 400 ft steel plate beam guardrail; 10 traffic barrier terminals; 97,654 ft thermoplastic pavement marking; mobilization; traffic control and protection; Federally funded. (55 Working Days) (Job No. C-99-005-06) (9-00069-0000) (SUPERPAVE) (4.00% DBE)
16. Contract No. 98976 Jackson-Massac Counties District 9
Section D-9 CONT. MAINT. FY 07-2
Various Routes (VARIOUS)
Pavement patching at various locations in Jackson and Massac counties; includes 1,056 dowel bars; 178 tie bars; 1,120 sq yds patching; 488 sq yds patching reinforcement; 277 sq yds pavement fabric; 3,139 ft saw cuts; mobilization; traffic control and protection. (25 Working Days) (Job No. C-99-044-06) (0-00857-9004) (0.00% DBE)

17. Contract No. 98979 Franklin-Williamson Counties District 9
Section D-9 CONT. MAINT. FY 07-5
FAS Route 903/2882 (IL 37)
3.37 miles of 23 ft and variable width milling and bituminous concrete surface on FAS Route 903 and IL Route 37 from Herrin to Johnston City Blacktop and north of West Frankfort; includes 2,279 tons bituminous concrete surface course, SUPERPAVE, MIX C; 1,745 tons bituminous concrete surface course, SUPERPAVE, MIX D; 47,491 sq yds milling; 460 sq yds patching; 266 tons aggregate shoulders; 227 tons bituminous shoulders; 46,238 ft paint pavement marking; mobilization; traffic control and protection. (25 Working Days) (Job No. C-99-046-06) (0-00857-9008 & 0-00857-9009) (SUPERPAVE) (0.00% DBE)
18. Contract No. 98983 Alexander-Saline Counties District 9
Section D9 CONT. MAINT FY07-6
FAP Route 14 & FAP Route 331 (US RT. 51/60/62 & IL RT 13)
0.25 mile of variable width milling and bituminous concrete surface on U.S. Route 51/60/62 & IL Route 13; includes 574 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, MIX D; 3,708 sq yds milling; 61 tons aggregate shoulders; 213 ft detector loops; 2,765 ft thermoplastic pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-99-052-06) (0-00857-9006,0-00857-9005) (SUPERPAVE) (0.00% DBE)
19. Contract No. 64B69 JoDaviess County District 2
Section D2 MRS 2006-14
FAP Route 306 (IL 35)
This project consists of bituminous cold milling, pavement patching, and resurfacing on IL Route 35 at the intersection of 3rd Street and Wall Street in East Dubuque; includes 506 sq yds bituminous surface removal; 86 sq yds patches; 43 tons bituminous concrete surface course, SUPERPAVE; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-150-05) (0-00857-2032) (SUPERPAVE) (0.00% DBE)
20. Contract No. 72A50 Adams-Brown Counties District 6
Section 5(RS-5,I)
FAP Route 317 (US 24)
1.40 miles of 22 ft width bituminous concrete surface, pavement patching and replacement of a box culvert with a 4' X 2' precast concrete box culvert all located on U.S. Route 24 from 1.10 miles west of the Adams/Brown County line; includes 8.9 cu yds subbase granular material; 337 sq yds preparation of base; 525 sq yds patching; 422 tons aggregate shoulders; removal of existing structure; 46 ft precast concrete box culvert; 18,814 ft paint pavement marking; 2,589 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; 21.6 cu yds granular culvert backfill; mobilization; traffic control and protection. (20 Working Days) (Job No. C-96-008-07) (0-00857-6008) (SUPERPAVE) (0.00% DBE)
21. Contract No. 72A57 Montgomery County District 6
Section (17R)RS-5
FAS Route 723 (NOKOMIS BLACKTOP)
1.79 miles of 22 ft width bituminous concrete surface course on Nokomis Blacktop from 1.3 miles west of Nokomis continuing easterly for 1.79 miles; includes 69 sq yds preparation of base; 8,626 sq yds milling; 849 tons aggregate shoulders; 4,324 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; 20,868 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-009-07) (0-00857-6009) (SUPERPAVE) (0.00% DBE)
22. Contract No. 76A03 St. Clair County District 8
Section 10-1RS-1
FAU Route 9185 (FOLEY DRIVE)
1.30 miles of 25 ft to 36 ft and variable width milling and bituminous concrete surface on Foley Drive from Main Street to 1.3 miles west, located in Belleville; includes 20,108 sq yds milling; 21,157 ft paint pavement marking; 2,626 ft detector loop replacement; 1,689 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-030-06) (0-00857-8007) (SUPERPAVE) (5.00% DBE)
23. Contract No. 76A04 St. Clair County District 8
Section 29RS-2,(Z-I)RS-1
FAU Route 9213/9228 (COLLINSVILLE RD/26TH ST.)
Variable width milling and bituminous concrete surface at 2 locations including 1.28 miles of Collinsville Road from east of IL Route 203 to St. Clair Avenue and 0.92 mile of 26th Street from north of Louisiana Avenue to Market Street in East St. Louis; includes 45,877 sq yds milling; 174 sq yds patching; 41,305 ft paint pavement marking; 3,954 tons bituminous concrete surface course, SUPERPAVE, MIX D; mobilization; traffic control and protection. (30 Working Days) (Job No. C-98-031-06) (0-00857-8008) (SUPERPAVE) (5.00% DBE)

24. Contract No. 76A09 Madison County District 8
Section 28-RS-2
FAU Route 9128 (OLD US 40 (ST. LOUIS RD))
0.53 mile of 36 ft width bituminous concrete surface on Old U.S. Route 30 (St. Louis Road) from the Water Plant to National Terrace Road in Collinsville; includes 15 tons aggregate shoulders; 1,129 tons bituminous concrete surface course, SUPERPAVE, MIX D; 12,978 ft thermoplastic pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-036-06) (0-00857-8013) (SUPERPAVE) (2.00% DBE)
[SEE MORE PAVEMENT](#)

BRIDGE SECTION

25. Contract No. 62531 Kane County District 1
Section E-8-4-B
FAP Route 326 (IL 47)
Replacement of the superstructure and repairs to the substructure of the bridge carrying IL Route 47 over I-88 (East-West Tollway) (SN 045-0082) located in Blackberry Township; includes 550 cu yds earth excavation; 22 units grading and shaping shoulders; 235 cu yds removal and disposal of unsuitable material; 2,075 sq yds topsoil; 0.5 acre seeding; 2,610 ft perimeter erosion barrier; 915 sq yds stone riprap; 2,760 sq yds subbase granular material; 536 sq yds bridge approach pavement; 73 sq yds pavement removal; 34 sq yds bituminous shoulders, SUPERPAVE; removal of existing superstructure; 18.6 cu yds concrete removal; 769.4 cu yds concrete; 1,800 sq yds bridge deck grooving; 1,984 ft precast, prestressed concrete I-beams; 165,740 lbs epoxy coated reinforcement bars; 430 sq ft bridge seat sealer; 350 ft steel plate beam guardrail; 6 traffic barrier terminals; 9,362 ft polyurea pavement marking; 168 sq ft structural repair of concrete; 2,765 sq yds bituminous base course, SUPERPAVE; 3,138 sq yds protective shield; 271 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (Completion Date: September 30, 2007 Plus 10 Working Days) (Job No. C-91-321-02) (1-71499-0100) (SUPERPAVE) (7.00% DBE)
26. Contract No. 74140 Wayne County District 7
Section (96-4HB-1)BR-06
FAI Route 64 (I-64)
Structural steel removal and repair, beam straightening and other work to the existing structures (SN 096-0053, 096-0059) at the Mill Shoals Interchange on I-64; includes 19.2 cu yds concrete removal; 19.2 cu yds concrete; 11,510 lbs structural steel; 144 stud shear connectors; 11,690 lbs structural steel removal; 3,620 lbs structural steel repair; 4,040 lbs epoxy coated reinforcement bars; beam straightening; 100 sq yds protective shield; temporary shoring and cribbing; mobilization; traffic control and protection. (Completion Date: November 17, 2006) (Job No. C-97-024-06) (MCHD Funds) (0.00% DBE)
27. Contract No. 76389 Washington County District 8
Section 2BR
FAP Route 42 (IL 127) Project F-42(97)
Removal of the existing structure and replacement with a single span @ 85'-6" wide flange beam bridge (SN 095-0076) carrying IL Route 127 over Tributary to Crooked Creek near Posey; includes 255 cu yds earth excavation; 1,040 cu yds channel excavation; 215 cu yds porous granular embankment; 970 sq yds stone riprap; 970 sq yds filter fabric; 254 sq yds bridge approach pavement; 504 sq yds pavement removal; 32 tons bituminous shoulders, SUPERPAVE; 230 cu yds structure excavation; 172.6 cu yds concrete; 559 sq yds bridge deck grooving; 91,130 lbs structural steel; 1,350 stud shear connectors; 31,490 lbs epoxy coated reinforcement bars; 335 ft steel piles HP 12 X 53; 1,365 sq ft temporary sheet piling; 538 ft steel plate beam guardrail; 8 traffic barrier terminals; 3,082 ft thermoplastic pavement marking; 1,121 sq yds bituminous base course, SUPERPAVE; 44 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; mobilization; traffic control and protection; Federally funded. (85 Working Days) (Job No. C-98-140-05) (8-89266-0100) (SUPERPAVE) (13.00% DBE)
28. Contract No. 76896 Madison County District 8
Section 68-BR-1
FAP Route 789 (IL 143) Project BHF-789(43)
Replacement of the existing superstructure of the bridge carrying IL Route 143 over Sugar Fork Creek (SN 060-0150) located 1.7 miles east of Marine; includes 71 cu yds earth excavation; 764 sq yds stone riprap; 764 sq yds filter fabric; 300 sq yds milling; 16 tons aggregate shoulders; removal of existing superstructure; 5.8 cu yds concrete removal; 4,034 sq ft precast, prestressed concrete deck beams; 1,320 lbs epoxy coated reinforcement bars; 462 sq yds waterproofing membrane system; 1,223 ft portland cement mortar fairing course; 37.5 ft steel plate beam guardrail; 9 traffic barrier terminals; 882 ft thermoplastic pavement marking; 38.5 sq yds concrete sealer; 173.5 sq ft structural repair of concrete; 111 sq yds bituminous concrete base course widening; 267 tons bituminous concrete binder and surface course, SUPERPAVE, MIX C; mobilization; traffic control and protection; Federally funded. (45 Working Days) (Job No. C-98-063-05) (8-00092-0000) (SUPERPAVE) (13.00% DBE)

29. Contract No. 76899 Clinton County District 8
Section 24-BR-2
FAS Route 1780 (OLD US 50) Project BHS-1780(120)
Removal of the existing Superstructure and replacement with precast prestressed concrete deck beams and overlay of the entire 3-span steel and 12-span PPC deck beam bridge (SN 014-0062) carrying Old U.S. Route 50 over Shoal Creek just east of Breese; includes 480 sq yds milling; 693 sq yds bituminous concrete removal (deck); removal of existing Superstructure; 9.3 cu yds concrete removal; 230.3 cu yds concrete; 22,028 sq ft precast, prestressed concrete deck beams; 1,650 lbs structural steel; 25,590 lbs epoxy coated reinforcement bars; 2,833 sq yds waterproofing membrane system; 6,343 ft portland cement mortar fairing course; 1,299 sq ft bridge seat sealer; 6 traffic barrier terminals; 450 ft retrofit concrete parapet; 3,101 ft thermoplastic pavement marking; 1,110 sq ft removal of existing precast, prestressed concrete deck beams; 356 sq ft structural repair of concrete; 127 sq yds bituminous concrete base course widening, SUPERPAVE; 385 tons bituminous concrete surface course, SUPERPAVE, MIX D; 70 sq yds deck slab repair; mobilization; traffic control and protection; Federally funded. (165 Working Days) (Job No. C-98-040-06) (8-89387-0100) (SUPERPAVE) (10.00% DBE)
30. Contract No. 76964 Washington County District 8
Section 101BR-3
FAS Route 819 (IL 177) Project BHS-819(131)
Replacement of the superstructure of the existing bridge carrying IL Route 177 over Grand Point Creek, west of Irvington; includes 16 cu yds earth excavation; 67 cu yds furnished excavation; 754 sq yds stone riprap; 754 sq yds filter fabric; 3.5 cu yds concrete removal; 4.9 cu yds concrete; 359 sq ft precast concrete bridge slab; 3,074 sq ft precast, prestressed concrete deck beams; 470 lbs epoxy coated reinforcement bars; 349 sq yds waterproofing membrane system; 893 ft portland cement mortar fairing course; 8 traffic barrier terminals; 675 ft thermoplastic pavement marking; 62 ft bridge joint system (expansion); 45 sq ft structural repair of concrete; 66 sq ft bituminous concrete base course widening; 152 tons bituminous concrete binder and surface course, SUPERPAVE, MIX C; mobilization; traffic control and protection; Federally funded. (40 Working Days) (Job No. C-98-133-05) (8-00094-0000) (SUPERPAVE) (12.00% DBE)
31. Contract No. 60B20 Cook County District 1
Section 2424.2B-BR-1
FAI Route 290 (I-290/CONGRESS PKWAY)
Structural steel repair to the bridges carrying I-290 (Eisenhower Expressway/ Congress Parkway) over South Branch of the Chicago River (SN 016-2445, SN 016-0460) in Chicago; includes 4,200 lbs structural steel repair; 4 temporary support systems; mobilization. (25 Working Days) (Job No. C-91-308-06) (0-00857-1002) (0.00% DBE)
32. Contract No. 60B67 Lake County District 1
Section 125SB-1-I-1
FAU Route 1238 (IL 176 (ROCKLAND RD.))
Replacement of the precast, prestressed concrete deck beams for the bridge carrying IL Route 176 (Rockland Road) over U.S. Route 41 (Skokie Highway) SN 049-0131 in Lake Bluff; includes 25.4 cu yds concrete removal; 25.4 cu yds concrete; 1,670 sq ft precast, prestressed concrete deck beams; 2,280 lbs epoxy coated reinforcement bars; 192 sq yds waterproofing membrane system; 737 ft portland cement mortar fairing course; 436 ft thermoplastic pavement marking; 1,695 sq ft removal of existing precast, prestressed concrete deck beams; 22 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (30 Working Days)
(Job No. C-91-392-06) (0-01047-1001) (SUPERPAVE) (0.00% DBE)
[SEE MORE BRIDGE](#)

ELECTRICAL SECTION

33. Contract No. 62887 Lake County District 1
Section 2004-121TS
FAP Route 541 (IL ROUTE 132) Project CMF-541(11)
Fiber optic communication network along IL Route 132 from IL Route 132 (Grand Avenue) from IL Route 83 to Sand Lake Road in Lake Villa and Lindenhurst; includes 9,338 ft conduit in trench; 1,961 ft conduit pushed; 14 handholes; 3 controllers; 3,626 ft electric cable; 9 traffic signal posts; 31 signal heads; 12,847 ft fiber optic cable; 5 maintenance of existing traffic signal installations; mobilization; traffic control and protection; Federally funded. (50 Working Days)
(Job No. C-91-077-05) (1-75941-0200) (0.00% DBE)
34. Contract No. 72A51 Sangamon-Montgomery Counties District 6
Section D-6 TRAFFIC SIGNAL MOD. 2007
Various Routes (VARIOUS) Project HSIP-000S(515)
Traffic signal modernization at various intersections located in Hillsboro, Litchfield and Rochester; includes 6,088 ft electric cable; 13 signal heads; 30.5 sq ft sign panel; 41 ft trench and backfill; 41 ft conduit in trench; 40 ft conduit augered; 1 controller; 3 mast arm assemblies and poles; 26 traffic signal backplates; 18 inductive loop detectors; mobilization; traffic control and protection; Federally funded. (30 Working Days)
(Job No. C-96-510-07) (6-60810-0000,6-60803-0000,6-60811-0000 & 6-60812-0000) (0.00% DBE)
[SEE MORE ELECTRICAL](#)

MISCELLANEOUS SECTION

35. Contract No. 44926 VARIOUS COUNTIES District 4
Section D 4 REFLECTOR REPL 2007-4
Various Routes
This project consists of removing and replacing raised reflective pavement markers on various highways throughout District Four; includes 932 raised reflective pavement markers; 8,206 replacement reflectors; 714 raised reflective pavement marker removals; mobilization. (Completion Date: June 30, 2007)
(Job No. C-60-005-07) (0-00527-4001) (0.00% DBE)
36. Contract No. 62635 Cook-Lake Counties District 1
Section 2003-0671
Various Routes (VARIOUS)
Scour countermeasures at 4 locations including Forest Avenue over Des Plaines River (SN 016-0874) Waukegan Road over West Fork of North Branch of the Chicago River (SN 016-0307), Caldwell Avenue over North Branch of the Chicago River (SN 016-0928) and IL Route 176 over East Skokie Ditch (SN 049-0013) located in Riverside, Glenview, Niles and Lake Bluff; includes 14 cu yds channel excavation; 2,600 sq yds stone riprap; 4,100 sq yds filter fabric; 100 cu yds gabions; 1,430 sq yds slope mattress; 4 dewatering structures; mobilization; traffic control and protection.
(80 Working Days) (Job No. C-91-171-03) (1-74816-2401) (0.00% DBE)
37. Contract No. 66654 LaSalle County District 3
Section VARIOUS
FAI Route 39 (I-39)
This project consists of pavement patching on the north and southbound lanes of Interstate 39 from the Marshall County Line to the Lee County Line near LaSalle; includes 1,086 sq yds patches; 1,086 sq yds patching reinforcement; 6,360 ft saw cuts; 1,868 ft epoxy pavement marking line; 220 tie bars; mobilization; traffic control and protection.
(30 Working Days) (Job No. C-93-074-06) (0-00857-3009) (0.00% DBE)
38. Contract No. 66659 Grundy County District 3
Section (32-2)I-4
FAI Route 80 (I-80)
This project consists of placing aggregate shoulder wedges on eastbound and westbound Interstate 80 from east of the Seneca Interchange to approximately 3.0 miles east of Illinois Route 47; includes 5,846 tons aggregate shoulders; 500 removing and replacing delineators; mobilization; traffic control and protection. (15 Working Days)
(Job No. C-93-079-06) (0-00857-3014) (0.00% DBE)

- Small Business Set-Aside.**
39. Contract No. 66675 Kendall-LaSalle Counties District 3
Section D3 TREE PLANTING 2007
FAP Route 591 & FAI Route 39 (US 34 & I-39)
This project consists of planting shade trees at locations in Kendall and LaSalle counties; includes 471 shade trees; mobilization. (20 Working Days) (Job No. C-93-082-06) (3-87337-0700) (0.00% DBE)

40. Contract No. 74189 Lawrence County District 7
Section D-7 PAVT. PATCHING 2007-1
FAP Route 327 (US 50)
Class B & D pavement patching along 10.5 miles of U.S. Route 50 from just west of Lawrenceville to the Indiana State Line; includes 373 sq yds Class B patches; 190 sq yds Class D patches; 18 sq yds pavement fabric; 880 dowel bars; 106 barricades; 2,169 ft saw cuts; mobilization; traffic control and protection. (20 Working Days)
(Job No. C-97-104-06) (0-00857-7001) (0.00% DBE)

NOTICE – PRE-QUALIFICATION WAIVER

- Pre-qualification of bidder with the Department of Transportation is not required on the BELOW item; however, prospective bidders must comply with Paragraph 3d of the Invitation For Bid in the Transportation Bulletin.**
41. Contract No. 76859 Randolph County District 8
Section 122I-4
FAP Route 312 (IL 3) Project NHF-312(30)
Slope stability improvements along IL Route 3 south of Chester at the Turkey Bluffs State Fish and Wildlife Area; includes 27,607 lbs epoxy coated reinforcement bars; 2,755 launched soil nails; 330 cu ft non-shrink grout; 31 pull-out testing; mobilization; traffic control and protection; Federally funded. (40 Working Days) (Job No. C-98-027-05) (8-00173-0000) (0.00% DBE)

42. Contract No. 76988 Madison County District 8
Section 132-3I-1
FAP Route 785 (IL 111/IL 140)
Slope restoration along IL Route 111/140 located 0.18 mile west of Fosterburg Road between Crest Drive and Wood River Creek near Alton; includes 346 units tree removal; 688 cu yds channel excavation; 38 cu yds furnished excavation; 3 tons riprap special; 784 sq yds filter fabric; 754 sq yds slope mattress; 800 sq ft permanent steel sheet piling; remove sheet piling; 1,141 sq yds remove existing riprap; mobilization; traffic control and protection. (20 Working Days)
(Job No. C-98-015-06) (0-00857-8002) (3.00% DBE)

43. Contract No. 98978 Jefferson County District 9
Section D-9 CONT. MAINT. FY 07-4
FAI Route 64 (I-64)
Class A pavement patching along 6.03 miles of I-64 east of Mt. Vernon; includes 1,150 sq yds Class A patches; 1,150 sq yds patching reinforcement; 140 tie bars; 3,212 ft saw cuts; mobilization; traffic control and protection. (20 Working Days)
(Job No. C-99-045-06) (0-00857-9003) (0.00% DBE)

NOTICE – PRE-QUALIFICATION WAIVER

Pre-qualification of bidder with the Department of Transportation is not required on the BELOW item; however, prospective bidders must comply with Paragraph 3d of the Invitation For Bid in the Transportation Bulletin.

44. Contract No. 60A67 Will County District 1
Section 2005-063I
FAI Route 55 (I-55) Project IM-55-6(222)250
Beam and bearing fabrication for the structures carrying FAI Route 55 over MS Railroad (SN 099-0022, 0023) over Elgin, Joliet and Eastern Railway Company Railroad (SN 099-0018, 0019), over U.S. Route 30 (SN 099-0016,0017) and over CSX Transportation Inc. Railroad (SN 099-0312) all in or near Shorewood and Joliet; includes furnishing 500,520 lbs structural steel; furnishing 43 elastomeric bearing assemblies; 377 units storage of structural steel and bearings; Federally funded. (Completion Date: May 15, 2007) (Job No. C-91-095-06) (1-74984-0950) (0.00% DBE)

45. Contract No. 60A70 Will County District 1
Section 2005-062I
FAI Route 55 (I-55) Project IM-55-6(223)250
Installation of 3-span trusses over the southbound lanes of I-55 and 3-span trusses and 1 cantilever truss over the northbound lanes of I-55 for signing beginning at I-80 and ending at Black Road in and near Shorewood and Joliet; includes 61 cu yds removal and disposal of unsuitable material; 7 temporary ditch checks; 2 inlet and pipe protection; 823 sq yds aggregate shoulders; 31.5 cu yds rock excavation for structures; 1,825 ft steel plate beam guardrail; 8 traffic barrier terminals; 1,246 sq ft sign panel; 1,051 sq ft remove sign panel; 1,288 sq ft relocate sign panel; 518 ft overhead sign structure-span; 40 ft overhead sign structure-cantilever; 192.9 cu yds drilled shaft concrete foundations; 21 guardrail markers; 273.8 ft overhead sign structure walkway; 1,878 sq yds topsoil; mobilization; traffic control and protection; Federally funded. (Completion Date: February 28, 2007 Plus 05 Working Days) (Job No. C-91-098-06) (1-74984-1000) (0.00% DBE)

46. Contract No. 64C37 Lee County District 2
Section D2 PATCHING 2007-1
FAI Route 39 (I-39)
19 miles of concrete pavement patching on Interstate 39 from the Lee/Ogle County Line to the Lee/LaSalle County Line; includes 2,194 sq yds patches; 134 sq yds pavement fabric; 1,656 sq yds patching reinforcement; 10,553 ft saw cuts; 1,097 sq yds stabilized subbase replacement; 729 dowel bars; 64 tie bars; mobilization; traffic control and protection. (25 Working Days) (Job No. C-92-127-06) (0-00857-2001, 2-20857-0000) (0.00% DBE)

47. THIS ITEM HAS BEEN WITHDRAWN

48. Contract No. 76A11 Madison-Calhoun Counties District 8
Section DIST. 8 SEAL COAT 2007-1
Various Routes (VARIOUS)
Bituminous surface treatment (oil and chip) at various locations; includes 12 tons bituminous materials (prime coat); 54 tons bituminous materials (cover and seal coats); 79 tons cover coat aggregate; 173 tons seal coat aggregate; 3,308 ft paint pavement marking; mobilization; traffic control and protection. (20 Working Days)
(Job No. C-98-038-06) (0-00857-8015) (3.00% DBE)

[SEE MORE MISCELLANEOUS](#)

PAVEMENT SECTION

49. Contract No. 70556 Vermilion County District 5
Section (33,116 SPUR)RS-1
FAS Route 500/FAU 7045 (BOWMAN AVENUE)
5.4 miles of 24 feet width bituminous milling and resurfacing on Bowman Avenue from Illinois Route 119 to TR 181 near Bismarck; includes 617 sq yds bituminous surface removal-butt joint; 1,579 tons aggregate shoulders; 1,496 sq ft work zone pavement marking removal; 50,479 ft paint pavement marking-line; 280 raised reflective pavement marker; 4,265 tons bituminous concrete surface course, SUPERPAVE, N 50; 2,551 tons leveling binder (machine method), SUPERPAVE, N 50. (15 Working Days) (Job No. C-95-077-06) (0-00857-5004) (SUPERPAVE) (0.00% DBE)
50. Contract No. 74155 Moultrie-Shelby Counties District 7
Section SFWA PARK ROADS 2003-1
PARK ROADS
Resurfacing the existing park roads and parking lots in the Kaskaskia and West Okaw Fish and Wildlife Units and the Margaret Guzy Pothole Wetland and Water Reserve Site all located along IL Route 121 from Bethany to Allenville and along IL Route 128 just west of the Moultrie/Shelby County line; includes 1,940 cu yds earth excavation; 775 cu yds furnished excavation; 1,070 ft grading and shaping ditches; 8 acres seeding; 800 lbs temporary erosion control seeding; 11,747 sq yds preparation of base; 8,906 gals bituminous materials (cover and seal coats); 152 tons cover coat aggregate; 119 tons seal coat aggregate; 54 ft steel plate beam guardrail; 827 tons stone lined ditch; 60 steel gate assemblies; mobilization; traffic control and protection. (105 Working Days) (Job No. C-97-054-06) (0-00197-7001) (7.00% DBE)
51. Contract No. 83532 Will County District 1
Section 00-P4003-00-BT
DELLWOOD PARK W BIKE PATH Project TE-D1(565)
The project consists of the construction of a bike path, walking path, pavement markings, installation of a prefabricated bridge, restoration and all other incidental work to complete the project in Dellwood Park West between the existing I & M Canal Tow Path and the existing stone roadway in Lockport Township Park District in the City of Lockport; includes 10 tree trunk protections; 2,400 cu yds earth excavation; 1,615 cu yds removal and disposal of unsuitable material; 330 lbs fertilizer nutrients; 2,500 ft perimeter erosion barrier; 6,000 sq yds aggregate base course; 150 tons aggregate surface course; removal of 2 existing structures; 21 cu yds concrete structures; 2,100 lbs reinforcement bars; 5,350 ft thermoplastic marking line; 1,212 sq ft pedestrian truss superstructure; 700 tons bituminous concrete surface course, SUPERPAVE; 1.2 acres hydraulic seeding; Federally funded. (60 Working Days) (Job No. C-91-287-00) (0-00986-0000) (5.00% DBE)
PREVIOUS LETTING: April 28, 2006 (Item 96)
52. Contract No. 83856 Cook County District 1
Section 05-00194-00-RP (DES PLAINES)
VARIOUS ALLEYS Project HD-8003(590)
Project consists of the reconstruction of 15 alleys including PCC pavement, new storm sewer installation, sidewalks, driveway removal and replacement, and all other incidental work to complete the project in the City of Des Plaines; includes 1,634 cu yds earth excavation; 3,064 cu yds trench backfill; 3,380 sq yds topsoil furnish and place; 3,380 sq yds sodding salt tolerant; 8,891 sq yds aggregate base course; 8,891 sq yds PCC pavement; 1,445 sq yds PCC driveway pavement; 3,530 sq ft PCC sidewalk; 9,290 sq yds pavement removal; 1,175 sq yds driveway pavement removal; 1,780 ft combination curb and gutter removal; 4,705 sq yds sidewalk removal; 4,760 ft storm sewers; 12 manholes; 2,397 ft combination concrete curb and gutter; 80 ft concrete curb; 165 tons temporary aggregate; 1,539 sq yds bituminous driveway removal and replacement; 455 ft storm sewer, ductile iron pipe; mobilization; traffic control and protection; Federally funded. (120 Working Days) (Job No. C-91-203-06) (1-20168-0000) (12.00% DBE)
53. Contract No. 83857 DuPage County District 1
Section 06-00079-00-RS (BARTLETT)
FAP Route 361 (STEARNS ROAD) Project F-361(23)
1.74 miles removal and replacement of bituminous surface, bituminous binder, pavement patching, curb & gutter and pavement marking on Stearns Road from South Bartlett Road to 350' west of County Farm Road in Bartlett; includes 2 drainage structure boxouts; 125 sq yds sod & topsoil furnish and place; 9,800 gals bituminous materials; 59 tons aggregate prime coat; 13,470 sq yds bituminous surface removal; 405 sq ft sidewalk; 161 ft combination curb & gutter removal & replacement; 570 tons aggregate shoulders; 40,727 ft pavement marking; 520 raised reflective pavement markers; 396 sq ft pavement marking removal; 240 ft detector loop replacement; 62 drainage structures inlet filter cleaning; 3,280 tons bituminous concrete surface, SUPERPAVE; 4,920 tons bituminous concrete binder, SUPERPAVE; 400 sq yds Class D patches; 61 sq yds bituminous pavement removal and replacement; 4 cal mos changeable message sign; mobilization; traffic control and protection; Federally funded. (Completion Date: November 15, 2006) (Job No. C-91-305-06) (1-20241-0000) (SUPERPAVE) (8.00% DBE)

54. Contract No. 83858 Will County District 1
Section 04-00037-00-WR (FRANKFORT)
FAU Route 3753 (SAUK TRAIL) Project M-8003(485)
The project will consist of the widening and resurfacing of Sauk Trail to provide a middle turn lane from Center Road to Larch Road, resurfacing from Larch Road to Pfeiffer Road and widening at the intersection of Sauk Trail to Pfeiffer Road to provide left turn lanes on Sauk Trail with work including curb and gutter, construction of a closed storm sewer system, sidewalk and driveway construction and all other items necessary to complete the project in the Village of Frankfort; includes removal of 30 trees (over 15 units diameter); 2,500 cu yds earth excavation; 3,600 cu yds removal and disposal of unsuitable material; 150 tons subbase granular material; 3,750 cu yds furnished excavation; 900 cu yds porous granular embankment, subgrade; 800 cu yds trench backfill; 2,046 cu yds topsoil excavation and placement; 10,419 sq yds topsoil furnished and place, 4"; 0.75 acre seeding, Class 2A; 7,200 sq yds sodding, salt tolerant; 7,875 ft perimeter erosion barrier; 5,478 sq yds subbase granular material; 232 tons aggregate surface course; 3,550 gals bituminous materials (prime coat); 15,110 sq ft PCC sidewalk; 2,060 sq yds bituminous surface removal; 2,003 sq yds driveway pavement removal; 565 ft combination curb and gutter removal; 670 sq yds Class D patches; 2,715 ft storm sewer, Class A; 24 manholes; 5,422 ft combination concrete curb and gutter; 13,559 ft thermoplastic pavement marking line; 5,478 sq yds bituminous base course 8" (SUPERPAVE); 1,718 tons bituminous concrete surface course, SUPERPAVE; 680 tons bituminous concrete binder course, SUPERPAVE; 290 tons aggregate for temporary access; 660 sq yds bituminous driveway pavement; mobilization; traffic control and protection; Federally funded. (70 Working Days)
(Job No. C-91-135-05) (1-20052-0000) (SUPERPAVE) (20.00% DBE)
55. Contract No. 83861 Cook County District 1
Section 00-00058-00-RS (FRANKLIN PARK)
FAU Route 1373 (BELMONT AVENUE) Project M-8003(310)
Improvement consists of resurfacing Belmont Avenue from Wolf Road to just east of LaPorte Avenue and the reconstruction of Belmont Avenue to include a full depth bituminous pavement, new storm sewer system, curb and gutter, railroad crossing and the relocation of existing water main and sanitary sewer from just east of LaPorte Avenue to Williams Drive all located in the Village of Franklin Park; includes 7,795 cu yds earth excavation; 1,265 cu yds porous granular embankment, subgrade; 1,575 sq yds bituminous surface removal 3"; 12,085 sq yds pavement removal; 6,325 ft combination curb and gutter removal; 5,017 sq ft sidewalk removal; 1,020 ft saw cuts; 14,286 sq yds aggregate subgrade 12"; 952 gals bituminous materials prime coat; 265 tons bituminous concrete surface course, SUPERPAVE, Mix D, N 70; 12,032 sq yds bituminous base course, SUPERPAVE 6 1/2"; 12,032 sq yds bituminous concrete pavement, (full depth), SUPERPAVE, 4 1/4"; 842 sq yds PCC driveway pavement; 14,654 sq ft PCC sidewalk; 318 sq yds Class C patches, Type IV, 6"; 427 sq yds aggregate shoulders; 110 lbs reinforcement bars, epoxy coated; 4,288 ft storm sewer, reinforced concrete culvert, storm drain and sewer pipe; 1,870 ft storm sewer removal; 2,371 ft storm sewer, ductile iron pipe, Class 52; 370 ft sanitary sewer removal; 5,017 sq ft sidewalk removal; 4,202 ft pipe underdrain; 79 catch basins; 25 manholes; 855 ft concrete curb, Type B; 7,328 ft combination concrete curb and gutter, Type B-6.12; 1,000 ft water main removal; 1,000 ft ductile iron water main Class 52; 2,753 ft thermoplastic pavement marking line; 21,300 ft temporary pavement marking; 3,014 cu yds trench backfill; 6,072 sq yds topsoil furnish and place; 6,072 sq yds sodding, salt tolerant; 7,707 ft perimeter erosion barrier; railroad protective liability insurance; traffic control and protection; Federally funded.
(170 Working Days) (Job No. C-91-147-03) (1-10675-0000) (SUPERPAVE) (12.00% DBE)
56. Contract No. 87319 DeKalb County District 3
Section 05-00001-01-PV (NORTHERN IL. UNIVERSITY)
WEST ACCESS ROAD Project HD-HPP-623(23)
Construction of an extension of the two northbound lanes and two southbound lanes north of the existing West Access Road including bituminous pavement with curb and gutter, a 16 foot median, sanitary sewer, water main, stormwater retention/detention facilities, sidewalk, roadway lighting, landscaping and all other work to complete the project on the Northern Illinois University Campus; includes removal of 99 trees; 56,868 cu yds earth excavation; 5,013 tons subbase granular material; 4,282 cu yds trench backfill; 5,069 cu yds topsoil excavation and placement; 6.4 acres seeding, Class I; 2,376 lbs fertilizer nutrients; 480 lbs temporary erosion control seeding; 406 tons aggregate base course; 2,739 gals bituminous materials (prime coat); 18,746 sq ft PCC sidewalk 5"; 77 ft combination curb and gutter removal; 327 ft pipe culverts; 1,193 ft ductile iron water main; 20 manholes; 4,415 ft combination concrete curb and gutter; 1,790 ft thermoplastic pavement marking; 13,900 ft electric cable in conduit; 3,904 ft storm sewers, Class A; 110 trees; 818 tons bituminous concrete surface course, SUPERPAVE; 1,227 tons bituminous concrete binder course, SUPERPAVE; 20 luminaires; 20 light poles; 1,299 ft sanitary sewers; mobilization; traffic control and protection; Federally funded.
(110 Working Days) (Job No. C-93-054-06) (3-10200-0000) (SUPERPAVE) (9.00% DBE)

57. Contract No. 87330 DeKalb County District 3
Section 05-00160-00-WR (DEKALB)
FAU Route 5348 (ANNIE GLIDDEN ROAD) Project HPP-2295(1)
Project consists of bituminous pavement reconstruction, bituminous bike path, precast box culverts, sidewalk, curb and gutter, storm sewer, water main, traffic signal modernization and interconnecting, landscaping, cleaning and painting steel bridge and all other work necessary to complete the project on FAU Route 5348 (Annie Glidden Road) from the Union Pacific Railroad Bridge to Fairview Drive in the City of DeKalb; includes 144 units tree removal; 24,977 cu yds earth excavation; 1,870 tons granular embankment, special; 4,946 cu yds trench backfill; 32,398 sq yds geotechnical fabric for ground stabilization; 14.4 acres seeding; 30 acres mulch, method 2; 503 sq yds stone riprap; 36,155 sq ft PCC sidewalk; 4,473 sq yds bituminous surface removal; 10,499 sq ft sidewalk removal; 535 sq yds Class D patches; 10,744 sq yds area reflective crack control treatment; cleaning and painting steel bridge; 24,290 lbs reinforcement bars, epoxy coated; 306 ft precast box culvert; 21 precast reinforced concrete flared end sections; 7,766 ft storm sewers, rubber gasket, Class A; 2,140 ft storm sewer removal; 3,391 ft ductile iron water main; 8 water valves; 8 fire hydrants with auxiliary valves and valve boxes; 71 catch basins, special; 35 manholes; 71 frames and grates, special; 14,536 ft combination concrete curb and gutter; 51,590 ft temporary pavement marking; 28,715 ft thermoplastic pavement marking line; 514 raised reflective pavement markers; 2,203 ft conduit pushed; 228 ft light pole foundations; 1 full-actuated controller and type IV cabinet; 10,512 ft electric cable in conduit; 4 steel combination mast arm assemblies and poles; 1 temporary traffic signal installation; 95 trees; 33,493 sq yds bituminous base course, SUPERPAVE; 3,887 tons bituminous concrete surface course, SUPERPAVE; 6,262 tons bituminous concrete binder course, SUPERPAVE; 364 tons leveling binder (machine method), SUPERPAVE; 110 tons incidental bituminous surfacing, SUPERPAVE; 17 signal heads, polycarbonate, LED; 990 sq yds bituminous driveway pavement, SUPERPAVE; 38,146 sq yds aggregate subgrade; 1 construction layout; 77,647 sq yds topsoil placement; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2007 Plus 10 Working Days) (Job No. C-93-089-06) (3-10199-0000) (SUPERPAVE) (10.00% DBE)
58. **This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)**
Contract No. 91357 McLean County District 5
Section 05-00047-09-RS
FAS Route 479 (CH 59) Project RS-479(107)
The placement of bituminous concrete binder and surface course, leveling binder, reflective crack control treatment system, aggregate shoulders and other miscellaneous items to complete the project on FAS Route 479 (CH 59) from 300E Road easterly and southerly to U.S. Route 136; includes 437 cu yds earth excavation; 1,067 sq yds aggregate base course; 3,975 gals bituminous materials (prime coat); 325 tons incidental bituminous surfacing; 34,826 sq yds area reflective crack control treatment, System A; 2,200 tons aggregate shoulders; 179 raised reflective pavement markers; 1,067 sq yds bituminous base course SUPERPAVE 7"; 2,550 tons bituminous concrete surface course, SUPERPAVE; 3,950 tons bituminous concrete binder course, SUPERPAVE; 1,200 tons leveling binder (machine method) SUPERPAVE; Federally funded. (20 Working Days) (Job No. C-95-303-06) (5-10578-0000) (6.00% DBE)
PREVIOUS LETTING: June 16, 2006 (Item 189)
59. Contract No. 95418 Lawrence County District 7
Section 03-00101-00-RS
FAS Route 801 (CH 10) Project RS-801(229)
Construction consists of 6.61 miles resurfacing, patching, pipe culverts and striping on FAS Route 801, CH 10 from the east city limits of Birds to IL Route 33; includes 4,468 tons leveling binder (machine method); 11,432 tons bituminous concrete surface course; 50 tons stone dumped riprap; 100 tons aggregate surface course; 350 sq yds Class D patches; 77,711 sq yds area reflective crack control treatment; 4,200 tons aggregate shoulders; 716 ft pipe culverts; 76 ft steel plate beam guardrail; 4 traffic barrier terminals; 3 calendar months engineer's field laboratory; 36,693 ft paint pavement marking-line 4"; traffic control and protection; Federally funded. (55 Working Days) (Job No. C-97-069-06) (7-10228-0000) (0.00% DBE)
60. Contract No. 95483 Fayette County District 7
Section 06-00054-00-PV (VANDALIA)
FAU Route 8435 (JOHNSON STREET) Project M-5068(6)
Construction consists of 0.084 mile of PCC pavement, curb and gutter, sidewalk, storm sewer and other items necessary to complete Johnson Street from 6th Street to 7th Street in the City of Vandalia; includes 281 cu yds earth excavation; 372 cu yds trench backfill; 1,645 sq yds subbase granular material; 1,370 sq yds PCC pavement 6 1/2"; 2,056 sq ft PCC sidewalk 4"; 671 ft storm sewers; 6 manholes; 1,062 ft combination concrete curb and gutter; 12 inlets; traffic control and protection; Federally funded. (45 Working Days) (Job No. C-97-062-06) (7-10373-0000) (0.00% DBE)
61. Contract No. 99263 Hamilton County District 9
Section 93-00076-00-RS
FAS Route 880 (CH 8) Project RS-880(105)
Construction consists of 3,915 miles of bituminous concrete resurfacing on FAS Route 880, CH 8 from Illinois Route 142 in Dahlgren easterly 3.915 miles; includes 5,519 tons bituminous concrete surface course; 6,270 tons leveling binder (machine method); 2,092 tons aggregate shoulders; 62,129 ft paint pavement marking-line 4"; traffic control and protection; Federally funded. (25 Working Days) (Job No. C-99-572-06) (9-10635-0000) (0.00% DBE)

62. Contract No. 99270 White County District 9
Section 06-00099-00-RS
FAS Route 1816 (CH 16) Project RS-1816(102)
Construction consists of 2.511 miles of bituminous concrete resurfacing on FAS Route 1816, CH 16 from Illinois Route 1, east of Norris City, running easterly 2.511 miles; includes 2,352 tons bituminous concrete surface course; 5,414 tons leveling binder (machine method); 29.3 tons stone dumped riprap; 1,577 tons aggregate shoulders; 70 feet insertion culvert liner 42"; 48,599 feet paint pavement marking-line 4"; 166 raised reflective pavement markers; traffic control and protection; Federally funded. (25 Working Days) (Job No. C-99-536-06) (9-10181-0000) (0.00% DBE)

63. Contract No. 60B32 Cook County District 1
Section (1213&3219)RS-7
FAU Route 2710 (DESPLAINES RIVER ROAD)
2.33 miles of 40 ft to 52 ft and variable width milling and bituminous concrete surface on Des Plaines River Road from U.S. Route 12 (Rand Road) to U.S. Route 14 (Dempster Street) and from Kennicott Court to Deveon Avenue in Des Plaines; includes 8,456 sq yds milling; 3,220 sq yds patching; 10,426 ft thermoplastic pavement marking; 120 ft detector loop replacement; 710 tons bituminous concrete surface course, SUPERPAVE, Mix D; mobilization; traffic control and protection. (25 Working Days) (Job No. C-91-322-06) (0-00857-1012) (SUPERPAVE) (5.00% DBE)

This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)

64. Contract No. 64B67 JoDaviess County District 2
Section D2 MRS 2006-12
FAP Route 308 (IL 84)
1.3 miles of 25 feet width intermittent bituminous resurfacing on IL Route 84 from U.S. Route 20 to the Carroll/JoDaviess County line near Hanover; includes 1,155 sq yds bituminous surface removal-butt joint; 583 tons aggregate shoulders; 42,748 ft paint pavement marking line; 91 raised reflective pavement markers; 1,416 tons bituminous concrete surface course, SUPERPAVE, N50; 1,133 tons leveling binder, machine method, SUPERPAVE, N50; mobilization; traffic control and protection. (15 Working Days) (Job No. C-92-148-05) (0-00857-2031) (SUPERPAVE) (0.00% DBE)
PREVIOUS LETTING: April 28, 2006 (Item 9)

BRIDGE SECTION

This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)

65. Contract No. 66614 Livingston County District 3
Section (25B-1)I
FAP Route 317 (US 24)
This project consists of bridge expansion joint repairs and deck resurfacing on the structure (S.N. 053-0152) carrying U.S. Route 24 over the South Fork Vermilion River approximately 0.26 miles west of the Illinois Route 47 intersection in Forrest; includes 698 sq yds bituminous concrete surface removal; 2,035 ft keyway repair; 40 floor drain extension; 624 lbs reinforcement bars, epoxy coated; 698 sq yds waterproofing membrane system; 570 ft thermoplastic pavement marking-line; 10 raised reflective pavement marker; 24 plug existing floor drains; 74 ft silicone joint sealer; 110 tons bituminous concrete surface course, SUPERPAVE, N70; 48 bearing pad adjustment; mobilization; traffic control and protection. (55 Working Days) (Job No. C-93-017-06) (0-00857-3001) (SUPERPAVE) (8.00% DBE)
PREVIOUS LETTING: January 20, 2006 (Item 77)

66. Contract No. 66673 Livingston County District 3
Section (DWIGHT MAINTENANCE YARD)T
OR Route 66 (OLD RT. 66)
This project consists of removing a one-span structure and installing a double 10' X 10' precast concrete box culvert located at the Dwight Maintenance Yard approximately 1.1 miles north of IL Route 17; includes 350 cu yds furnished excavation; 275 tons aggregate surface course; 2 box culvert end sections; 36 ft precast concrete box culvert; mobilization. (30 Working Days) (Job No. C-93-080-06) (0-00857-3015) (0.00% DBE)

67. Contract No. 66678 LaSalle County District 3
Section (50-4B)I-4
FAI Route 39 (I-39)
This project consists of emergency "call-out" work which involves bridge deck patching on the structure (SN 050-0191) carrying Interstate 39 over the Illinois River near LaSalle; includes 60 cu yds concrete removal; 60 cu yds concrete superstructure; 17,280 lbs reinforcement bars, epoxy coated; 16,022 ft thermoplastic pavement marking-line; 13,151 ft epoxy pavement marking line; 4,340 sq ft pavement marking removal; 180 raised reflective pavement markers; 1,780 ft preformed plastic pavement marking line; 6 impact attenuators; 1,200 sq yds protective shield; 28,900 sq yds ultra-thin bonded wearing course; mobilization; traffic control and protection. (Completion Date: June 30, 2007)
(Job No. C-93-094-06) (3-50191-0204) (3.00% DBE)

This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. *(Letting Set = All plans, proposals and addendums pertaining to a specific letting)*
Small Business Set-Aside.

68. Contract No. 70462 Vermilion County District 5

Section 48B
FAP Route 332 (IL 1)

This project consists of removing and replacing a box culvert on IL Route 1 just north of Rossville; includes 1,219 cu yds channel excavation; 100 ft exploration trench; 170 sq ft concrete sidewalk; 159 sq yds patches; removal of existing structures; 66 ft precast concrete box culvert; 68 ft combination concrete curb and gutter; 77 ft paint pavement marking line; 8 shade trees; mobilization; traffic control and protection. (20 Working Days) (Job No. C-95-011-05) (5-52450-0000) (7.00% DBE)

PREVIOUS LETTING: June 16, 2006 (Item 141)

69. THIS ITEM HAS BEEN WITHDRAWN

70. Contract No. 87329 Bureau County District 3

Section 05-12124-00-BR
TR 87 Project BROS-11(68)

Construction consists of a single span, 1 @ 79'-3" precast, prestressed concrete deck beam bridge carrying TR 87 over Pike Creek 1 mile south of LaMoille; includes 510 cu yds furnished excavation; 0.4 acre seeding; 369 tons dumped riprap special; 585 tons aggregate surface course; removal of existing structure; 16.6 cu yds concrete structures; 1,864 sq ft precast, prestressed concrete deck beams; 2,080 lbs reinforcement bars, epoxy coated; 405 ft driving and filling shells; 60 ft pipe culverts; Federally funded. (25 Working Days) (Job No. C-93-084-06) (3-10214-0000) (4.00% DBE)

71. Contract No. 93421 Adams County District 6

Section 02-23118-00-BR
TR 20 Project BROS-1(63)

Construction consists of a 223' 5" B/B abutment, 3 span, 160' steel truss main span with 30' precast, prestressed concrete deck beams carrying TR 20 over Bear Creek, 1.5 miles west of Marcelline; includes 2,480 cu yds channel excavation; 776 tons riprap, special; 305 tons aggregate base course; removal of existing structure; 172 cu yds concrete structures; 1,440 sq ft precast, prestressed concrete deck beams; 10,960 lbs reinforcement bars, epoxy coated; 1,400 ft driving steel piles; furnishing and erecting prefabricated bridge superstructure; 2 underwater structure excavation and protection; 103 tons bituminous concrete surface course; traffic control and protection; Federally funded. (90 Working Days) (Job No. C-96-208-06) (6-10221-0000) (0.00% DBE)

72. Contract No. 93422 Sangamon County District 6

Section 05-00445-00-BR (SPRINGFIELD)
FAU Route 8009 (AMOS AVENUE) Project BRM-5146(61)

Project consists of the complete removal of the existing timber pile structure and replacing it with a new triple barrel box culvert including construction of a new combination curb and gutter, full-depth bituminous concrete pavement, sidewalks and all other work necessary to complete the project on FAU Route 8009 (Amos Avenue) over drainage ditch 2 blocks north of Jefferson Street in Springfield; includes 460 cu yds earth and channel excavation; 135 lbs fertilizer nutrients; 60 sq yds stone riprap; 420 tons subbase granular material; 24.3 tons aggregate surface course; 275 gals bituminous materials (prime coat); 2,015 sq ft PCC sidewalk 4"; removal of existing structures; 58,670 lbs reinforcement bars; 274.4 cu yds concrete box culverts; 287 ft combination concrete curb and gutter; 30 ft storm sewers, Class A; 550 sq yds bituminous concrete pavement (full depth), SUPERPAVE; 472 tons rock fill (replacement); mobilization; traffic control complete; Federally funded. (Completion Date: December 15, 2006) (Job No. C-96-242-06) (6-10237-0000) (15.00% DBE)

- This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)
73. Contract No. 95469 Fayette County District 7
Section 02-00104-00-BR
FAS Route 712 (CH 24) Project BRS-712(105)
Remove existing structure carrying CH 24 over Ash Creek and replace with a 2-span precast, prestressed concrete deck beam bridge with bituminous approaches, aggregate shoulders and guardrail located 1.5 miles east of Ramsey; includes 48 units tree removal; 670 cu yds earth excavation; 75 cu yds channel excavation; 0.65 acre seeding; 1,040 tons stone riprap; 904 tons aggregate base; 282 tons aggregate shoulders; 32.4 cu yds concrete structure; 3,210 sq ft precast, prestressed concrete deck beams; 4,470 lbs reinforcement bars; 425 ft steel plate beam guardrail; 301 ft furnish steel piles; 10.8 cu yds concrete encasement; 50 ft pipe culverts; 30 tons bituminous concrete surface, SUPERPAVE; 8 tons leveling binder, SUPERPAVE; 1,324 sq yds bituminous concrete pavement, SUPERPAVE; 472 ft breaking paved ditch; 6 setting piles in rock; 241 ft Portland Cement mortar fairing course; traffic control and protection; Federally funded. (30 Working Days) (Job No. C-97-090-02) (7-10185-0000) (SUPERPAVE) (3.00% DBE)
PREVIOUS LETTING: June 16, 2006 (Item 153)
74. Contract No. 95472 Jasper County District 7
Section 05-00101-00-BR
CH 11 Project RS-79(132)
Construction consists of a single span, 1 @ 41" – 6" precast prestressed concrete deck beam bridge carrying CH 11 over west fork of Wetweather Creek, 2 miles southeast of Bogota; includes 360 cu yds channel excavation; 0.40 acre seeding; 205 tons stone dumped riprap; 80 tons aggregate base course; 200 tons aggregate surface course; 1 removal of existing structures; 19.8 cu yds concrete structures; 1,120 sq ft precast prestressed concrete deck beams; 2,520 lbs reinforcement bars; 270 ft driving steel piles; 113 ft pipe culverts; 4 traffic barrier terminals; Federally funded. (30 Working Days) (Job No. C-97-100-06) (7-10334-0000) (4.00% DBE)
75. Contract No. 95480 Clark County District 7
Section 05-00261-00-BR
FAS Route 690 (FOX ROAD) Project RS-690(108)
Project consists of the removal of existing bridge and construction of a 2 span precast, prestressed concrete deck beam bridge (27" depth), guardrail and all other work necessary to complete the project on FAS Route 690 (Fox Road) over Hurricane Creek 5.5 miles southwest of Marshall; includes 370 cu yds channel excavation; 570 tons riprap, special; removal of existing structures; 27.2 cu yds concrete structures; 3,510 sq ft precast, prestressed concrete deck beams (27" depth); 4,200 lbs reinforcement bars; 266 ft steel railing; 240 ft furnishing steel piles; 50 ft steel plate beam guardrail; 8 traffic barrier terminals; 5 setting piles in rocks; mobilization; Federally funded. (25 Working Days) (Job No. C-97-133-06) (7-10584-0000) (0.00% DBE)
76. Contract No. 95481 Fayette County District 7
Section 05-07128-00-BR
TR 416 Project BROS-51(73)
Remove existing structure and replace with a single span precast prestressed concrete deck beam bridge with riprap, earthwork and aggregate surface on TR 416 over an unnamed tributary to the Kaskaskia River 3 miles Northwest of St. Peter; includes 34 cu yds earth excavation; 323 cu yds channel excavation; 0.02 acre seeding; 1 temporary ditch check; 88 tons stone dumped riprap; 90 tons aggregate surface course; remove existing structure; 18.2 cu yds concrete structure; 1,440 sq ft precast prestressed concrete deck beams; 2,300 lbs reinforcement bars; 120 ft steel railing; 187 ft furnish steel piles; 187 ft driving steel piles; test steel pile; 2.1 cu yds concrete encasement; mobilization; Federally funded. (30 Working Days) (Job No. C-97-101-06) (7-10286-0000) (0.00% DBE)
77. Contract No. 95484 Shelby County District 7
Section 05-17117-00-BR
TR 133 Project BROS-173(143)
Remove existing structure and replace with a 3-span precast prestressed concrete deck beam bridge with aggregate surface on TR 133 over Robinson Creek 2.5 miles south of Westervelt; includes 0.1 acre tree removal; 867 cu yds earth excavation; 880 cu yds channel excavation; 1,705 cu yds furnished excavation; 0.9 acre seeding and mulching; 243 lbs fertilizer nutrient; 699 tons stone riprap; 489 sq yds filter fabric; 845 tons aggregate surface; remove existing structure; 99.0 cu yds concrete structures; 3,456 sq ft precast prestressed concrete deck beams; 8,230 lbs reinforcement bars; 289 ft steel railing; 435 ft furnish steel piles; 17 cu yds concrete encasement; 38 ft pipe culverts; 4 traffic barrier terminals; mobilization; underwater structure excavation protection; Federally funded. (55 Working Days) (Job No. C-97-135-06) (7-10348-0000) (0.00% DBE)

78. Contract No. 95486 Wayne County District 7
Section 03-07118-00-BR
TR 587 Project BROS-191(51)
Construction consists of a single span, 1 @ 50'-0" precast prestressed concrete deck beam bridge carrying TR 587 over tributary to Four Mile Creek, 4.5 miles southwest of Wayne City; includes 603 cu yds furnished excavation; 0.5 acre seeding; 80 tons stone dumped riprap; 397 tons aggregate base course; 1 removal of existing structures; 20.2 cu yds concrete structures; 1,200 sq ft precast prestressed concrete deck beams; 2,200 lbs reinforcement bars; 455 ft driving steel piles; 38 ft pipe culverts; traffic control and protection; Federally funded. (30 Working Days)
(Job No. C-97-136-06) (7-10256-0000) (3.00% DBE)
79. Contract No. 97277 Jersey County District 8
Section 04-07118-00-BR
TR 137 Project BROS-83(38)
Remove existing structure and replace with a single span precast prestressed concrete deck beam bridge with open reinforced concrete abutments and approach roadway embankments on TR 137 over Little Piasa Creek 0.8 mile west of Brighton; includes 0.2 acre tree removal; 258 cu yds earth excavation; 51 cu yds channel excavation; 1,125 cu yds furnished excavation; 0.6 acre seeding; 314 tons stone dumped riprap; 544 sq yds filter fabric; remove existing structure; 67 cu yds structure excavation; 45.5 cu yds concrete structures; 1,312 sq ft precast prestressed concrete deck beams 27"; 3,970 lbs reinforcement bars; 112 ft steel railing; 222 ft furnished and drive steel piles; test pile; 2 terminal markers; mobilization; 4 traffic barrier terminals; traffic control and protection; Federally funded. (30 Working Days)
(Job No. C-98-310-06) (8-10041-0000) (10.00% DBE)
80. Contract No. 99251 Hamilton County District 9
Section 01-06128-00-BR
TR 229 Project BROS-65(37)
Construction consists of a triple span 3 @ 25'-0" precast prestressed concrete deck beam bridge carrying TR 229 over Sullivan Branch, 2 miles north of Macedonia; includes 230 tree removal; 287 cu yds furnished excavation; 493 tons stone dumped riprap; 325 tons aggregate surface course; 1 removal of existing structures; 30.8 cu yds concrete structures; 1,800 sq ft precast prestressed concrete deck beams; 4,080 lbs reinforcement bars; 528 ft driving steel piles; Federally funded. (35 Working Days) (Job No. C-99-529-06) (9-10162-0000) (7.00% DBE)
81. Contract No. 99261 Jackson County District 9
Section 04-02119-00-BR
TR 209A(GLENN ROAD) Project BROS-77(41)
Project consists of the removal of an existing three span precast concrete slab bridge on timber pile abutments and piers and construction of a three span precast prestressed concrete deck beam bridge (21" and 27" depth) on steel pile bent abutments and piers including roadway approach work and incidental work required to complete the section on TR 209A (Glenn Road) over Sugar Creek, 3 miles northwest of Carbondale; includes 0.1 acre tree removal; 510 cu yds earth and channel excavation; 500 cu yds furnished excavation; 90 tons porous granular embankment; 0.6 acre seeding, Class 2 (special); 2,900 sq yds erosion control blanket; 850 tons riprap, special; 380 tons aggregate surface course; 1 removal of existing structures; 40.8 cu yds concrete structures; 4,800 sq ft precast prestressed concrete deck beams (21" and 27" depth); 5,400 lbs reinforcement bars; 1,260 ft furnishing steel piles; 50 ft steel plate beam guardrail; 8 traffic barrier terminals; mobilization; Federally funded. (40 Working Days) (Job No. C-99-543-05) (9-10042-0000) (10.00% DBE)

ELECTRICAL SECTION

82. Contract No. 76973 Madison-St. Clair-St.Louis Mo Counties District 8
Section DIST. 8 ITS 2006-2
FAI Route 55/70 (I-55/70) Project ITS-41-7(104)
Installation of permanent communications devices along I-55/70 from east of IL Route 111 to the first pier of the Poplar Street Bridge in St. Louis, Missouri; includes 1,620 lbs fertilizers; 4 acres seeding; 400 lbs temporary erosion control seeding; 10 inlets and pipe protection; 66 sq ft sign panel; 156 lbs structural steel sign support-breakaway; 25.9 cu yds concrete foundations; 22.5 ft drilled shaft concrete foundations; 2,791 ft locating underground cable; 6 service installations; 35,126 ft conduit in trench; 599 ft conduit pushed; 1,582 ft conduit attached to structure; 37 junction boxes; 56 concrete handholes; 35,241 trench and backfill; 5 steel light poles; 42,895 ft fiber optic cable in conduit; 38,466 ft electric cable; 3 CCTV camera systems; 1 wide area network; 400 fiber optic utility markers; configure digital video encoder and digital video decoder; 5 air conditioned controller cabinets; 1 media converter; modify 15 existing controller cabinets; 5 radar vehicle detection systems; 3 relocate existing ITS equipment; 5 wired communication data converters; mobilization; traffic control and protection; Federally funded. (Completion Date: July 17, 2007)
(Job No. C-75-016-06) (ITS Program) (5.00% DBE)
83. Contract No. 83860 Cook County District 1
Section 06-00241-00-TL (OAK PARK)
FAU Route 1398 (CHICAGO AVENUE) Project CMM-8003(624)
Fiber optic interconnection of 3 existing signalized intersections along Chicago Avenue from Marion Avenue to Oak Park Avenue in Oak Park and includes conduit installation, detector loop installation and traffic control; includes 3,106 ft conduit pushed; 7 handholes; 3 maintenance of existing traffic signal installations; full-actuated controller; 2 transceivers-fiber optic; 2,129 ft electric cable in conduit, lead-in; 6 inductive loop detectors; 217 ft detector loop; pedestrian push-button; remove existing traffic signal equipment; 2,364 ft electric cable in conduit, tracer; reoptimize existing signal system; 2,364 ft fiber optic cable in conduit; 4 modify existing cabinet equipment and appurtenances; mobilization; traffic control and protection; Federally funded. (35 Working Days) (Job No. C-91-304-06) (1-11003-0000) (0.00% DBE)

MISCELLANEOUS SECTION

84. Contract No. 62962 Cook County District 1
Section 530CRC-PP
FAP Route 342 (IL 53 EXT)
0.93 mile of patching along IL Route 53 Extension from IL Route 68 (Dundee Road) to Lake-Cook Road in Arlington Heights; includes 2,715 sq yds Class D patches; 2,660 ft polyurea pavement marking; mobilization; traffic control and protection. (Completion Date: November 6, 2006)
(Job No. C-91-215-05) (0-00857-1022) (5.00% DBE)
PREVIOUS LETTING: January 20, 2006 (Item 41)
PREVIOUS LETTING: June 16, 2006 (Item 234)
85. Contract No. 66655 Kankakee County District 3
Section (1R)I
FAP Route 330 (IL 17)
5.7 miles of variable width pavement patching on IL Route 17 from Eastridge Road to IL Route 1 near Kankakee; includes 1,113 sq yds Class A patches; 1,113 sq yds patching reinforcement; 8,100 ft saw cuts; 126,816 ft paint pavement marking line; mobilization; traffic control and protection. (25 Working Days) (Job No. C-93-075-06) (0-00857-3010) (4.00% DBE)
86. Contract No. 66664 Iroquois County District 3
Section D3 TREE PLANTING 2006-2
FAI Route 57 (I-57)
This project consists of planting woody plants in designated areas along interstate 57 near Clifton; includes 193 shade trees; 662 shrubs; 90 evergreens; mobilization. (Completion Date: December 01, 2007)
(Job No. C-93-055-05) (3-87337-0601) (0.00% DBE)
PREVIOUS LETTING: November 18, 2005 (Item 36)

87. Contract No. 66674 LaSalle County District 3
Section (6)DM
FAS Route 1279 (IL 178) Project HD-1279(104)
This project consists of removing a house foundation, a two story house, and a house with a garage located in Utica; includes 1,365 sq yds topsoil; 0.28 acre seeding; building removal no. 1-3; removal and disposal of friable asbestos, building no. 1-2; removal and disposal of non-friable asbestos, building no. 1-2; mobilization. Federally Funded (15 Working Days) (Job No. C-93-081-06) (3-44320-0005) (0.00% DBE)
88. Contract No. 68545 Woodford County District 4
Section D4 PATCHING 2007
FAI Route 39 (I 39)
This project consists of patching the northbound lanes of Interstate 39 from 3 miles south of Illinois Route 116 to 1 mile north of Illinois Route 116 near Minonk; includes 3,012 sq yds patches; 12,204 ft saw cuts; 2,861 tie bars; traffic control and protection; Federally funded. (35 Working Days) (Job No. C-94-014-06) (0-00857-4007) (0.00% DBE)

89. Contract No. 74154 Effingham County District 7
Section D-7 WETLAND MITIGATION 1
FAP Route 774 (IL 33)
Wetland mitigation consisting of construction of an earth berm, precast block revetment, tree and perennial planting and seeding located along IL Route 33 north of Wabash River Overflow, 0.25 mile north of Ford Avenue in Effingham; includes 1,212 ft temporary fence; 505 cu yds earth excavation; 4.6 acres seeding; 4.6 acres mulch; 460 lbs temporary erosion control seeding; 6 temporary ditch checks; 150 ft perimeter erosion barrier; 33 sq yds precast block revetment mat; 85 shade trees; 85 tree care; 85 units tree intermediate and shrub watering; 1.7 units perennial plants; 85 tree trunk predator protection; 3.24 gals weed control; clearing and grubbing; 6.8 acres maintenance mowing; mobilization. (Completion Date: October 15, 2009) (Job No. C-97-053-06) (7-77710-0500) (10.00% DBE)
PREVIOUS LETTING: June 16, 2006 (Item 169)

90. Contract No. 64A11 Whiteside County District 2
Section 115M
FAP Route 22 (IL 78)
This project consists of intersection improvements at IL Route 78 and 3rd Street in Prophetstown; includes 64 cu yds trench backfill; 816 sq yds bituminous surface removal; 157 sq yds pavement patching; 114 ft storm sewers; 2 inlets; 621 ft thermoplastic pavement marking-line; construction layout; 69 tons bituminous concrete surface course, SUPERPAVE, N50; mobilization; traffic control and protection. (15 Working Days)
(Job No. C-92-065-06) (2-97627-0001 & 2-97627-0002) (SUPERPAVE) (0.00% DBE)
PREVIOUS LETTING: June 16, 2006 (Item 31)

91. Contract No. 64B01 Rock Island County District 2
Section 1-3-LS
FAP Route 595 (IL 5) Project F-595(29)
This project involves (wetland mitigation) landscaping with trees and plants at the wetland site adjacent to Interstate 74/280 approximately 7 miles from the Milan Beltway and Green Rock Wetland Mitigation site; includes 4,995 lbs fertilizer nutrient; 18 acres seeding; 18 acres mulch method; 500 sq yds erosion control blanket; 1,577 shade trees; 3.94 units seeding; mobilization; Federally funded. (15 Working Days) (Job No. C-92-127-05) (2-95140-0207) (0.00% DBE)
PREVIOUS LETTING: June 16, 2006 (Item 175)

This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. *(Letting Set = All plans, proposals and addendums pertaining to a specific letting)*

92. Contract No. 44917 Cook County District 1
Section PULLMAN HISTORIC SITE
PARK ROAD

Pathway construction at the Pullman Historic Site located near Lake Calumet; includes 20 units tree removal; 1,045 cu yds earth excavation; 100 cu yds trench backfill; 17,260 sq yds topsoil; 3 acres seeding; 860 tons aggregate base course; 15 sq yds concrete pavement; 175 sq ft concrete sidewalk; 25 sq yds pavement patching; 40 tons aggregate shoulders; 52 ft storm sewers; 115 ft ductile iron water main; 18 shade trees; 614 shrubs; 735 perennial plants; mobilization; traffic control and protection. (25 Working Days) (Job No. C-30-012-06) (0-00197-1001) (0.00% DBE)

PREVIOUS LETTING: June 16, 2006 (Item 223)

ILLINOIS DEPARTMENT OF NATURAL RESOURCES
LAND RECLAMATION

- 1LR. Williamson County
AML-GWME-0514
WILLIAMSON COUNTY AIRPORT REMEDIAL RECLAMATION
The proposed reclamation project is located approximately 1 mile east of Energy, Illinois. The proposed work includes approximately 320 cu yds of earth excavation, 350 cu yds of riprap excavation, 100 tons of dumped riprap, 77 cu yds of grout for use with riprap, the construction of two temporary ditch checks (riprap) with two 70 foot PE pipe culverts, the construction of two small concrete structures with reinforcement bar, the construction and removal of one cofferdam, the repair of two private water lines, the restoration of one section of concrete box culvert and the seeding and soil amendments for 4.5 acres. (0.00% DBE)

- 2LR. This item is being re-advertised for bids. Contractors and suppliers who requested plans and proposals for this item from a previous letting should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for the CD ROM Letting Set. (*Letting Set = All plans, proposals and addendums pertaining to a specific letting*)
Saline County
AML-GSIE-0513
GALATIA C.C. #5 MAIN SHAFT RECLAMATION PROJECT
The proposed project is located west of the city of Galatia and south of IL Route 34. The proposed work will include sealing a collapsed mine shaft with approximately 1,694 tons of CA-1, followed by a Class SI Concrete Plug of 200 cu yds, capped by a soil mound requiring an estimated 3,185 cu yds of earth excavation. Work also includes approximately 2 acres of special clearing, the placement of 1,989 sq yds of erosion control blanket, and seeding and soil amendments for 3.5 acres. (0.00% DBE) [PRE-BID CONFERENCE](#)
PREVIOUS LETTING: June 16, 2006 (Item 1LR)

REVIEW AND INSPECTION

Items 1X, 2X, 3X and 4X are NOT included in the August 4, 2006 Letting but are expected to be included in an undetermined, future letting. They are being published to allow for review and inspection by potential bidders and suppliers. They are NOT for bidding purposes at this time.

They will not be available on the IDOT Web Site until after July 21, 2006.

When the following items are for bid in said future letting, they will available to bid in the following combinations:

Combination No. 1 1X, 2X, 3X and 4X
Combination No. 2 1X and 3X
Combination No. 3 2X and 4X

PLEASE NOTE: If a combination bid is submitted, an individual item bid must also be submitted for each individual item. Failure to include an individual bid for each of these items will cause the combination to be declared irregular. If a combination bid is not submitted, the bidder may submit an individual bid on all, some, or none of the items.

- 1X. Contract No. 60A62 Cook County District 1
 Section (1919.15,2021-922PT1&PT2)R-1
 FAI Route 94/90 (I-94 (DAN RYAN)/I-90) Project ACIM-000-S(518)
 1.43 miles of reconstruction of the northbound local lanes and westbound Skyway local ramp on FAI Route 94/90 (Dan Ryan Expressway) between 63rd Street and Garfield Boulevard in Chicago; includes 38,284 cu yds earth excavation; 2,426 cu yds removal and disposal of unsuitable material; 1,684 cu yds porous granular embankment; 3,102 cu yds trench backfill; 42,709 sq yds geotechnical fabric for ground stabilization; 12,937 sq yds topsoil; 3.06 acres seeding; 37,727 sq yds subbase granular material; 29,253 sq yds continuously reinforced concrete pavement; 39,601 sq yds pavement removal; 204 cu yds structure excavation; 153.6 cu yds concrete; 1,315 sq ft rustication finish; 18,160 lbs epoxy coated reinforcement bars; 4,362 ft storm sewers; 172 cu yds sand backfill; 10,134 ft pipe underdrains; 3,420 ft concrete curb and gutter; 10,365 sq ft concrete median surface; 787.5 ft steel plate beam guardrail; 6 traffic barrier terminals; 1086.1 sq ft sign panel; 70,264 ft polyurea pavement marking; 966 ft trench and backfill; 153 shrubs; 652 vines; 21,595 sq ft temporary soil retention system; 284,719 lbs soil stabilizer; 205 sq yds temporary pavement (interstate); 10,493 sq yds concrete shoulders; 42,709 sq yds stabilized subbase; 29,253 sq yds pavement reinforcement; 150 ft aerial cable; 653 ft conduit embedded in structure; 1,008 sq ft structural repair of concrete; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2007 Plus 05 Working Days) (Job No. C-91-090-06) (1-74823-0523) (15.00% DBE)
- 2X. Contract No. 60A63 Cook County District 1
 Section (1919.15,2021-922PT1&PT2)R-2
 FAI Route 94/90 (I-94/90 (DAN RYAN)) Project IM-000-S(516)
 0.99 mile of reconstruction of the southbound local lanes of FAI Route 94/90 (Dan Ryan Expressway) between 63rd Street and Garfield Boulevard in Chicago; includes 34,429 cu yds earth excavation; 2,033 cu yds removal and disposal of unsuitable material; 1,555 cu yds porous granular embankment; 967 cu yds trench backfill; 35,907 sq yds geotechnical fabric for ground stabilization; 8,544 sq yds topsoil; 1.61 acres seeding; 35,703 sq yds subbase granular material; 27,335 sq yds continuously reinforced concrete pavement; 30,474 sq yds pavement removal; 61 cu yds concrete removal; 71 cu yds structure excavation; 116.5 cu yds concrete superstructure; 1,005 sq ft rustification finish; 14,161 lbs epoxy coated reinforcement bars; 205 cu yds sand backfill; 5,240 ft pipe underdrains; 1,661 ft concrete curb and gutter; 5,638 sq ft concrete median surface; 125 ft steel plate beam guardrail; 1,107.5 sq ft sign panel; 59,148 ft polyurea pavement marking; 848 ft trench and backfill; 607 shrubs; 342 vines; 206,725 lbs soil stabilizers; 35,907 sq yds stabilized subbase; 27,335 sq yds pavement reinforcement; 6,520 sq yds concrete shoulders; 351 ft conduit embedded in structure; 2,814 sq ft structural repair of concrete; 12,531 sq ft temporary soil retention system; 6 heavy-duty handholes; 2 traffic barrier terminals; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2007 Plus 05 Working Days) (Job No. C-91-091-06) (1-74823-0524) (12.00% DBE)

- 3X. Contract No. 62301 Cook County District 1
Section (2021-922PT2ETC2324.6-1P)R-10
FAI Route 94/90 (I-94 (DAN RYAN)/I-90) Project ACIM-000-S(519)
3.16 miles of reconstruction of the northbound local lanes of I-94/90 (Dan Ryan Expressway) between Garfield Boulevard and 31st Street in Chicago; includes 98,981 cu yds earth excavation; 217 cu yds rock excavation; 9,658 cu yds removal and disposal of unsuitable material; 1,712 cu yds porous granular embankment; 3,902 cu yds trench backfill; 124,027 sq yds geotechnical fabric for ground stabilization; 63,713 sq yds topsoil; 15.98 acres seeding; 124,028 sq yds subbase granular material; 124,027 sq yds stabilized subbase; 2,219 sq yds concrete base course; 6,214 sq yds concrete pavement (jointed); 430 sq yds bridge approach pavement; 83,582 sq yds continuously reinforced concrete pavement; 2,162 sq yds milling; 114,998 sq yds pavement removal; 24,730 sq yds concrete shoulders; removal of existing structure; 18 cu yds concrete removal; 631 cu yds structure excavation; 269.4 cu yds rock excavation for structures; 670 cu yds concrete; 1,608 sq yds bridge deck grooving; 8,182 sq ft rustication finish; 1,692 stud shear connectors; 6,541 sq ft untreated timber lagging; 4,341 ft soldier piles; 99,190 lbs epoxy coated reinforcement bars; 21,866 ft pipe underdrains; 3,566 ft concrete gutter; 17,289 ft concrete curb and gutter; 11,880 sq ft concrete median surface; 1,012 ft steel plate beam guardrail; 16 traffic barrier terminals; 60,458 ft shoulder rumble strip; 8,333.6 sq ft sign panel; 520 ft overhead sign structure-span; 367.8 ft overhead sign structure walkway; 117,388 ft polyurea pavement marking; 4,127 ft trench and backfill; 6 luminaires; 3 aluminum light poles; 1,132 vines; 8.36 units perennial plants; 19 roadway cleaning; 20 pile extraction; 218 ft fluted knee wall; 1,669,253 lbs soil stabilizers; 654 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 83,582 sq yds pavement reinforcement; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2007 Plus 05 Working Days) (Job No. C-91-418-01) (1-74823-0513) (SUPERPAVE) (18.00% DBE)
- 4X. Contract No. 62303 Cook County District 1
Section (2021-922PT2ETC2324.6-1P)R-11
FAI Route 94/90 (I-94/90 (DAN RYAN EXPWY)) Project ACIM-000-S(517)
3.02 miles of reconstruction of the southbound local lanes and ramps along I-94/90 (Dan Ryan Expressway) between Garfield Boulevard and 31st Street in Chicago; includes 112,986 cu yds earth excavation; 10,252 cu yds removal and disposal of unsuitable materials; 1,575 cu yds porous granular embankment; 3,234 cu yds trench backfill; 119,406 sq yds geotechnical fabric for ground stabilization; 63,842 sq yds topsoil; 16.0 acres seeding; 120,406 sq yds subbase granular material; 127,796 sq yds stabilized subbase; 4,265 sq yds concrete base course; 6,013 sq yds concrete pavement; 400 sq yds bridge approach pavement; 80,645 sq yds continuously reinforced concrete pavement; 3,931 sq yds milling; 107,704 sq yds pavement removal; 25,903 sq yds concrete shoulders; removal of 2 existing structures; 87 cu yds concrete removal; 803 cu yds structure excavation; 156 cu yds rock excavation for structures; 989 cu yds concrete; 142 sq yds bridge deck grooving; 12,868 sq ft rustication finish; 2,778 stud shear connectors; 9,342 sq ft untreated timber lagging; 5,815 ft soldier piles; 144,630 lbs epoxy coated reinforcement bars; 23,367 ft pipe underdrains; 3,445 ft concrete gutter; 20,734 ft concrete curb and gutter; 18,805 sq ft concrete median surface; 988 ft steel plate beam guardrail; 15 traffic barrier terminals; 60,655 ft shoulder rumble strip; 7,557 sq ft sign panel; 754 ft overhead sign structure-span; 26 ft overhead sign structure-cantilever; 532 ft overhead sign structure walkway; 112,139 ft polyurea pavement marking; 3,979 ft trench and backfill; 239 shrubs; 1,634 vines; 17,647 sq ft temporary soil retention system; 34,266 cu ft drilling and setting soldier piles (in soil); 1,695,770 lbs soil stabilizers; 719 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 80,645 sq yds pavement reinforcement; 56 ft drilled shaft in soil; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2007 Plus 05 Working Days) (Job No. C-91-420-01) (1-74823-0514) (SUPERPAVE) (18.00% DBE)

STATE OF ILLINOIS
Department of Transportation
Division of Aeronautics

This Bulletin constitutes official notification to Contractors of the intention to receive bids for Airport related work. The Transportation Bulletin is available on the Department's Internet website at <http://www.dot.il.gov>. The following phone numbers and e-mail address are available if assistance is needed:
Phone: 217/782-7806; Fax: 217/785-1141; TDD: 217/524-4875;
E-mail: duncanjr@dot.il.gov.

INVITATION FOR BIDS

1. TIME AND PLACE OF OPENING PROPOSALS: Sealed bids, subject to the conditions contained herein, will be received by the Department of Transportation at the Auditorium in the Harry R. Hanley Building, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois, until 10:00 A.M. prevailing time, August 4, 2006. These bids will, at that time, be publicly opened and read for furnishing all labor and materials, and performing all work for the Project(s) listed and defined in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics.
2. INSTRUCTIONS TO BIDDERS:
 - a. Plans and Contract Documents. Plans and Contract Documents for those Project(s) specified in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics may be examined and reviewed at the following offices:
 - (1) Department of Transportation, Division of Aeronautics, One Langhorne Bond Drive, Capital Airport, Springfield, Illinois.
 - (2) Department of Transportation, Harry R. Hanley Building, Plans and Contracts Office, Room 323, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois.
 - (3) Office of the consulting engineer(s).
 - b. Contract documents for bidding will not be loaned to prospective bidders. They may be purchased on CD-ROM at the above address of the Chief Contract Official. A form for purchases is included in the Transportation Bulletin, and is entitled "Request for Authorization to Bid/or Not For Bid Status" (BDE 124 INT). A charge of \$35 will be made for each Letting set (Letting set = all plans & proposals pertaining to a specific Letting). Payment shall be made by check, bank draft or money order payable to the order of Treasurer, State of Illinois. Currency will not be accepted. No refunds will be made for CD-ROMs returned or not bid. Electronic plans and/or proposals may also be downloaded from the Department's web site www.dot.il.gov.

Contractors wanting to bid must submit the properly completed "Request for Proposal Forms and Plans & Request for Authorization to Bid" (BD 124) and the properly completed ORIGINAL "Affidavit of Availability" (BC 57) to Room 322 or 323 no later than 4:30 p.m. prevailing time, three (3) days prior to letting date. The Authorization to Bid request cut-off date is 4:30 p.m. prevailing time, August 1, 2006.

- c. Each bid shall be accompanied by one (1) copy of a Bid Bond on Form BD 356B in the amount, which is not less than five (5) percent of the aggregate amount of the bid.
- d. Pre-Qualification Rating. The Illinois Department of Transportation pre-qualification ratings and other applicable evidence of competency of bidders to perform the work contemplated will be utilized for all Service Bulletin items. This pre-qualification rating will be established on the basis of a Financial Statement and Experience Questionnaire.
- e. Requirements for Corporations outside the State of Illinois. Before any Contract is executed, a Corporation from another State must conform to the Statutes of the State of Illinois, and may be asked to furnish a copy of the certificate from the Secretary of State, State of Illinois, showing that such foreign corporation is authorized to do business in the State of Illinois.
- f. Civil Rights Act of 1964. The Illinois Department of Transportation, Division of Aeronautics, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-assisted programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds or race, color, or national origin in consideration for an award.

In a case in which a bidder or prospective contractor or proposed subcontractor who has participated in a previous contract or subcontract subject to the equal opportunity clause has not filed a compliance report due under applicable instructions, such bidder, prospective contractor, or proposed subcontractor shall submit a compliance report prior to the award of the proposed contract or subcontract. When a determination has been made to award a contract to a specific contractor, such contractor shall prior to award, furnish such other pertinent information regarding his own employment policies and practices as well as those of his proposed subcontractors as the Sponsor, or the Executive Vice Chairman of the President's Committee may require.

For any contract or subcontract for \$50,000.00 or more, and having 50 or more employees, the contractor or subcontractor will be required to maintain a written Affirmative Action Plan.

g. Special Requirements.

- (1) Payment to Labor. The successful bidder will be required to pay to the laborers, workmen, mechanics, and other employees for the work under the contracts, not less than the general prevailing wage for each craft, trade or occupation, and not less than the minimum wage rates as shall be established by the U. S. Secretary of Labor for federally assisted projects and by the Illinois Department of Labor for state/local projects.
- (2) Affirmative Action Requirements - Equal Employment Opportunity. Various contractor, union and minority organizations have prepared specific plans for Equal Employment Opportunity. Should such a plan or plans apply to the proposed project(s) listed below, the Bid Conditions will be included in the Contract Document for that project, and all bidder's, prospective contractors and/or subcontractors shall be required to comply with any and all provisions set forth therein.

- h. Specifications. The proposed work is to be constructed in accordance with the requirements of the Illinois Standard Specifications for Construction of Airports, dated January, 1985, the Supplemental Specifications and Recurring Special Provisions, adopted July 1, 2004 and the Special Provisions specified in the proposal. The Illinois Standard Specifications for Construction of Airports and the Supplemental Specifications and Recurring Special Provisions are available at www.dot.il.gov/aero/airspecs.html. Printed copies of the Illinois Standard Specifications for Construction of Airports may be obtained by applying to the Department of Transportation, Division of Aeronautics, Bureau of Engineering, Design Section, at Capital Airport/One Langhorne Bond Drive, Springfield, Illinois 62707-8415. The order should be accompanied by a check made payable to the Division of Aeronautics in the amount of \$10.00 for each copy ordered.

3. Proposed Work:

Note: The Following Projects are Fully Funded.

2A Morris Municipal Airport

Morris, Illinois

Grundy County

Ill. Proj. C09-3358

AIP No. 3-17-0071-B11

Contract No. MR017

Construct 1,000' Extension with Parallel Taxiway for Runway 18/36 - which includes the following major work items: 7,700 L.F. UG Cable in UD; 30 Each MITL-Stake Mounted; 1 Pair Relocate REILs; 1 L.S. Temporary Threshold; 50,272 C.Y. Unclassified Excavation; 10,815 C.Y. Borrow Excavation; 12,643 L.F. Class E Fence, 8'; 6,497 Ton Bit. Base Course; 14,770 S.Y. Crushed Agg. Base Course; 1,305 Ton Bit. Surface Course; 5,169 Gal. Bit. Prime Coat; 10,857 S.F. Pavement Marking-Waterborne; 104 L.F. 36" RCP, Class III; 4,810 L.F. 6" Perforated Underdrain w/Sock; 20.8 Acre Seeding & Mulching
Pre-Bid meeting: N/A
(DBE 18.0%)

3A DuPage Airport

West Chicago, Illinois

DuPage County

Ill. Proj. DPA-3454

AIP No. 3-17-0017-B19

Contract No. DU074

Rehabilitate Taxiways A & C - which includes the following major work items: 14,485 L.F. UG Cable in UD; 29 Each MITL-Base Mounted; 5 Each Taxi Guidance Sign; 10 Each Inlet Protection; 1,200 L.F. Sand Mix Crack Repair; 24,500 S.Y. Crack Control Fabric; 2,860 Ton Bit. Surface Course; 2,530 Ton Bit. Surface Course-Leveling; 5,800 S.Y. Bit. Pavement Milling; 2,280 S.Y. Butt Joint Construction; 2,900 S.Y. Remove Bit. Pavement; 1,140 S.Y. Rem. & Repl. Bit. Pavement-Type A; 6 Each Remove Tie Down; 7,030 S.F. Pavement Marking-Waterborne; 12,000 S.Y. Soil Guard; 800 C.Y. Shoulder Fill; 120 Each Retrofit Existing MITL or Taxiway Sign; 2.5 Acre Seeding; 8,800 S.Y. Topsoiling

Pre-Bid meeting: N/A

(DBE 6.0%)

4A U of I - Willard Airport

Savoy, Illinois

Champaign County

Ill. Proj. CMI-3589

AIP No. 3-17-0016-xx

Contract No. UN045

Rehabilitate GA/School Apron - which includes the following major work items: 2 Each Apron Light Pole w/Double Fixture; 2 Each Remove Apron Light Pole & Foundation; 125 L.F. 1-Way Concrete Encased Duct; 250 C.Y. Unclassified Excavation; 400 Ton Bit. Base Course; 100 Ton Crushed Agg. Base Course; 300 Ton Bit. Surface Course; 2,400 S.Y. Remove Bit. Pavement; 12 Each Tie Down; 480 L.F. Remove Fence Post Foundation

Pre-Bid meeting: N/A

(DBE 6.0%)

5A St. Louis Regional Airport

East Alton, Illinois

Madison County

Ill. Proj. ALN-3348

Contract No. SR084

Construct Aircraft Parking Apron - which includes the following major work items: 217 C.Y. Unclassified Excavation; 784 C.Y. Offsite Borrow Excavation; 2,512 S.Y. Separation Fabric; 535 L.F. Class E Fence, 8'; 39 Ton Bit. Base Course; 788 Ton Oversize Aggregate; 504 Ton Crushed Agg. Base Course; 28 Ton Bit. Surface Course; 166 S.Y. Remove Bit. Pavement; 2,221 S.Y. 7" PCC Pavement; 248 L.F. 12" RCP, Class IV; 522 S.Y. Aggregate Removal; 2 Each Inlet; 0.7 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 10.0%)

9A Fairfield Municipal Airport

Fairfield, Illinois

Wayne County

Ill. Proj. FWC-3547

AIP No. 3-17-0043-B9

Contract No. FA003

Porous Friction Course on Runway 18/36, Taxiways & Apron - which includes the following major work items: 1,283 S.Y. Shoulder Adjustment; 1,611 S.Y. Remove & Replace Bit. Pavement; 21,485 S.Y. Porous Friction Course, 0.10'; 18 Each Adjust Tie Down; 159 S.Y. PCC Butt Joint; 5,371 Gal. Bit. Tack Coat; 8,423 S.F. Pavement Marking-Waterborne; 366 S.Y. Tar Emulsion Seal Coat; 1,283 S.Y. Excelsior Blanket; 0.3 Acre Seeding

Pre-Bid meeting: N/A

(DBE 0.0%)

10A Albertus Airport

Freeport, Illinois

Stephenson County

Ill. Proj. FEP-3129

AIP No. 3-17-0045-B20

Contract No. FR037

Repair Apron Taxiway, Taxiway & T-Hangar Pavement - which includes the following major work items: 2,220 S.Y. Crack Control Fabric; 270 Ton Bit. Surface Course; 1,170 S.Y. Remove & Replace Bit. Pavement; 330 Gal. Bit. Tack Coat; 1,150 S.F. Pavement Marking-Waterborne; 85 S.Y. Remove & Replace Bit. Pavement (Partial Depth); 545 S.Y. Butt Joint Construction

Pre-Bid meeting: N/A

(DBE 4.0%)

11A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3571

AIP No. 3-17-0068-55

Contract No. QU098

Remove Taxiway C - which includes the following major work items: 2,590 L.F. UG Cable in UD; 1 Each HIRLQ Base Mounted; 18 Each Remove Base Mounted Light; 13 Each Remove Taxi Guidance Sign; 3 Each Relocate Taxi Guidance Sign; 3 Each Refurbish Taxi Guidance Sign; 1 L.S. Traffic Maintenance; 1,000 C.Y. Unclassified Excavation; 685 C.Y. Unclassified Disposal Offsite; 340 C.Y. Offsite Borrow Excavation; 5,325 S.Y. Remove Bit. Pavement; 3 Each Reconstruct Manhole; 165 L.F. Secondary Wire in Saw Kerf; 2.4 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 9.0%)

- 14A Quincy Regional Airport
 Quincy, Illinois
 Adams County
 Ill. Proj. UIN-3618
 AIP No. 3-17-0085-xx
 Contract No. QI056
 Install Wind Cones - which includes the following major work items: 6 Each L-806 Wind Cone-8' Lighted; 5 Each Remove Wind Cone; 13,400 L.F. UG Cable in UD; 1 L.S. Install Electrical Equipment; 1,160 L.F. 4" Directional Bore; 5 Each Splice Can
 Pre-Bid meeting: N/A
 (DBE 0.0%)
- 15A Salem-Leckrone Airport
 Salem, Illinois
 Marion County
 Ill. Proj. SLO-3602
 AIP No. 3-17-0089-B11
 Contract No. SA026
 Rehabilitate T-Hangar Pavements - which includes the following major work items: 150 C.Y. Unclassified Excavation; 514 Ton Bituminous Surface Course; 3,634 S.Y. Bituminous Pavement Milling; 277 S.Y. Remove Bituminous Pavement; 430 Gal. Bituminous Tack Coat; 222 L.F. Trench Drain; 175 L.F. 8" PVC Storm Sewer; 1 Each Inlet, TY "A"; 0.11 Acre Seeding & Mulching
 Pre-Bid meeting: N/A
 (DBE 0.0%)
- 16A Shelby County Airport
 Shelbyville, Illinois
 Shelby County
 Ill. Proj. 2H0-3615
 AIP No. 3-17-0093-B7
 Contract No. SE002
 Rehabilitate Apron; Pavement Repairs on Runway; Install Underdrains on Parallel Taxiway - which includes the following major work items: 1 L.S. Haul Route; 4,571 S.Y. Shoulder Adjustment; 24,000 L.F. Clean & Seal Bit. Cracks; 1,981 Ton Bit. Surface Course; 2,082 S.Y. Butt Joint Construction; 200 S.Y. Remove & Replace Bit. Pavement; 35,716 S.Y. Porous Friction Course, 0.10'; 48 Each Tie Down; 11,931 Gal. Bit. Tack Coat; 11,646 S.F. Pavement Marking-Waterborne; 6,864 L.F. 6" Perforated Underdrain w/Sock; 21 Each Underdrain Inspection Hole; 6,549 S.Y. Strip Seeding; 6,549 S.Y. Excelsior Blanket
 Pre-Bid meeting: N/A
 (DBE 5.0%)

17A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3580

AIP No. 3-17-0068-xx

Contract No. QU097

Construct Security Fence, (Phase III) - which includes the following major work items: 78 Each Clearing Trees; 1 L.S. Unclassified Excavation; 61 S.Y. Riprap-Gradation No. 4; 20,373 L.F. Class E Fence-10'; 8 Each Class E Gate; 8 Each Electric Gate; 20,429 L.F. Remove Class E Fence; 5,890 L.F. Temporary Fence; 562 Ton Agg. Base Course; 1 Each Turnstile Gate; 1 L.S. Relocate ASOS Meter; 1 L.S. Relocate VASI Meter & Electrical Equip.; 1 L.S. Re-Serve Ramp Pad Transformer
Pre-Bid meeting: N/A
(DBE 5.0%)

19A Quincy Regional Airport

Quincy, Illinois

Adams County

Ill. Proj. UIN-3619

AIP No. 3-17-0085-xx

Contract No. QI057

Runway 13/31 RSA Imps - which includes the following major work items: 1,171 L.F. UG Cable in UD; 2 Each MIRL, Stake Mounted; 6 Each MI Threshold Light Stake MTD; 18 Each Remove Stake Mounted Light; 80,974 S.F. Pavement Marking-Waterborne; 13,081 S.F. Pavement Marking-Black Border; 71,481 S.F. Pavement Marking Removal; 10 Each Weed Control Light Ring
Pre-Bid meeting: N/A
(DBE 0.0%)

22A Robinson Municipal Airport

Robinson, Illinois

Crawford County

Ill. Proj. RSV-3490

AIP No. 3-17-0086-B8

Contract No. RB014

Widen Runway 9/27 to 100' - which includes the following major work items: 61 Each Relocate Stake Mounted Light; 2 L.S. Relocate REILs; 2 Each Relocate PLASI; 6,019 C.Y. Unclassified Excavation; 3,342 C.Y. Off-Site Borrow Excavation; 666 Ton By Product Lime; 16,266 S.Y. Soil Processing 16"; 7,497 Ton Bituminous Base Course; 8,011 Ton Crushed Aggregate Base Course; 1,602 Ton Bituminous Surface Course; 6,675 Gal Bituminous Tack Coat; 38,605 S.F. Pavement Marking-Waterborne; 715 C.Y. Porous Backfill; 9,150 L.F. 4" Perforated Underdrain w/Sock; 12 Acre Seeding & Mulching
Pre-Bid meeting: N/A
(DBE 8.0%)

NOTE: The following projects (1A, 6A, 7A, 12A, 13A, 18A, 20A, 21A & 23A) are currently unfunded but are actively seeking federal discretionary funding. The award period for these projects is 75 days and expires on October 18, 2006. At that point, the contractor may request, in writing, an award extension of 86 days, which will expire on January 12, 2007. At this point, the contractor may request a second and final award extension, in writing, of 131 days which will expire on May 23, 2007. There is no guarantee that any or all of these projects will be awarded.

1A Southern Illinois Airport
Carbondale, Illinois
Jackson County
Ill. Proj. MDH-3577
AIP No. 3-17-0009-B26
Contract No. SO077

Construct inner Parallel Taxiway & Parallel connecting Taxiway for Runway 36R - which includes the following major work items: 4,125 L.F. UG Cable in UD; 168 L.F. 1-Way Concrete Encased Duct; 46 Each MITL-Stake Mounted; 9 Each MITL-Base Mounted; 4,724 C.Y. Unclassified Excavation; 3,877 C.Y. Borrow Excavation; 200 Ton By-Product Lime; 10,100 S.Y. Soil Processing 12"; 2,420 Ton Bit. Base Course; 4,240 Ton Crushed Agg. Base Course; 885 Ton Bit. Surface Course; 1,650 S.Y. Remove Bit. Pavement; 3,030 Gal. Bit. Prime Coat; 179 L.F. RCP, Class IV; 2,169 L.F. 4" Perforated Underdrain w/Sock; 3 Each Inlet Box Standard 542546; 5 Acre Seeding & Mulching
Pre-Bid meeting: N/A
(DBE 4.0%)

6A THIS ITEM HAS BEEN WITHDRAWN

7A Palwaukee Municipal Airport
Prospect Heights, Illinois
Cook County
Ill. Proj. PWK-3613
AIP No. 3-17-0018-Bxx
Contract No. PA050

Extend Taxiway L; Construct NE Quad. Sitework (Phase 1) - which includes the following major work items: 7,775 L.F. UG Cable; 6,265 L.F. 2" PVC Duct, Direct Bury; 420 L.F. 2-Way Concrete Encased Duct; 14 Each Electrical Handhole; 61 Each MITL-Base Mounted; 17 Each Taxi Guidance Sign; 34,515 C.Y. Unclassified Excavation; 27,765 S.Y. Soil Stabilization Fabric; 5,440 L.F. Silt Fence; 2,150 Ton Bit. Base Course; 4,810 C.Y. Porous Granular Embankment; 26,975 S.Y. Crushed Agg. Base Course; 2,445 Ton Bit. Surface Course; 3,070 S.Y. Rem. Bit. Pavement; 10,545 S.Y. 10" PCC Pavement; 4,825 Gal. Bit. Prime Coat; 13,365 S.F. Pavement Marking-Waterborne; 2,795 L.F. RCP; 6,350 L.F. 6" Perforated Underdrain w/Sock; 800 L.F. Remove Underdrain; 11 Each Manhole; 1,340 L.F. 12" Ductile Iron Water Main; 70 L.F. 24" Steel Casing; 2 Each 12" x 12" Tapping Valve & Sleeve; 12 Each Type 1 Inlet; 7 Acre Seeding
Pre-Bid meeting: N/A
(DBE 12.0%)

8A Dixon Municipal Airport

Dixon, Illinois

Ogle County

Ill. Proj. C73-3548

AIP No. 3-17-0036-B8

Contract No. DI022

Replace the Electrical Vault - which includes the following major work items: 2,570 L.F. UG Cable in UD; 1 L.S. Construct Electrical Vault; 1 L.S. Install Electrical Equipment; 1 L.S. Remove Electrical Vault; 430 L.F. 4" Directional Bore; 3 Each Electric Handhole; 46 C.Y. Unclassified Excavation; 103 S.Y. 6" Agg. Base Course; 907 S.F. 4" PCC Sidewalk; 1 L.S. Upgrade Airport Rotating Beacon; 153 L.F. Power Cables in Duct; 206 S.Y. Sodding; 16 C.Y. Topsoiling (From On Site)

Pre-Bid meeting: N/A

(DBE 4.0%)

12A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3574

AIP No. 3-17-0068-xx

Contract No. QU099

PFC Overlay on Runway 13/31 - which includes the following major work items: 1 L.S. Traffic Maintenance; 1,050 S.Y. Crack Control Fabric; 5,771 Ton Bit. Surface Course; 82,550 S.Y. Bit. Pavement Milling; 80,720 S.Y. Porous Friction Course, 5/8"; 28,960 Gal. Bit. Tack Coat; 34,800 S.F. Pavement Marking; 1 L.S. Surface Sensor Installation

Pre-Bid meeting: N/A

(DBE 0.0%)

13A Quincy Regional Airport

Quincy, Illinois

Adams County

Ill. Proj. UIN-3338

AIP No. 3-17-0085-xx

Contract No. QI055

Realign Taxiway C - which includes the following major work items:

1 L.S. Haul Route; 3,000 L.F. UG Cable in UD; 25 Each MITL-Stake Mounted; 28 Each Remove Stake Mounted Light; 1,552 C.Y. Unclassified Excavation; 293 Ton By-Product Lime; 6,284 S.Y. Soil Processing-16"; 1,992 Ton Crushed Agg. Base Course; 236 Ton Bit. Surface Course; 3,373 S.Y. Bit. Pavement Removal; 6,029 S.Y. 11" PCC Pavement; 1,623 S.F. Pavement Marking-Waterborne; 2,128 S.Y. Erosion Control Blanket; 240 L.F. RCP, Class IV; 1,885 L.F. 6" Perforated Underdrain w/Sock; 1 Each Inlet; 1,264 L.F. Remove Underdrain; 3.2 Acre Seeding

Pre-Bid meeting: N/A

(DBE 6.0%)

18A Quad-City International Airport

Moline, Illinois

Rock Island County

Ill. Proj. MLI-3564

AIP No. 3-17-0068-xx

Contract No. QU001

Runway 31 Extension - Earthwork - which includes the following major work items: 6 Each L-806 Wind Cone-8' Lighted; 990 L.F. UG Cable in UD; 1 L.S. Traffic Maintenance; 44,165 C.Y. Unclassified Excavation; 3,415 S.Y. Riprap-Gradation No. 3; 2,480 Ton Crushed Agg. Base Course; 3,415 S.Y. Geotextile Fabric; 346 L.F. RCP, Class IV; 243 L.F. RCEP Span 23 Rise 14; 3 Each Inlet-Special; 2 Each Manhole 7'; 2 Each Special Structure; 5 Each Settlement Plates; 25 Acre Seeding; 25 Acre Mulching-Method 3

Pre-Bid meeting: N/A

(DBE 8.5%)

20A Greater Rockford Airport

Rockford, Illinois

Winnebago County

Ill. Proj. RFD-3617

AIP No. 3-17-0088-xx

Contract No. RO013

Reconstruct Taxiway F Northwest - which includes the following major work items: 5,791 L.F. UG Cable in UD; 1,350 L.F. 3" Steel Duct, Direct Bury; 45 Each MITL-Base Mounted; 45 Each Remove Base Mounted Light; 315 C.Y. Unclassified Excavation; 898 S.Y. Soil Stabilization Fabric; 898 S.Y. Crushed Agg. Base Course; 3,983 Ton Bit. Surface Course; 33,250 S.Y. Bit. Pavement Milling; 1,558 S.Y. Butt Joint Construction; 15,933 S.Y. 15" PCC Pavement; 5,462 Gal. Bit. Prime Coat; 14,781 S.F. Pavement Marking-Waterborne; 2,247 S.Y. Soil Guard; 0.5 Acre Seeding

Pre-Bid meeting: N/A

(DBE 7.0%)

21A Aurora Municipal Airport

Aurora, Illinois

Kane County

Ill. Proj. ARR-3468

AIP No. 3-17-0003-B31

Contract No. AU062

Construct Runway 33 Instrument Landing System and Relocate Runway 9 Localizer - which includes the following major work items: 552 L.F. Steel Duct, Jacked; 1 Each Relocate PAPI; 1 L.S. Localizer; 1 L.S. DME; 1 L.S. Glideslope; 4 Each Shelter Building; 1 L.S. MALSR Installation; 1 Each Remove Shelter Building; 1 L.S. Relocate Localizer; 0.50 Acre Clearing & Grubbing; 8,600 C.Y. Unclassified Excavation; 5,300 L.F. Silt Fence; 9,440 S.Y. Separation Fabric; 400 L.F. Class E Fence; 9,440 S.Y. Crushed Aggregate Base Course; 95 Ton Bituminous Surface Course; 38,210 S.F. Pavement Marking-Waterborne; 3,200 S.Y. Remove Gravel; 1 Each Threshold Light Bar; 44 Acre Seeding & Mulching

Pre-Bid meeting: N/A

(DBE 13.0%)

23A Greater Peoria Regional Airport

Peoria, Illinois

Peoria County

Ill. Proj. PIA-3616

AIP No. 3-17-0080-xx

Contract No. PE085

Realign Taxiways A & D, (Phase II) - which includes the following major work items: 19,486 L.F. UG Cable in UD; 1,590 L.F. Concrete Encased Duct; 121 Each MITL-Base Mounted; 15 Each Taxi Guidance Sign; 94 Each Remove Base Mounted Light; 33,109 C.Y. Unclassified Excavation; 563 Ton By-Product Lime; 23,418 S.Y. Soil Processing-12"; 4,880 L.F. Silt Fence; 18,970 Ton Bit. Base Course; 32,471 S.Y. Crushed Agg. Base Course; 5,895 Ton Bit. Surface Course; 5,818 S.Y. Bit. Pavement Milling; 29,372 S.Y. Remove Bit. Pavement; 13,280 S.Y. 18" PCC Pavement; 420 S.Y. PCC Pavement Repairs; 56,100 L.F. Clean & Seal Joints; 56,100 L.F. Route, Clean & Seal Cracks; 21,451 S.F. Pavement Marking; 462 L.F. RCP, Class IV; 4 Each Inlet; 1,672 L.F. Bit. Edge Removal; 29.9 Acre Seeding & Mulching
Pre-Bid meeting: Airport Managers Office on July 28, 2006 at 1:00pm
(DBE 8.0%)