

# IMPORTANT NOTICE: TRANSPORTATION BULLETIN REVISIONS

**Letting Date: September 23, 2005**

The following revisions have been made to this Transportation Bulletin. If you downloaded the bulletin prior to the noted revision date, you should incorporate the revisions or download and use a new copy of the bulletin.

---

Revision date **September 13, 2005**

Revision No. 1: [Item No. 5](#) reads (Job No. C-98-080-55) (0-00856-8015). The description has been changed to read (Job No. C-98-080-05) (0-00856-8015).

Revision No. 2: [Item No. 6](#) reads (Job No. C-98-086-05) (0-00865-8021). The description has been changed to read (Job No. C-98-086-05) (0-00856-8021).

Revision No. 3: [Item No. 25](#) has been WITHDRAWN from the Letting.

Revision No. 4: [Item No. 37](#) reads (Job No. C-60-006-06) (0-00526-0000). The description has been changed to read (Job No. C-60-006-06) (0-00526-3001).

Revision No. 5: [Item No. 38](#) reads (Job No. C-60-007-06) (0-00526-0000). The description has been changed to read (Job No. C-60-007-06) (0-00526-4001).

Revision No. 6: [Item No. 40](#) has had the Small Business Set-Aside status removed.

Revision No. 7: [Item No. 41](#) has had the Small Business Set-Aside status removed.

Revision No. 8: [Item No. 60](#) reads (Job No. C-91-272-05) (1-70000-0500). The description has been changed to read (Job No. C-91-272-05) (1-77485-0400).

Revision No. 9: [Item No. 69](#) has had these pay items removed from the description; 7,069 ft polyethylene conduit; 105 ft pvc conduit; 10 ft conduit in trench; 115 ft trench and backfill; remove and salvage 72 lighting units; remove 72 lighting unit foundations.

Revision No. 10: [Item No. 70](#) has had these pay items removed from the description; 7,884 ft polyethylene conduit; remove and salvage existing lighting unit.

Revision No. 11: [Item No. 73](#) reads 88 locks for gates. The description has been changed to read 176 locks for gates.

Revision No. 12: [Item No. 73](#) reads (Job No. C-91-357-04) (1-77278-0100). The description has been changed to read (Homeland Security Funds).

Revision No. 13: [Item No. 74](#) the description has been changed to remove; including earthwork to reestablish wetland ponds, de activate field tiles and drainage ditches.

Revision No. 14: [Item No. 74](#) the quantity of 30 units tree intermediate and shrub watering has been changed to read 90 units tree intermediate and shrub watering.

Revision No. 15: [Item No. 74](#) reads (Completion Date: October 15, 2008). The description has been changed to read (Completion Date: June 30, 2009).

Revision No. 16: [Item No. 75](#) reads (20.00% DBE). The description has been changed to read (14.00% DBE).

Revision No. 17: [Item No. 75](#) has no completion date. The description has been changed to read (Completion Date August 15, 2006 Plus 10 Working Days).

## Letting Item Descriptions

Paving

Bridge

Electrical

Miscellaneous

Division of Aeronautics

**PAVEMENT SECTION**

1. Contract No. 74085 White County District 7  
Section D-7 ROADWAY REPAIRS  
FAP Route 877 (IL 141)  
Roadway repair consisting of 45 ft of milling and bituminous concrete surface on IL Route 141 located at County Road 800 East, west of New Haven; includes 130 sq yds milling; 11 tons bituminous concrete surface course, SUPERPAVE, MIX C; 78 ft paint pavement marking; mobilization; traffic control and protection. (15 Working Days)  
(Job No. C-97-032-05) (MCHD) (SUPERPAVE) (0.00% DBE)
2. Contract No. 76300 St. Clair County District 8  
Section 27-1R  
FAP Route 103 (IL 13/15) Project ACF-103(63)  
3.54 miles of pavement widening and reconstruction on IL Route 13/15 from Green Mount Road to Rogers Drive also includes drainage improvements, all located in Freeburg; includes 182,203 cu yds earth excavation; 307 cu yds removal and disposal of unsuitable material; 307 cu yds porous granular embankment; 55 acres seeding; 9,825 sq yds sodding; 2,136 sq yds stone dumped riprap; 142,772 sq yds processing modified soils; 2,751 tons lime; 34,690 tons subbase granular material; 1,026 tons aggregate base course; 2,974 sq yds aggregate base course; 6,556 sq yds preparation of base; 3,027 tons aggregate surface course; 234 sq ft concrete sidewalk; 39,062 sq yds milling; 14,538 sq yds pavement removal; 1,549 sq yds patching; 401 sq yds aggregate shoulders; 63,728 sq yds bituminous shoulders, SUPERPAVE; removal of 3 existing structures; 3,600 sq ft temporary sheet piling; 2,876 ft precast concrete box culverts; 5,734 ft pipe culverts; 61,741 ft pipe underdrains; 3,209 ft concrete curb and gutter; 512.5 ft steel plate beam guardrail; 4 traffic barrier terminals; 1,298 sq ft sign panel; 710 ft detector loop; 43 shade trees; 628 intermediate trees; 11,192 tons material transfer device; 2,659 sq yds bituminous concrete base course widening, SUPERPAVE; 81,723 sq yds bituminous concrete pavement, full-depth, SUPERPAVE; 25,611 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 264 ft wide crack routing; 504 lbs wide crack filling; mobilization; traffic control and protection; Federally funded. (270 Working Days) (Job No. C-98-089-03) (8-88970-0100) (SUPERPAVE) (12.00% DBE)
3. Contract No. 76815 St. Clair County District 8  
Section 82-6K-1  
FAI Route 64 (I-64) Project NHI-64-1(118)13  
0.40 mile of variable width widening, bituminous concrete surface, traffic signals, striping and minor structure repairs all located at the I-64/West Highway Interchange at O'Fallon; includes 4,688 sq yds bituminous concrete binder course, SUPERPAVE, IL-19.0; 881 cu yds earth excavation; 3,349 cu yds furnished excavation; 4.2 acres seeding; 6,329 sq yds processing modified soils; 122 tons lime; 402 sq yds concrete base course; 1,500 sq yds milling; 320 sq yds pavement removal; 500 sq yds patching; 411 tons aggregate shoulders; 856 tons bituminous shoulders, SUPERPAVE; 185 cu yds concrete removal; 84 cu yds concrete; 23,450 lbs epoxy coated reinforcement bars; 2,460 ft pipe underdrains; 1,988 ft concrete curb and gutter; 3,350 sq ft concrete median surface; 430.5 sq ft sign panel; 22,344 ft thermoplastic pavement marking; 5,000 ft locating underground cable; 1,730 ft conduit in trench; 4,504 ft trench and backfill; 2,826 ft unit duct; 14,443 ft electric cable; 7 aluminum traffic signal posts; 5,341 ft detector loop; 12 signal heads; 4,045 tons polymerized bituminous concrete binder and surface course, SUPERPAVE, Mix E; 725 sq yds bridge deck hydro-scarification; 725 sq yds bridge deck microsilica concrete overlay; mobilization; traffic control and protection; Federally funded. (115 Working Days) (Job No. C-98-081-04) (8-00117-0000) (SUPERPAVE) (17.00% DBE)
4. Contract No. 76918 St. Clair County District 8  
Section A-1(1RS)-3  
FAU Route 9162 (LEBANON ROAD)  
0.33 mile of 20 ft width milling, bituminous concrete surface and patching on Lebanon Road at IL Route 157 connection to IL Route 161 located at the west limits of Belleville; includes 48 cu yds earth excavation; 107 tons aggregate base course; 4,341 sq yds milling; 358 ft gutter removal; 253 sq yds patching; 10.6 cu yds concrete; 250 ft concrete gutter; 343 tons bituminous concrete surface course, SUPERPAVE, Mix C; 6,824 ft paint pavement marking; mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-079-05) (0-00856-8014) (SUPERPAVE) (20.00% DBE)
5. Contract No. 76919 St. Clair-Monroe Counties District 8  
Section DIST. 8 RESURFACING 2006-3  
FAI Route 255 (I-255)  
Resurfacing of bridge approaches to remove pavement bumps at four locations along I-255 in St. Clair and Monroe counties; includes 300 sq yds milling; 784 sq yds concrete surface removal; 135 tons polymerized bituminous concrete surface course, SUPERPAVE, Mix E; 1,080 ft preformed plastic pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-080-05) (0-00856-8015) (SUPERPAVE) (0.00% DBE)

6. Contract No. 76925 Madison County District 8  
Section 37-1RS-4  
FAU Route 9393 (MAIN STREET)  
0.7 mile of 24 ft to 27 ft width milling and bituminous concrete surface on Main Street from IL Route 162 to U.S. Route 40 in Troy; includes 102 sq yds patching; 580 tons polymerized bituminous concrete surface course, SUPERPAVE, MIX D; 9,899 ft paint pavement marking; 10,365 sq yds milling; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-086-05) (0-00856-8021) (SUPERPAVE) (10.00% DBE)
7. This Item has been deleted from the Letting
8. Contract No. 76974 Washington County District 8  
Section 9-31  
FAP Route 42 (IL 127/MILL STREET)  
0.24 mile of partial pavement removal and replacement with granular subbase and bituminous concrete pavement (full-depth) on IL Route 127 (Mill Street) from Adams Street to Chester Street in Nashville; includes 432 cu yds earth excavation; 453 tons subbase granular material; 1,945 sq yds pavement removal; 40 sq yds patching; 7 inlets to be adjusted; 1,945 sq yds bituminous concrete pavement (full-depth), SUPERPAVE; mobilization; traffic control and protection. (15 Working Days) (Job No. C-98-145-05) (0-00856-8022) (SUPERPAVE) (10.00% DBE)
9. Contract No. 83667 Cook County District 1  
Section 05-F3000-01-BT (COOK COUNTY – FP)  
SA Route LT CREEK GREENWAY TRAIL Project CMM-8003(498)  
15.85 km bituminous bike trail construction including culverts, signs, traffic signals, retaining walls and landscaping between the Busse Woods Forest Preserve and 47<sup>th</sup> Street through the Village of Lyons; includes 4,258 trees removed; 6,972 cu m furnished excavation; 31,666 sq m topsoil furnish and place; 3.4 ha seeding; 15,844 sq m aggregate base course; 42,839 liter bituminous materials; 27,895 sq m pavement removal; 71 m combination concrete curb and gutter removal and replacement; 32 precast reinforced concrete flared end sections; 104 m pipe culverts; 14,696 m pavement marking; 432 m electric cable in conduit; 37 trees; 5,120 m tons bituminous concrete surface course, SUPERPAVE; 20 signal heads; 193 sq m segmental concrete block wall; 289 m rustic rail fence; 107.6 m aluminum sign post; 1 information kiosk; traffic control and protection; Federally funded. (65 Working Days) (Job No. C-91-174-05) (1-11002-0000) (SUPERPAVE) (14.00% DBE)
10. Contract No. 83803 Will County District 1  
Section 99-00030-00-PV (FRANKFORT)  
FAU Route 3751 (PFEIFFER ROAD) Project M-7003(799)  
0.49 mile pavement replacement with bituminous base, binder and surface courses, earth excavation, curb and gutter, driveways, sidewalks, drainage, pavement markings, traffic signals and landscaping on Pfeiffer Road from U.S. Route 30 to 750' south of Charrington Drive and on U.S. Route 30 from west of Pfeiffer Road east 0.21 mile all in Frankfort; includes 5,784 cu yds removal and disposal of unsuitable material; 4,530 cu yds earth excavation; 14,997 sq yds topsoil furnish and place and sodding; 16,483 sq yds subbase granular material; 12,986 sq ft PCC sidewalk; 7,494 sq yds pavement removal; 4,887 ft storm sewers; 883 ft storm sewer removal; 2,694 ft pipe underdrain; 4,985 ft combination curb and gutter; 16,864 ft thermoplastic pavement marking; 1,390 ft conduit in trench; 8,720 ft electric cable in conduit; 57 trees; 8,045 tons bituminous concrete SUPERPAVE; 12 signal heads; 1,443 sq yds aggregate base course; 3,492 sq yds surface removal; traffic control and protection; Federally funded. (140 Working Days) (Job No. C-91-417-99) (1-10698-0000) (SUPERPAVE) (25.00% DBE)
11. Contract No. 83809 Cook County District 1  
Section 02-00086-00-RS (PARK FOREST)  
FAU Route 2830 (MONEE ROAD) Project M-8003(525)  
0.36 mile surface removal, patching, bituminous surface course, channelization, and incidental work to complete the improvement on Monee Road between Western Avenue and the Will County Line in Park Forest; includes 1,269 sq yds topsoil furnish and place; 1,269 sq yds sodding; 418 sq yds bituminous surface removal; 596 gals bituminous materials; 12 tons aggregate prime coat; 60 ft combination concrete curb and gutter removal and replacement; 953 sq yds Class D patches; 5,960 sq yds area reflective crack control treatment; 200 tons aggregate shoulder; 7,634 ft thermoplastic pavement marking; 336 ft detector loop replacement; 6 manholes to be adjusted; 257 tons leveling binder, SUPERPAVE; 685 tons bituminous concrete surface course, SUPERPAVE; 45 lbs fertilizer nutrient; 5 units supplemental watering; mobilization; traffic control and protection; Federally funded. (15 Working Days) (Job No. C-91-286-05) (1-20041-0000) (SUPERPAVE) (10.00% DBE)

12. Contract No. 83811 Cook County District 1  
Section 03-P4045-01-BT (LAN-OAK PARK DISTRICT)  
PENNSY GREENWAY BIKE PATH Project CMM-8003(325)  
2.75 miles Pennsy Greenway Bike Path on abandoned railroad corridor consisting of earth excavation, aggregate base, bituminous surface and chain link fence to become part of the Grand Illinois Trail connecting to Burnham Greenway Trail at the north and Thorn Creek Trail at the south in Lansing between the state line and the Little Calumet River; includes 3 acres tree removal; 11,320 cu yds earth excavation; 49,000 sq yds topsoil furnish and place; 10.1 acres seeding; 2,730 lbs fertilizer nutrient; 16,162 sq yds aggregate base course; 8,075 gals bituminous materials; 800 sq ft sidewalk; 160 ft combination concrete curb and gutter; 110 sq ft concrete median surface; 120 sq ft sign panel; 670 ft pavement marking; 1 electric utility service connection; 2,400 ft conduit in trench; 3,044 ft electric cable in conduit, signal; 620 evergreens; 12 post mounted flashing beacons; 1,860 tons bituminous concrete surface, SUPERPAVE; 3 acres selective clearing; traffic control and protection; Federally funded. (40 Working Days)  
(Job No. C-91-207-03) (1-11002-0000) (SUPERPAVE) (25.00% DBE)
13. Contract No. 83814 DuPage County District 1  
Section 04-00029-00-PV (BURR RIDGE)  
FAU Route 1552 (83<sup>RD</sup> STREET) Project M-8003(505)  
1.46 miles pavement reconstruction with resurfacing, drainage, curb and gutter on 83<sup>rd</sup> Street from the South Frontage Road to County Line Road in Burr Ridge; includes 383 units tree removal; 1,574 cu yds earth excavation; 4,500 sq yds topsoil furnish and place; 4,500 sq yds sodding; 671 tons aggregate base; 376 sq yds PCC driveway pavement; 25,703 sq yds bituminous surface removal; 2,001 ft combination curb and gutter removal; 220 ft storm sewers; 2,490 ft combination concrete curb and gutter; 3,325 ft pavement marking; 18 trees; 632 sq yds bituminous base course, SUPERPAVE; 800 sq yds Class D patches; 1,894 tons bituminous concrete surface, SUPERPAVE; 3,474 tons bituminous concrete binder, SUPERPAVE; 4,988 ft pavement contraction joint; 1 trainee; 27 ft detector loop; traffic control and protection; Federally funded. (45 Working Days)  
(Job No. C-91-188-05) (1-20043-0000) (SUPERPAVE) (15.00% DBE)
14. Contract No. 87310 Kankakee County District 3  
Section 05-00055-00-RS (MANTENO)  
FAU Route 6512 (MAPLE STREET) Project M-5034(15)  
Construction consists of 0.39 miles of bituminous concrete resurfacing of FAU Route 6512, Maple Street from Park to Eighth Street in the Village of Manteno; includes 124 tons incidental bituminous surfacing; 7,439 sq yds bituminous surface removal; 10,096 sq yds area reflective crack control treatment; 5 manholes to be adjusted; 1,012 ft thermoplastic pavement marking-line 6"; 772 tons bituminous concrete surface course; 707 tons leveling binder; mobilization; traffic control and protection; Federally Funded. (15 Working Days) (Job No. C-93-049-05) (3-10064-0000) (6.00% DBE)
15. Contract No. 99233 Williamson County District 9  
Section 05-00097-00-RS  
FAS Route 1901 (SPILLWAY ROAD) Project RS-1901(103)  
Construction consists of 7.83 miles bituminous resurfacing with aggregate shoulders on FAS Route 1901, Spillway Road from the intersection with Illinois Route 13 extending southerly 7.83 miles; includes 11,320 tons bituminous concrete surface course; 2,780 tons aggregate shoulders; 153,562 ft paint pavement marking-line 4"; 545 raised reflective pavement markers; mobilization; Federally funded. (30 Working Days)  
(Job No. C-99-521-05) (9-10060-0000) (4.00% DBE)
16. Contract No. 99234 Franklin County District 9  
Section 05-00051-00-RP (WEST FRANKFORT)  
FAU Route 9477 (CLEVELAND STREET) Project M-5071(11)  
Construction consists of 0.243 miles PCC pavement, curb and gutter, storm sewer and sidewalk on FAU Route 9477, Cleveland Street from Lincoln Street to west of Park entrance in the city of West Frankfort; includes 253 tree removal; 3,150 cu yds earth excavation; 282.1 cu yds trench backfill; 2,910 sq yds erosion control blanket; 1,200 tons subbase granular material; 300 tons aggregate surface course; 235.7 sq yds PCC driveway pavement; 1,124 sq ft PCC sidewalk; 5 cu yds concrete structures; 1,468 ft storm sewers; 920 ft water main 6"; 12 cal mos engineer's field office; 4,875 sq yds PCC pavement 7"; 920 ft detection wire; 600 ft water service line ¾"; 28 inlets, special; 66.75 sq ft sign panel; Federally funded. (70 Working Days) (Job No. C-99-540-05) (9-10055-0000) (10.00% DBE)  
[SEE MORE PAVEMENT](#)

**BRIDGE SECTION**

17. Contract No. 62580 Cook County District 1  
Section 2003-028I  
FAI Route 94 (NB) (I-94/90 (DAN RYAN))  
2.0 miles of repairs to the elevated bridge that carries FAI 94/90 (Dan Ryan Expressway) northbound from 15<sup>th</sup> Street to 28<sup>th</sup> Street consisting of bridge deck scarification, concrete overlay, deck repairs, bearing and joint repairs, structural steel repairs and substructure repairs, located in Chicago; includes 1,158 cu yds concrete removal; 1,289 cu yds concrete; 97,841 sq yds bridge deck grooving; 355 sq ft formed concrete repair; erecting 272,450 lbs structural steel; 15,488 lbs structural steel repair; 180,010 lbs epoxy coated reinforcement bars; 179,778 ft epoxy pavement marking; 1,150 ft conduit in trench; 500 ft trench and backfill; 4,020 ft electric cable; 7,029 sq ft high performance-enhanced shotcrete; 1,965 ft bridge joint system (expansion); 584 ft bridge joint system (fixed); 7.5 cal mos maintenance of existing lighting system complete; 7.5 cal mos maintenance of existing traffic surveillance; 1,578 sq yds temporary pavement; 364 ft bridge drainage system repairs; 98,764 sq yds bridge deck microsilica concrete overlay; 98,764 sq yds bridge deck hydro-scarification; 35,556 sq yds cleaning bridge seats; 140 sq yds deck slab repair; 39,910 sq yds protective shield; 3 temporary shoring and cribbing; 98,764 sq yds bridge deck thermography; column repair; 31 microloop sensor under bridge deck; 31 microloop vehicle detectors; mobilization; traffic control and protection.  
(Completion Date: October 31, 2006 Plus 05 Working Days) (Job No. C-91-082-03) (1-76073-0300) (8.00% DBE)  
[MANDATORY PRE-BID CONFERENCE](#)
18. Contract No. 62875 Cook County District 1  
Section 3333-212VB-I  
FAI Route 290 (I-290)  
Bridge beam replacement on the structure carrying Circle Avenue over I-290, CSX Transportation, Inc. Railroad, and CTA located in Forest Park; includes 1,600 lbs structural steel repair; beam straightening; mobilization; traffic control and protection. (15 Working Days) (Job No. C-91-059-05) (MCHD) (0.00% DBE)
19. Contract No. 62901 Will County District 1  
Section (12&13)T-1  
FAP Route 353 (US 30)  
Removal of the existing bridge and construction of a triple 7' x 4' box culvert carrying U.S. Route 30 over a stream located 0.3 mile west of Wolf Road in Mokena; includes 1,170 cu yds earth excavation; 2,424 cu yds removal and disposal of unsuitable material; 1,183 cu yds furnished excavation; 2,615 cu yds porous granular backfill; 4,432 sq yds topsoil; 828 sq yds compost; 1.0 acre seeding; 487 sq yds pavement removal; 12.9 tons aggregate shoulders; 9,055 lbs reinforcement bars; 55.9 cu yds concrete box culverts; 410.4 ft precast concrete box culvert 7' x 4'; 6,575 ft thermoplastic pavement marking; 70 sq yds bituminous concrete base course widening, SUPERPAVE; 740 tons bituminous concrete binder and surface course, SUPERPAVE, MIX D; 1,045 sq yds milling; 2,264 sq yds temporary pavement, SUPERPAVE; 899 sq yds aggregate subgrade; 70 sq ft wire faced mechanically stabilized earth wall; mobilization; traffic control and protection. (55 Working Days) (Job No. C-91-101-05) (1-76638-0100) (SUPERPAVE) (10.00% DBE)
20. Contract No. 66578 Marshall County District 3  
Section (62-2VB)I  
FAI Route 412 (I-39 (SB))  
This project consists of the removal and replacement of the north approach pavement, shoulder removal and replacement, abutment back wall and expansion joint removal and replacement and other related items to complete the work at the structure (Structure Number 062-0051) carrying southbound Interstate 39 over the Burlington Northern Santa Fe Railroad approximately 1.0 mile south of Illinois Route 17 near Wenona; includes 19 cu yds earth excavation; 137 sq yds bridge approach pavement; 479 sq yds bridge approach pavement connector; 272 sq yds approach slab removal; 89 sq yds continuously reinforced concrete pavement removal; 252 sq yds portland cement concrete shoulder removal; 10 tons aggregate shoulders; 16 cu yds structure excavation; 44 ft preformed joint seal; 12 cu yds concrete structure; 1,436 lbs reinforcement bars, epoxy coated; 620 sq ft workzone pavement marking removal; 2,128 ft epoxy pavement marking line; 309 sq yds stabilized subbase, SUPERPAVE; 51 bar splicers; 2 impact attenuators; mobilization; traffic control and protection. (45 Working Days) (Job No. C-93-084-05) (0-00856-3008) (SUPERPAVE PROJECT) (4.00% DBE)

21. Contract No. 66579 Marshall County District 3  
Section (62-2VB)I-1  
FAI Route 412 (I-39 (NB))  
This project consists of the removal and replacement of the south approach pavement, structure backwall, shoulders, and expansion joint at Structure Number 062-0052 carrying northbound Interstate 39 over the Burlington Northern Santa Fe Railroad approximately 1.0 mile south of Illinois Route 17; includes 19 cu yds earth excavation; 16 cu yds porous granular embankment; 30 tons subbase granular material; 96 cu yds subbase granular material (special); 597 sq yds protective coat; 136 sq yds bridge approach pavement; 504 sq yds bridge approach pavement connector; 274 sq yds approach slab removal; 103 sq yds continuously reinforced concrete pavement removal; 263 sq yds concrete shoulder removal; 16 cu yds structure excavation; 44 ft preformed joint seal; 12 cu yds concrete structures; 12 sq yds protective coat; 1,436 lbs reinforcement bars epoxy coated; 46 ft pipe drains; 620 sq ft pavement marking removal; 2,128 ft epoxy pavement marking line; 3 raised reflective pavement marker; 309 sq yds stabilized subbase, SUPERPAVE; 51 bar splicers; 1 impact attenuator; mobilization; traffic control and protection. (45 Working Days)  
(Job No. C-93-085-05) (0-00856-3009) (SUPERPAVE PROJECT) (4.00% DBE)
22. Contract No. 68437 Warren County District 4  
Section D4 BRIDGE REPAIR 2006  
FAP Route 404 (US 34)  
This project consists of replacing existing preformed joint seals with strip seals on structure Nos. 094-0025 and 094-0026 and repairing the backwall of the westbound Structure No. 094-0025 located on U.S. Route 34 approximately 4.5 miles east of Monmouth; includes 55 cu yds concrete removal; 55 cu yds concrete superstructure; 12 sq ft formed concrete repair; 10,280 lbs reinforcement bars, epoxy coated; 1,562 ft pavement marking tape; 780 ft temporary concrete barrier; 202 ft strip seal expansion joint assembly; 80 bar splicers; 4 impact attenuators; mobilization; traffic control and protection. (25 Working Days) (Job No. C-94-021-05) (0-00856-4005) (5.00% DBE)
23. Contract No. 74098 Marion County District 7  
Section 26JI  
FAP Route 322 (US 51) Project NHF-322(76)  
Guardrail placement, channel cleaning, riprap and other work along U.S. Route 51 located north and south of Patoka and on the structures over Deer Creek and Louse Creek; includes 305 cu yds channel excavation; 87 sq yds stone riprap; 87 sq yds filter fabric; 1,862.5 ft steel plate beam guardrail; 8 traffic barrier terminals; 28 guardrail markers; mobilization; traffic control and protection; Federally funded. (15 Working Days) (Job No. C-97-061-05) (7-80850-0800) (0.00% DBE)
24. Contract No. 76908 Clinton County District 8  
Section 1-1BR-1I  
FAP Route 42 (IL 127)  
Bituminous overlay and patching of the existing structure carrying IL Route 127 over the Kaskaskia River located 2.5 miles southeast of Carlyle; includes 3,786 sq yds waterproofing membrane system; 3,887 ft paint pavement marking; 37 cu ft polymer concrete; 324 ft silicone joint sealer; 55 sq yds deck slab repair (full-depth); 916 sq yds deck slab repair (partial); 335 tons bituminous concrete surface course, SUPERPAVE, Mix D, N 70; mobilization; traffic control and protection. (50 Working Days) (Job No. C-98-069-05) (0-00856-8004) (SUPERPAVE) (0.00% DBE)
25. THIS ITEM HAS BEEN WITHDRAWN FROM THE LETTING
26. Contract No. 91335 Shelby County District 5  
Section 03-01123-00-BR  
TR 205 Project BROS-173(129)  
Construction consists of a single span, 1 @ 78' - 0" precast prestressed concrete deck beam bridge carrying TR 205 over Flat Branch 0.5 miles east of Sexson; includes 1,516 cu yds furnished excavation; 0.9 acre seeding; 1,075 ft perimeter erosion barrier; 208 tons stone riprap; 783 tons aggregate surface course; 1 removal of existing structures; 27.2 cu yds concrete structures; 1,872 sq ft precast prestressed concrete deck beams; 3,140 lbs reinforcement bars; 280 ft driving steel piles; 70 ft pipe culverts; 168 ft storm sewers; 4 terminal markers; Federally funded. (35 Working Days)  
(Job No. C-95-314-05) (5-10093-0000) (8.00% DBE)



27. Contract No. 93399 Brown County District 6  
Section 02-00063-00-BR  
FAS Route 585 (CH 11) Project BHS-585(104)  
Construction consists of a single span bridge deck replacement on FAS Route 585, CH 11 over Camp Creek, 2 miles north of Versailles; includes 60 tons porous granular backfill; 0.2 acre seeding; 50 tons riprap, special; 65 tons aggregate base course; 1 removal of existing concrete deck; 30.9 cu yds concrete SUPERSTRUCTURE; 580 lbs furnishing and erecting structural steel; 540 stud shear connectors; cleaning and painting steel bridge; 7,945 lbs reinforcement bars, epoxy coated; 250 ft steel plate beam guardrail; 7 traffic barrier terminals; mobilization; Federally funded. (25 Working Days) (Job No. C-96-231-04) (6-10168-0000) (10.00% DBE)
28. Contract No. 95437 Jefferson County District 7  
Section 98-11120-00-BR  
TR 227 (GREEN ROAD) Project BROS-81(43)  
Construction consists of 3 bridges, main bridge, overflow bridge and a field road bridge with reconstruction of the approach roadways and removal of existing 3 span timber bridge on TR 227, Green Road, 1.5 miles north of Mt. Vernon; includes 2,324 cu yds channel excavation; 72,155 cu yds furnished excavation; 3.9 acre seeding; 4,940 ft perimeter erosion barrier; 820 tons stone dumped riprap; 2,054 tons aggregate base course; 1 removal of existing structure; 301 cu yds concrete structures; 9,122 sq ft precast prestressed concrete deck beams; 41,950 lbs reinforcement bars; 3,539 ft driving steel piles; 920 sq ft temporary sheet piling; 1,612 ft steel plate beam guardrail; 14 traffic barrier terminals; railroad protective liability insurance; setting precast concrete bridge slabs; mobilization; Federally funded. (130 Working Days) (Job No. C-97-015-05) (7-10218-0000) (8.00% DBE)
29. Contract No. 98935 Pulaski County District 9  
Section D-9 CONT. MAINT. FY06-4  
FAP Route 726 (IL 37)  
Milling and reinforced concrete overlay on the structure carrying IL Route 37 over Kitchel Slough located 1 mile south of the Johnson County Line; includes 343 sq yds protective coat; 252 sq yds bituminous concrete removal (deck); 251 sq yds bridge deck grooving; 3,310 lbs epoxy coated reinforcement bars; 262 ft paint pavement marking; 252 sq yds concrete wearing surface; 252 sq yds bridge deck hydro-scarification; mobilization; traffic control and protection. (30 Working Days) (Job No. C-99-033-05) (0-00856-9013) (0.00% DBE)
30. Contract No. 99232 Gallatin County District 9  
Section 00-00065-00-BR  
FAS Route 888 (CH 11) Project BRS-888(119)  
Construction consists of a seven span, 5 @ 60' – 1" and 2 @ 59' – 11 1/2" precast prestressed concrete deck beam bridge carrying FAS Route 888, CH 11 over the Middle Fork of Cypress Creek 3 miles north of Shawneetown; includes 680 cu yds channel excavation; 2.2 acre seeding; 1,000 ft perimeter erosion barrier; 880 tons riprap; 200 tons aggregate shoulders; 1 removal of existing structures; 83 cu yds concrete structures; 12,600 sq ft precast prestressed concrete deck beams; 11,185 lbs reinforcement bars, epoxy coated; 7,240 ft driving steel piles; 67.2 cu yds concrete encasement; 1,400 sq yds waterproofing membrane system; 350 ft steel plate beam guardrail; 8 traffic barrier terminals; 2,075 ft paint pavement marking-line 5"; 290 tons bituminous concrete surface course; 155 tons aggregate base course widening; Federally funded. (Completion Date: July 01, 2006) (Job No. C-99-075-00) (9-00500-0000) (8.00% DBE)
31. Contract No. 72A01 Cass County District 6  
Section (144BR-2)I-3,(144BR-3)I-2  
FAP Route 614 (IL 78)  
Installation of debris deflection systems on structures carrying IL Route 78 over Sangamon River and over Panther Creek located near Chandlerville; includes 1 debris deflection system, complete; 203 ft furnishing metal pile shells; 203 ft driving and filling shells; mobilization; traffic control and protection. (15 Working Days)  
(Job No. C-96-001-06) (0-00856-6008) (0.00% DBE)  
[SEE MORE BRIDGE](#)

#### **ELECTRICAL SECTION**

32. Contract No. 62906 Lake County District 1  
Section 2005-002TS  
FAP Route 334 (US 12 (RAND ROAD)) Project CMF-334(15)  
Fiber optic communication network along U.S. Route 12 (Rand Road) from Soyton Road/Eagle Point Road to Grand Avenue in Fox Lake; includes 834 ft conduit in trench; 428 ft conduit pushed; 834 ft trench and backfill; 1 controller; 3,090 ft electric cable; 1,770 ft fiber optic cable; 8 pedestrian signal heads; maintenance of 2 existing traffic signal installations; 8 pedestrian push-buttons; mobilization; traffic control and protection; Federally funded. (40 Working Days)  
(Job No. C-91-110-05) (1-77408-0000) (0.00% DBE)

33. Contract No. 62907 Kane County District 1  
Section 2005-003TS  
FAU Route 3902 (IL 31) Project CMM-3902(1)  
Fiber optic communication network along IL Route 31 from IL Route 56 (State St.) to Lovedale Lane in North Aurora; includes 670 ft thermoplastic pavement marking; 692 ft conduit in trench; 862 ft conduit pushed; 222 ft conduit attached to structure; 4,240 ft trench and backfill; 4 maintenance of existing traffic signal installations; 5 controllers; 9,705 ft electric cable; 2 steel mast arm assemblies and poles; 26 signal heads; 4,785 ft fiberoptic cable; mobilization; traffic control and protection; Federally funded. (50 Working Days) (Job No. C-91-111-05) (1-77409-0000) (0.00% DBE)
34. Contract No. 62947 Cook County District 1  
Section 2005-020I  
FAI Route 94/90 (NB) (I-94/90 (DAN RYAN)) Project IM-94-3(399)55  
Procurement of dynamic message signs and uninterruptible power supply upgrade for I-94/90 (Northbound) – Dan Ryan Expressway from 31<sup>st</sup> Street to the I-57 interchange in Chicago; includes uninterruptible power supply; 2 dynamic message sign cabinets, material only; 13 uninterruptible power system cabinets, material only; 2 dynamic message sign cabinets, equipment, material only; 13 uninterruptible power system cabinets, equipment, material only; 13 LED dynamic message sign full matrix configuration, material only; Federally funded. (Completion Date: August 01, 2007) (Job No. C-91-192-05) (1-74823-0519) (0.00% DBE)
35. Contract No. 83808 Kane County District 1  
Section 03-00320-00-TL  
FAP Route 360 (KIRK ROAD) Project CMF-360(9)  
This project consists of the interconnection of nine traffic signals and modernization as required, along Kirk Road from Pine Street to IL Route 64 in Kane County; includes 25,686 ft conduit in trench; 7 full actuated controller and cabinets; 37,836 ft electric cable in conduit; 31,692 ft fiber optic cable in conduit; 4 ft concrete foundation; 66 ft detector loop; 37 inductive loop detectors; re-optimize traffic signal system; 6 remote controlled video systems; 6 weeks of changeable message signs; 46 handholes; traffic control and protection; Federally funded. (95 Working Days) (Job No. C-91-113-04) (1-11002-0000) (3.00% DBE)

36. **Small Business Set-Aside**  
Contract No. 76935 Madison County District 8  
Section 57-TS-1  
FAP Route 586 (IL 162)  
Modernize traffic signals at the intersections of IL Route 162 with Maryville Road and 23<sup>rd</sup> Street in Granite City; includes 10 cu yds furnished excavation; 490 sq ft median surface removal and replacement; 10 cu yds non-special waste disposal; 102 ft locating underground cable; 82 ft conduit in trench; 75 ft trench and backfill; 650 ft electric cable; 1,040 ft detector loop; mobilization; traffic control and protection. (25 Working Days) (Job No. C-98-097-05) (8-89365-0000) (10.00% DBE)  
[SEE MORE ELECTRICAL](#)

#### **MISCELLANEOUS SECTION**

37. Contract No. 44892 Grundy County District 3  
Section D3 REFLECTOR REPL 2006-5  
FAI Route 80 (I-80)  
This project consists of installing new raised reflective pavement markers, removing damaged pavement markers, and replacing reflectors on Interstate 80 from 7 miles west of Morris to 3 miles east of Morris; includes 100 raised reflective pavement marker; 2,865 replacement reflector; 100 raised reflective pavement marker removal; mobilization. (Completion Date: June 30, 2006) (Job No. C-60-006-06) (0-00526-3001) (0.00% DBE)
38. Contract No. 44893 Various Counties District 4  
Section D4 RAISED REFL PAV MKR 2006-6  
Various Routes (VARIOUS)  
This project consists of installing new raised reflective pavement markers on various highways throughout District Four; includes 1,473 raised reflective pavement markers; 3,407 replacement reflectors; 1,473 raised reflective pavement markers removed; mobilization. (Completion Date: November 30, 2006) (Job No. C-60-007-06) (0-00526-4001) (0.00% DBE)
39. Contract No. 62830 Various Counties District 1  
Section 2004-090I  
Various Routes (VARIOUS)  
Roadway sweeping on various expressway and arterial routes throughout the district; includes 300 miles supplemental sweeping; 1,763 miles inner city sweeping (special); 6 full expressway cleaning cycles; 1 initial arterial cleaning cycle; 2 full arterial cleaning cycles; 1 initial expressway cleaning cycles; 1 sign cleaning cycle; 5 inner city expressway cleaning cycles. (Completion Date: December 31, 2006) (Job No. C-91-349-04) (Formal Contract) (13.00% DBE)

40. Contract No. 62884 Will County District 1  
Section 2004-118GRR  
FAI Route 55 (INTERSTATE 55) Project HS-55-6(216)54  
Guardrail installation along 1.59 miles of I-55 from Caton Farm Road to north of Black Road at Joliet; includes 16 pipe underdrain outlet extensions; 437 cu yds earth excavation; 2,332 cu yds removal and disposal of unsuitable material; 1,897 cu yds furnished excavation; 12,590 sq yds topsoil; 2.6 acres seeding; 5,830 sq yds aggregate shoulders; 55 sq yds bituminous shoulders, SUPERPAVE; 32 concrete collars; 8,235 ft steel plate beam guardrail; 4 traffic barrier terminals; mobilization; traffic control and protection. (30 Working Days)  
(Job No. C-91-074-05) (1-70000-0200) (SUPERPAVE) (0.00% DBE)
41. Contract No. 62885 Will County District 1  
Section 2004-119GRR  
FAI Route 55 (INTERSTATE 55) Project HS-55-6(215)058  
Guardrail installation along I-55 from south IL Route 126 to Renwick Road in Romeoville; includes 844 cu yds earth excavation; 3,407 cu yds removal and disposal of unsuitable material; 1,717 cu yds furnished excavation; 12,947 sq yds topsoil; 2.7 acres seeding; 12,947 sq yds erosion control blanket; 8,514 sq yds aggregate shoulders; 55 sq yds bituminous shoulders, SUPERPAVE; 36 concrete collars; 12,217 ft steel plate beam guardrail; 2 traffic barrier terminals; mobilization; traffic control and protection; Federally funded. (40 Working Days)  
(Job No. C-91-075-05) (1-70000-0100) (SUPERPAVE) (0.00% DBE)
42. **Small Business Set-Aside.**  
Contract No. 62934 Cook County District 1  
Section (1516.1,1717&1818)I-5  
FAI Route 94 (I-94 (DAN RYAN))  
Construction of 4 landscaped medians including irrigation and planting along I-94 (Dan Ryan Expressway) from the I-57 interchange to 71<sup>st</sup> Street in Chicago; includes 230 sq yds subbase granular material; 91 sq yds concrete base course; 331 sq ft concrete sidewalk; 125 ft water service line; 971 sq ft concrete median surface (corrugated); 90 ft thermoplastic pavement marking; 4 backflow preventors; 779 sq yds irrigation system; 677 shrubs; 12 shade trees; 391 units perennial plants; 602 ft concrete median wall; 970 sq ft concrete median surface; 779 sq yds planting mix furnish and place; 40 sq ft castinplace warning surface system for ramps; 994 sq yds median and pavement removal; 30 sq yds pavement removal and replacement; 10 tons bituminous concrete surface course, SUPERPAVE, MIX D; 20 ft concrete curb and gutter; mobilization; traffic control and protection. (Completion Date: May 31, 2007 Plus 15 Working Days)  
(Job No. C-91-170-05) (1-74823-1503) (SUPERPAVE) (35.00% DBE)
43. **Small Business Set-Aside.**  
Contract No. 62939 Lake County District 1  
Section 2005-016PCC-PP  
FAP Route 344 (US 45 (S. LAKE ST.))  
Pavement patching, drainage structure adjustments and curb and gutter removal and replacement along U.S. Route 45 (South Lake Street) just north of IL Route 60 in Mundelein; includes 100 ft curb and gutter removal and replacement; 1,085 sq yds patching; 5,174 ft saw cuts; 2 frames and grates to be adjusted; 465 ft polyurea pavement marking; 66 ft detector loop replacement; mobilization; traffic control and protection. (15 Working Days)  
(Job No. C-91-178-05) (0-00856-1000) (10.00% DBE)
44. Contract No. 66577 LaSalle County District 3  
Section 50(1HB-2,1HB)BP  
FAI Route 412 (I-39)  
This project consists of cleaning and painting the existing structural steel on (2) bridges. Bridge No. 1 (Structure Number 050-0214) is located approximately 1.0 mile north of Illinois Route 18 and carries Township Road 525 over Interstate 39. Bridge No. 2 (Structure Number 050-0215) carries Illinois Route 18 over Interstate 39. This project is located near Lottant; includes cleaning and painting steel bridge No. 1; cleaning and painting steel bridge No. 2; blasting residue containment and disposal bridge No. 1; blasting residue containment and disposal bridge No. 2; bridge cleaning and painting warranty No. 1; bridge cleaning and painting warranty No. 2; mobilization; traffic control and protection.  
(45 Working Days) (Job No. C-93-083-05) (0-00856-3007) (0.00% DBE)
45. Contract No. 66603 Livingston-Grundy Counties District 3  
Section (53-1,32-3)I-3  
FAI Route 55 (I-55)  
6.0 miles of pavement patching on Interstate 55 from approximately 3 miles south of Illinois Route 17 to approximately 3 miles north of Illinois Route 17 near Dwight, also included in this project is the removal and replacement of wide flange beam terminal joints; includes 4 wide flange beam terminal joints, complete; 1,353 sq yds patches; 1,353 sq yds patching reinforcement; 6,156 ft saw cuts; 55 calendar days traffic control surveillance; 2,375 ft epoxy pavement marking line; 4 wide flange beam joint removals; 226 tie bars; mobilization; traffic control and protection.  
(Completion Date: December 15, 2005) (Job No. C-93-110-05) (0-00856-3021) (4.00% DBE)

46. Contract No. 66605 Grundy County District 3  
Section (32-1)J  
FAI Route 55 (I-55 (NB))  
This project consists of placing 5.4 miles of high tension cable system along the edge of the shoulder in the northbound lane of Interstate 55; includes 672 tons aggregate shoulders; 26,545 ft high tension cable median barrier system; mobilization; traffic control and protection. (45 Working Days) (Job No. C-93-112-05) (3-05532-0010) (0.00% DBE)
47. Contract No. 66670 Kendall County District 3  
Section (13C)DM  
FAP Route 326 (IL 47)  
This project consists of removing a single-family residence at Spring Street and a single-family residence with a detached garage on Somanauk Street along IL Route 47 in Yorkville; includes 10,800 sq yds topsoil furnish and place; building removal no. 1; building removal no. 2; removal and disposal of friable asbestos, building no. 1; removal and disposal of non-friable asbestos, building no. 1 and 2. (15 Working Days) (Job No. C-93-065-05) (3-31666-0002) (0.00% DBE)
48. Contract No. 70477 Vermilion County District 5  
Section 92(11,12,12-1)RS-1,I  
FAI Route 74 (I-74 (EB)) Project HS-74-6(146)216  
0.076 mile of milling and paving the shoulder to install a high tension cabled barrier system on the Interstate 74 Eastbound Exit Ramp at Bowman Avenue in Danville; includes 5 cu yds earth excavation; 20 cu yds furnished excavation; 425 ft perimeter erosion barrier; 197 sq yds bituminous shoulder removal; 15 tons aggregate shoulders; 197 sq yds bituminous shoulders SUPERPAVE; 4 delineators removed; 400 ft preformed plastic pavement marking tape; 371 ft high tension cable median barrier system; mobilization. (15 Working Days)  
(Job No. C-95-024-05) (5-91986-0402) (SUPERPAVE) (0.00% DBE)
49. Contract No. 74094 Effingham County District 7  
Section D-7 PAVT. PATCHING 2006-1  
FAI Route 57 (I-57)  
Pavement patching along 4 miles of I-57 from the Shelby/Effingham County Line to north of Effingham; includes 388 sq yds patching; 388 sq yds patching reinforcement; 1,900 ft saw cuts; 59 tie bars; mobilization; traffic control and protection. (20 Working Days) (Job No. C-97-059-05) (0-00856-7001) (0.00% DBE)
50. Contract No. 74126 Jefferson County District 7  
Section (41-4-1,41-4)J  
FAI Route 57 (I-57) Project HS-57-3(155)102  
High tension cable barrier system along I-57 at three locations at the Dix Interchange; includes 9,020 ft high tension cable median barrier system; mobilization; traffic control and protection; Federally funded. (25 Working Days)  
(Job No. C-97-096-05) (7-83350-0000) (0.00% DBE)
51. **Small Business Set-Aside.**  
Contract No. 76915 Madison County District 8  
Section DISTRICT 8 PATCHING 2006-1  
FAU Route 9080 & FAU Route 8983 (MARYVILLE ROAD & BROADWAY)  
Partial depth pavement patching along Maryville Road from Illinois Route 203 to west of Chain of Rocks Road and Broadway from Illinois Route 3 to Allen Street in Alton; includes 53 tons partial depth patching; 470 sq yds partial depth removal; 0.15 ton bituminous materials prime coat; mobilization; traffic control and protection. (15 Working Days)  
(Job No. C-98-076-05) (0-00856-8011) (0.00% DBE)
52. Contract No. 76933 Madison-St. Clair Counties District 8  
Section DIST 8 DEEP WELLS 2006-1  
Various Routes (VARIOUS)  
Well treatment at various locations in East St. Louis and Venice; includes 4 wells chemical treatments; 1 well chemical treatment, special; 10 additional treatments; mobilization; traffic control and protection. (45 Working Days)  
(Job No. C-98-095-05) (Formal Contracts) (0.00% DBE)
53. Contract No. 76940 Madison County District 8  
Section 60-(1,2)I-2  
FAI Route 55 (I-55)  
High tension cable median barrier system along I-55 from 1.6 miles north of I-70 to 2.2 miles north of IL Route 143; includes 18,365 ft high tension cable median barrier system; 0.38 acre seeding; 5,747 sq yds bituminous shoulders, SUPERPAVE; mobilization; traffic control and protection. (30 Working Days)  
(Job No. C-98-104-05) (8-00030-0100) (SUPERPAVE) (0.00% DBE)

54. Contract No. 83797 DuPage County District 1  
Section 04-00094-01-SG (DOWNERS GROVE)  
FAP Route 311 (OGDEN AVENUE) Project CMF-311(28)  
Project consists of sign modernization at various locations along Ogden Avenue between Walnut Avenue and Park Street in the Village of Downers Grove; includes 57 sign panels and posts removed Type 1; 115 sq ft remove sign panel; 722 sq ft sign panel and appurtenances Type 1 and Type 2; 57 fluted sign supports; 57 18" diameter drilled shaft concrete foundations; mobilization; traffic control and protection; Federally funded. (35 Working Days)  
(Job No. C-91-196-05) (1-11002-0000) (5.00% DBE)
55. Contract No. 83810 Cook County District 1  
Section 05-00192-00-SW (DES PLAINES)  
Various Routes Project CMM-8003(487)  
Construction consists of 1.7 miles of sidewalk along FAU Route 2686, Mt. Prospect Road, FAU Route 3514, Algonquin Road and FAU Route 1290, Oakton Street in the City of Des Plaines; includes 14 trees pruning; 1,134 cu yds earth excavation; 3,690 sq yds topsoil furnish and place 4"; 3,690 sq yds sodding, salt tolerant; 41,405 sq ft PCC sidewalk 5"; 1,420 lbs reinforcement bars, epoxy coated; 840 ft paint pavement marking-line 4"; 6 sanitary manholes to be adjusted; 5 calendar days railroad flagger; construction layout; railroad protective liability insurance; mobilization; Federally funded. (45 Working Days) (Job No. C-91-139-05) (1-11002-0000) (2.00% DBE)
56. Contract No. 83812 Cook County District 1  
Section 02-00077-00-SW (PALATINE)  
FAU Route 3512/FAP 364 (NORTHWEST HWY./EUCLID AVE.) Project CMF-000S(469)  
0.28 mile PCC sidewalk along Northwest Highway between IL Route 53 and Williams Avenue and 0.49 mile bituminous bike path along Euclid Avenue between Roselle and Quentin Roads all in Palatine; includes 20 trees pruning; 118 cu yds earth excavation; 414 cu yds removal and disposal of unsuitable material; 1,822 sq yds topsoil furnish and place; 90 lbs fertilizer nutrient; 1,822 sq yds sodding, salt tolerant; 3,700 sq yds aggregate base course; 1,330 sq yds protective coat; 7,456 sq ft PCC sidewalk; 422 sq ft detectable warnings; 400 sq ft sidewalk removal; adjust 7 manholes; 39 sq ft sign panel; 1,394 ft pavement marking; 815 ft wood fence; 18 ft bike path bollards; 322 tons bituminous concrete surface, SUPERPAVE; 1,396 sq ft modular block wall; 5 units supplemental watering; traffic control and protection; Federally funded. (35 Working Days) (Job No. C-91-108-03) (1-11002-0000) (SUPERPAVE) (10.00% DBE)
57. **Small Business Set-Aside**  
Contract No. 98917 Various Counties District 9  
Section D-9 CONT. MAINT. FY06-5  
Various Routes (VARIOUS)  
Guardrail repair and replacement at various locations in the district; includes 963 ft steel plate beam guardrail; 4 traffic barrier terminals; 25 guardrail markers; 300 ft timber curb; mobilization; traffic control and protection. (20 Working Days)  
(Job No. C-99-025-05) (0-00856-9017) (0.00% DBE)
58. Contract No. 98922 Jackson-Johnson Counties District 9  
Section D-9 CONT. MAINT. FY06-2  
Various Routes (VARIOUS)  
Concrete pavement patching in three locations in Jackson and Johnson counties; includes 1,903 sq yds patching; 2,384 dowel bars; 2,384 tie bars; 11,382 ft saw cuts; mobilization; traffic control and protection. (15 Working Days)  
(Job No. C-99-038-05) (0-00856-9009, 0-00856-9010, 0-00856-9003) (0.00% DBE)
59. Contract No. 98923 Various Counties District 9  
Section D-9 CONT. MAINT. FY06-1  
Various Routes (VARIOUS)  
Repair of existing concrete pavement consisting of removal and replacement of concrete pavement repairing concrete by replacing with PCC inlay at various locations; includes 108 sq yds concrete inlay; 160 sq ft corrugated median removal; 485 sq yds subbase granular material; 445 sq yds concrete pavement; 535 sq yds pavement removal; 835 ft saw cuts; 243 tons aggregate shoulders; 815 sq yds bituminous shoulders, SUPERPAVE; 25 ft concrete curb and gutter; 513 ft polyurea pavement marking; mobilization; traffic control and protection. (25 Working Days)  
(Job No. C-99-036-05) (0-00856-9005, 9008) (SUPERPAVE) (0.00% DBE)
60. Contract No. 60A11 Will County District 1  
Section 2005-040GRR  
FAI Route 55 (I-55) Project HS-55-6(217)248  
High tension cable median barrier system along I-55 from U.S. Route 6 to south of I-80 located in Channahon; includes 9,135 ft high tension cable median barrier system; mobilization; traffic control and protection; Federally funded. (35 Working Days) (Job No. C-91-272-05) (1-77485-0400) (0.00% DBE)



61. Contract No. 64B50 Henry County District 2  
Section D2 DRAINAGE 2006-1  
FAI Route 74 (I-74)  
This project consists of desilting and video inspection storm sewers at the Interstate 74 Eastbound Krisdala Baka Rest Area approximately 3.5 miles north of Illinois Route 17; includes 249 ft video inspection of storm sewer; 3 desilting drainage structures; 249 ft desilting storm sewer; mobilization. (15 Working Days)  
(Job No. C-92-123-05) (0-00856-2009) (0.00% DBE)  
[SEE MORE MISCELLANEOUS](#)

**RE-ADVERTISED SECTION**

Items 62 through 75 are being re-advertised for bids. Contractors and suppliers who requested plans and proposals for these items in connection with the previous advertisement should request the complete set to ensure that revised and/or added material is issued. A charge of \$35 will be made for each CD ROM Letting Set. (Letting Set = All plans, proposals and addendums pertaining to a specific letting)

**PAVEMENT SECTION**

- |     |  |
|-----|--|
| 62. | <b>Small Business Set-Aside</b><br>Contract No. 60754 Cook County District 1<br>Section 1316RS-1<br>FAU Route 2760 (SHERMER ROAD)<br>0.50 mile of 20 ft width milling and bituminous concrete surface on Shermer Road from Willow Road to Old Willow Road in Glenview; includes 30 units grading and shaping shoulders; 1,668 sq yds patching; 2,300 ft curb and gutter removal and replacement; 9,222 sq yds milling; 246 ft detector loop replacement; 1,171 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 7,047 ft thermoplastic pavement marking; mobilization; traffic control and protection. (20 Working Days) (Job No. C-91-245-99) (1-73385-0000) (SUPERPAVE) (10.00% DBE)<br><br><b>PREVIOUS LETTING: August 5, 2005 (Item 64)</b> |
|-----|--|

63. Contract No. 62941 Cook County District 1  
Section 3035-Z-Y-1-RS-1  
FAP Route 341 (TOUHY AVENUE)  
0.18 mile of 2 @ 24 ft and variable width milling and bituminous concrete surface on Touhy Avenue at U.S. Route 12/45 (Mannheim Road) in Des Plaines; includes 6,285 sq yds milling; 200 ft concrete curb and gutter removal and replacement; 180 sq yds patching; 186 ft detector loop replacement; 3,040 ft thermoplastic pavement marking; 880 tons bituminous concrete binder and surface course, SUPERPAVE, Mix F; mobilization; traffic control and protection. (20 Working Days) (Job No. C-91-180-05) (0-00856-1002) (SUPERPAVE) (14.00% DBE)  
  
**PREVIOUS LETTING: August 5, 2005 (Item 4)**

64. Contract No. 72118 Mason County District 6  
Section SAND RIDGE STATE FOREST 2004  
PARK ROADS (SAND RIDGE&JAKE WOLF MF RD)  
4.28 miles of reconstruction of internal park roads and parking areas at Sand Ridge State Forest located northeast of Havana; includes 14.53 acres tree removal; 16,016 cu yds earth excavation; 12,324 tons subbase granular material; 21.8 acres seeding; 815 tons cover coat aggregate; 408 tons seal coat aggregate; 174 tons bituminous materials (cover and seal coats); 287 sq ft sidewalk removal; 216 tons aggregate shoulders; 100 sq yds patching; 840 ft pipe culverts; 91 ft concrete curb and gutter; 96.5 sq ft sign panel; 2,162 ft thermoplastic pavement marking; 18 bumper blocks; 2,628 tons bituminous concrete binder and surface course, SUPERPAVE, Mix C; 3,571 sq yds furnish and install pond liner; drilling and installing water well; 41 sq yd bituminous base course, SUPERPAVE; mobilization; traffic control and protection. (Completion Date: June 01, 2006) (Job No. C-96-554-04) (0-00196-6001) (SUPERPAVE) (9.00% DBE)  
  
**PREVIOUS LETTING: August 5, 2005 (Item 73)**

65. Contract No. 72A08 Sangamon County District 6  
Section 84-4(B-1)I  
FAI Route 55 (I-55)  
0.15 km of 18 m width bituminous concrete surface on I-55 for dip correction at the south approach of the southbound lanes at the Lake Springfield Bridge in Springfield; includes 428.4 m tons polymerized bituminous concrete binder and surface course, SUPERPAVE, MIX D; 385 m preformed plastic pavement marking; mobilization; traffic control and protection. (15 Working Days) (Job No. C-96-513-06) (6-76511-0001) (SUPERPAVE) (6.00% DBE)  
  
**PREVIOUS LETTING: August 5, 2005 (Item 39)**

**BRIDGE SECTION**

66. Contract No. 62900 Will County District 1  
Section 2004-1301  
FAP Route 330 (US 45)  
Removal and replacement of precast, prestressed concrete deck beams on the existing structures carrying U.S. Route 45 over the North Branch of Prairie Creek and over Prairie Creek located in Green Garden Township; includes 20.8 sq yds bituminous concrete surface removal; 13.6 cu yds concrete removal; 13.6 cu yds concrete; 1,804 sq ft precast, prestressed concrete deck beams; 2,170 lbs epoxy coated reinforcement bars; 216.3 sq yds waterproofing membrane system; 732 ft concrete mortar fairing course; 2 temporary traffic signal installation; 29.2 tons bituminous concrete surface course, SUPERPAVE, MIX D; mobilization; traffic control and protection. (55 Working Days)  
(Job No. C-91-100-05) (0-01045-1002) (SUPERPAVE) (25.00% DBE)

PREVIOUS LETTING: August 5, 2005 (Item 82)

67. Contract No. 62944 Cook County District 1  
Section 2005-0191  
Various Routes (VARIOUS)  
Installing permanent protective shielding on nine structures in Skokie, Morton Grove, Stickney, Tinley Park and Chicago; includes 8,538 sq yds protective shield (permanent); mobilization; traffic control and protection.  
(40 Working Days) (Job No. C-91-183-05) (0-00856-1005) (0.00% DBE)

PREVIOUS LETTING: August 5, 2005 (Item 40)

68. Contract No. 83790 Lake County District 1  
Section 02-00025-00-BR (LAKE BLUFF)  
FAU Route 2758 (MOFFETT ROAD) Project BRM-8003(182)  
The work includes the removal of an existing bridge and construction of a new bridge with concrete bridge approach slabs, storm sewer replacement, sanitary sewer replacement, bituminous pavement resurfacing curb and gutter removal and replacement and all other work necessary to complete the project on Moffett Road from Sylvan Road to Ravine Avenue in the Village of Lake Bluff; includes 115 trees removed; 712 cu yds earth excavation; 21 lbs fertilizer nutrients; 952 sq yds stone riprap; 4 tons aggregate, special; 0.2 ton bituminous materials (prime coat); 20 sq yds PCC driveway; 107 sq ft PCC sidewalk; 187 sq yds pavement removal; 176 ft combination curb and gutter removal; 195.1 cu yds concrete superstructure; 75,830 lbs reinforcement bars; 6 manholes; 166 ft combination concrete curb and gutter; 760 ft epoxy pavement marking; 206 ft sanitary sewer; 38 tons bituminous concrete surface course, SUPERPAVE; 48 tons bituminous concrete binder course, SUPERPAVE; 4,000 sq ft coating system for concrete; Federally funded. (Completion Date: May 15, 2006 Plus 10 Working Days) (Job No. C-91-079-02) (1-10615-0000) (SUPERPAVE) (10.00% DBE)

PREVIOUS LETTING: June 17, 2005 (Item 119)

[SEE MORE BRIDGE](#)

**ELECTRICAL SECTION**

69. **Small Business Set-Aside**  
Contract No. 62806 Cook County District 1  
Section 2004-067L  
FAI Route 90/94 (DAN RYAN EXPRESSWAY)  
1.50 miles of lighting improvements along I-90/94 (Dan Ryan Expressway) from 59<sup>th</sup> Street to 47<sup>th</sup> Street (Frontage Roads) in Chicago; includes 365 ft concrete foundation; 11 electric handholes; mobilization; traffic control and protection.  
(Completion Date: November 14, 2005) (Job No. C-91-291-04) (1-74823-1206) (SUPERPAVE) (0.00% DBE)

PREVIOUS LETTING: April 29, 2005 (Item 34)

**Small Business Set-Aside**

70. Contract No. 62807 Cook County District 1  
Section 2004-068L  
FAI Route 90/94 (DAN RYAN EXPRESSWAY)  
Removal of the existing lighting system and installation of conduit, handholes and light pole foundation along Interstate 90/94 (Dan Ryan Expressway) on South Wentworth Avenue from 59<sup>th</sup> Street to 47<sup>th</sup> Street (Frontage Roads) in Chicago; includes 1 calendar month changeable message sign; 102.8 sq ft temporary information signing; 72 ground rods; 619 ft concrete foundation; 6 electric handholes; mobilization; traffic control and protection. (Completion Date: November 17, 2005) (Job No. C-91-292-04) (1-74823-1207) (0.00% DBE)

**PREVIOUS LETTING: April 29, 2005 (Item 35)**

71. Contract No. 62877 Cook County District 1  
Section 0305-302K-L-3  
FAI Route 290/FAP Route 342 (I-290/IL 53)  
Lighting, CCTV and fiber optic communications network along I-290/IL Route 53 from south of IL Route 62 (Algonquin Road) to north of IL Route 72 (Higgins Road) in Schaumburg and Rolling Meadows; includes 52 lighting towers; 1,520 ft light tower foundation; 271 luminaires; 46,285 ft unit duct; 3,240 ft conduit pushed; 2 lighting controllers; 16 buck booster transformer; 29,500 ft fiber optic cable; 14 CCTV cabinets; 6 CCTV cabinet equipment; 6 CCTV dome cameras (material only); CCTV distribution subsystem; 9,125 ft electric cable; 3,290 ft conduit attached to structure; 16 handholes; 36,000 ft fiber optic innerduct; 29,800 ft trench and backfill; 22 aluminum light poles; mobilization; traffic control and protection. (Completion Date: May 31, 2006) (Job No. C-91-061-05) (1-75649-0700) (0.00% DBE)

**PREVIOUS LETTING: June 17, 2005 (Item 227)**

72. Contract No. 72963 Sangamon County District 6  
Section (17X)TS-1  
FAP Route 663 (DIRKSEN PARKWAY)  
Installation of new traffic signals at the intersection of Dirksen Parkway and Wide Track Drive in Springfield; includes 5 cu yds non-special waste disposal; 55 sq ft sign panel; 92 ft thermoplastic pavement marking; 646 ft conduit in trench; 283 ft conduit augered; 646 ft trench and backfill; 4 luminaires; 1 controller; 665 ft fiber optic cable; 3,683 ft electric cable; 4 steel combination mast arm assemblies and poles; 16 signal heads; mobilization; traffic control and protection. (35 Working Days) (Job No. C-96-516-05) (6-76510-0005) (0.00% DBE)

**PREVIOUS LETTING: August 5, 2005 (Item 100)**

**MISCELLANEOUS SECTION**

73. Contract No. 62833 Cook-DuPage Counties District 1  
Section 2004-089I  
Various Routes (VARIOUS)  
Installation of chain link fence along various expressways in the district; includes 7,286 ft chain link fence; 56 chain link gates; 176 locks for gates; 52 signs; mobilization; traffic control and protection. (40 Working Days) (Homeland Security Funds) (0.00% DBE)

**PREVIOUS LETTING: September 17, 2004 (Item 49)**

74. Contract No. 72967 Brown County District 6  
Section D6 WETLAND MITIGATION NO. 2  
Various Routes (LAGRANGE WETLAND BANK)  
Wetland mitigation located at the LaGrange Wetland Bank in the northeast corner of Brown County; includes 40.7 acres interseeding; 40.7 acres mowing; 2,199 shade trees; tree care; 90 units tree intermediate and shrub watering; 2,932 tree trunk predator protection; 20 gals weed control, non-selective and non-residual; 244.4 acres maintenance mowing; mobilization. (Completion Date: June 30, 2009) (Job No. C-96-508-06) (6-00333-0000) (30.00% DBE)

**PREVIOUS LETTING: August 5, 2005 (Item 110)**



**BRIDGE SECTION**

75. Contract No. 62853 Cook County District 1  
Section 2004-108BR  
FAP Route 305 (PALATINE ROAD)

Bridge rehabilitation for the structures carrying the east and west frontage roads over Palatine Road, Wisconsin Central Ltd. Railroad over Palatine Road and Wolf Road over Palatine Road all located in Prospect Heights and Wheeling; includes 179 cu yds removal and disposal of unsuitable material; 806 sq yds topsoil; 806 sq yds sodding; 253 sq ft concrete sidewalk; 1,405 sq yds milling; 732 sq yds pavement removal; 873 sq yds bituminous concrete surface removal complete; 19.7 cu yds concrete removal; 164 ft preformed joint seal; 86.9 cu yds concrete; 868 sq yds bridge deck grooving; 903 sq yds concrete wearing surface; 680 sq ft formed concrete repair; 1,210 sq ft precast, prestressed concrete deck beams; 5,465 lbs structural steel; 100 lbs structural steel repair; 20,110 lbs epoxy coated reinforcement bars; 66 ft steel bridge rail; 1,000 ft epoxy crack sealing; 341 ft concrete curb and gutter; 3,559 sq ft concrete median; 8,912 ft thermoplastic pavement marking; 14 ft conduit in trench; 14 ft trench and backfill; 7,294 ft electric cable; 132 ft detector loop; 5,281 ft remove electric cable from conduit; 1,210 sq ft removal of existing precast, prestressed deck beams; 732 sq yds temporary pavement; 298 tons bituminous concrete binder and surface course, SUPERPAVE, Mix D; 84 bearing pad adjustments; 87 ft keyway repair; 27 sq ft bridge sidewalk repair; mobilization; traffic control and protection. (Completion Date: August 15, 2006 Plus 10 Working Days )  
(Job No. C-91-026-05) (1-74819-0300, 1-74821-0300) (14.00% DBE)

PREVIOUS LETTING: April 29, 2005 (Item 101)

**REVIEW AND INSPECTION**

Items 1X and 2X are **NOT** included in the September 23, 2005 Letting but are expected to be included in an undetermined, future letting. They are being published to allow for review and inspection by potential bidders and suppliers. They are **NOT** for bidding purposes at this time.

- 1X. Contract No. 62300 Cook County District 1  
Section (1818,ETC,2324.6-1P)R-8  
FAI Route 94/90 (NB) (I-94/90 (DAN RYAN EXPR.)) Project IM-94-3(397)55  
5.12 miles of roadway reconstruction of FAI Route 94/90 (Dan Ryan Expressway) northbound from 31st Street to 71st Street including repairs to 3 existing structures, overhead sign structures, storm sewers and pavement markings located in Chicago; includes 217,181 cu yds earth excavation; 37,065 cu yds trench backfill; 219,063 sq yds geotechnical fabric for ground stabilization; 5,347 sq yds topsoil; 1 acre seeding; 225,099 sq yds subbase granular material; 456 sq yds bridge approach pavement; 148,867 sq yds continuously reinforced concrete pavement; 151,914 sq yds pavement removal; 135 sq yds patching; 1,321 cu yds concrete; 212 sq yds bridge deck grooving; 1,263 sq ft formed concrete repair; 80,795 lbs epoxy coated reinforcement bars; 28,250 ft storm sewers; 50,398 ft pipe underdrains; 2 traffic barrier terminals; 4,294 sq ft sign panel; 1,890 lbs structural steel sign support; 546 ft overhead sign structure; 154,967 ft epoxy pavement marking; 305 ft trench and backfill; 6,621 cu yds braced excavation; 53,565 sq ft temporary soil retention system; 52,802 sq yds concrete shoulders; 1,199 ft concrete curb and gutter; 148,867 sq yds pavement reinforcement; 1,191 ft video taping of sewers; 237 sq yds concrete slab hydro-demolition; 21,248 ft CTA fence; 804 cu yds non-special waste disposal; 1,123 cu yds structure excavation; 12,190 ft soldier piles; 35,885 cu yds drilling and setting soldier piles in soil; 14,027 sq ft untreated timber lagging; drainage system; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2006 Plus 5 Working Days) (Job No. C-91-417-01) (1-74823-0502) (20.00% DBE)  
[MANDATORY PRE-BID CONFERENCE](#)
- 2X. Contract No. 62302 Cook County District 1  
Section (1818,ETC,2324.6-1P)R-9  
FAI Route 94/90 (SB) (I-94/90 (DAN RYAN EXPR.)) Project ACIM-94-3(398)55  
5.25 miles of reconstruction of FAI Route 94/90 (Dan Ryan Expressway) southbound from 31st Street to 71st Street, including repairs to 2 existing structures, overhead sign structures, storm sewers and pavement markings located in Chicago; includes 215,989 cu yds earth excavation; 33,825 cu yds trench backfill; 680 cu yds sand backfill; 215,074 sq yds geotechnical fabric for ground stabilization; 5,627 sq yds topsoil; 1 acre seeding; 224,179 sq yds subbase granular material; 146,651 sq yds continuously reinforced concrete pavement; 161,041 sq yds pavement removal; 135 sq yds patching; 3,909 cu yds structure excavation; 2,078 cu yds concrete; 212 sq yds bridge deck grooving; 695 sq ft formed concrete repair; 16,237 sq ft untreated timber lagging; 196,985 lbs epoxy coated reinforcement bars; 53,984 ft pipe underdrains; 2 traffic barrier terminals; 3,245 sq ft sign panel; 3,150 lbs structural steel sign support; 487 ft overhead sign structure; 297 ft overhead sign structure walkway; 159,320 ft epoxy pavement marking; 919 ft trench and backfill; 700 ft aerial cable; 32,127 ft storm sewers; 5,499 cu yds braced excavation; 53,371 sq ft temporary soil retention system; 54,685 cu ft drilling and setting soldier piles in soil; 57,423 sq yds concrete shoulders; 16,650 ft soldier piles; 215,074 sq yds stabilized subbase; 146,650 sq yds pavement reinforcement; 713 ft video taping of sewers; 505 ft steel casing; drainage system; 237 sq yds concrete slab hydro-demolition; 22,921 ft CTA fence; mobilization; traffic control and protection; Federally funded. (Completion Date: October 31, 2006 Plus 5 Working Days) (Job No. C-91-419-01) (1-74823-0501) (20.00% DBE)  
[MANDATORY PRE-BID CONFERENCE](#)

STATE OF ILLINOIS  
Department of Transportation  
Division of Aeronautics

---

This Bulletin constitutes official notification to Contractors of the intention to receive bids for Airport related work. The Transportation Bulletin is available on the Department's Internet website at <http://www.dot.il.gov>. The following phone numbers and e-mail address are available if assistance is needed:  
Phone: 217/782-7806; Fax: 217/785-1141; TDD: 217/524-4875;  
E-mail: duncanjr@dot.il.gov.

INVITATION FOR BIDS

1. TIME AND PLACE OF OPENING PROPOSALS: Sealed bids, subject to the conditions contained herein, will be received by the Department of Transportation at the Auditorium in the Harry R. Hanley Building, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois, until 10:00 A.M. prevailing time, September 23, 2005. These bids will, at that time, be publicly opened and read for furnishing all labor and materials, and performing all work for the Project(s) listed and defined in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics.
2. INSTRUCTIONS TO BIDDERS:
  - a. Plans and Contract Documents. Plans and Contract Documents for those Project(s) specified in Paragraph 3.0 of this Service Bulletin for the Division of Aeronautics may be examined and reviewed at the following offices:
    - (1) Department of Transportation, Division of Aeronautics, One Langhorne Bond Drive, Capital Airport, Springfield, Illinois.
    - (2) Department of Transportation, Harry R. Hanley Building, Plans and Contracts Office, Room 323, 2300 South Everett McKinley Dirksen Parkway, Springfield, Illinois.
    - (3) Office of the consulting engineer(s).
  - b. Contract documents for bidding will not be loaned to prospective bidders. They may be purchased on CD-ROM at the above address of the Chief Contract Official. A form for purchases is included in the Transportation Bulletin, and is entitled "Request for Authorization to Bid/or Not For Bid Status" (BDE 124 INT). A charge of \$35 will be made for each Letting set (Letting set = all plans & proposals pertaining to a specific Letting). Payment shall be made by check, bank draft or money order payable to the order of Treasurer, State of Illinois. Currency will not be accepted. No refunds will be made for CD-ROMs returned or not bid. Electronic plans and/or proposals may also be downloaded from the Department's web site [www.dot.il.gov](http://www.dot.il.gov).

Contractors wanting to bid must submit the properly completed "Request for Proposal Forms and Plans & Request for Authorization to Bid" (BD 124) and the properly completed ORIGINAL "Affidavit of Availability" (BC 57) to Room 322 or 323 no later than 4:30 p.m. prevailing time, three (3) days prior to letting date. The Authorization to Bid request cut-off date is 4:30 p.m. prevailing time, September 20, 2005.

- c. Each bid shall be accompanied by one (1) copy of a Bid Bond on Form BD 356B in the amount, which is not less than five (5) percent of the aggregate amount of the bid.
- d. Pre-Qualification Rating. The Illinois Department of Transportation pre-qualification ratings and other applicable evidence of competency of bidders to perform the work contemplated will be utilized for all Service Bulletin items. This pre-qualification rating will be established on the basis of a Financial Statement and Experience Questionnaire.
- e. Requirements for Corporations outside the State of Illinois. Before any Contract is executed, a Corporation from another State must conform to the Statutes of the State of Illinois, and may be asked to furnish a copy of the certificate from the Secretary of State, State of Illinois, showing that such foreign corporation is authorized to do business in the State of Illinois.
- f. Civil Rights Act of 1964. The Illinois Department of Transportation, Division of Aeronautics, in accordance with Title VI of the Civil Rights Act of 1964, 78 Stat. 252, 42 U.S.C. 2000d-4 and Title 49, Code of Federal Regulations, Department of Transportation, Subtitle A, Office of the Secretary, Part 21, Nondiscrimination in Federally-assisted programs of the Department of Transportation issued pursuant to such Act, hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, minority business enterprises will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds or race, color, or national origin in consideration for an award.

In a case in which a bidder or prospective contractor or proposed subcontractor who has participated in a previous contract or subcontract subject to the equal opportunity clause has not filed a compliance report due under applicable instructions, such bidder, prospective contractor, or proposed subcontractor shall submit a compliance report prior to the award of the proposed contract or subcontract. When a determination has been made to award a contract to a specific contractor, such contractor shall prior to award, furnish such other pertinent information regarding his own employment policies and practices as well as those of his proposed subcontractors as the Sponsor, or the Executive Vice Chairman of the President's Committee may require.

For any contract or subcontract for \$50,000.00 or more, and having 50 or more employees, the contractor or subcontractor will be required to maintain a written Affirmative Action Plan.

g. Special Requirements.

- (1) Payment to Labor. The successful bidder will be required to pay to the laborers, workmen, mechanics, and other employees for the work under the contracts, not less than the general prevailing wage for each craft, trade or occupation, and not less than the minimum wage rates as shall be established by the U. S. Secretary of Labor for federally assisted projects and by the Illinois Department of Labor for state/local projects.
- (2) Affirmative Action Requirements - Equal Employment Opportunity. Various contractor, union and minority organizations have prepared specific plans for Equal Employment Opportunity. Should such a plan or plans apply to the proposed project(s) listed below, the Bid Conditions will be included in the Contract Document for that project, and all bidder's, prospective contractors and/or subcontractors shall be required to comply with any and all provisions set forth therein.

- h. Specifications. The proposed work is to be constructed in accordance with the requirements of the Illinois Standard Specifications for Construction of Airports, dated January, 1985, the Supplemental Specifications and Recurring Special Provisions, adopted July 1, 2004 and the Special Provisions specified in the proposal. The Illinois Standard Specifications for Construction of Airports and the Supplemental Specifications and Recurring Special Provisions are available at [www.dot.il.gov/aero/airspecs.html](http://www.dot.il.gov/aero/airspecs.html). Printed copies of the Illinois Standard Specifications for Construction of Airports may be obtained by applying to the Department of Transportation, Division of Aeronautics, Bureau of Engineering, Design Section, at Capital Airport/One Langhorne Bond Drive, Springfield, Illinois 62707-8415. The order should be accompanied by a check made payable to the Division of Aeronautics in the amount of \$10.00 for each copy ordered.

3. Proposed Work:

1A Greater Rockford Airport

Rockford, Illinois

Winnebago County

Ill. Proj. RFD-3487

AIP No. 3-17-0088-43

Contract No. RO012

Rehabilitate Taxiway F East and Taxiway B North, Phase 1; Relocate Falcon Road, including Runway 1/19 RSA Improvements; Construct South RIAT Perimeter Road - which includes the following major work items: 36,430 L.F. UG Cable; 4,500 L.F. 1-Way Concrete Encased Duct; 50 Each MITL-Base Mounted; 31,659 C.Y. Unclassified Excavation; 10,090 S.Y. Soil Stabilization Fabric; 3,901 L.F. Class E Fence, Vinyl-10'; 4,085 L.F. Remove Class E Fence; 5,590 Ton Bituminous Base Course; 10,925 C.Y. Porous Granular Embankment; 36,980 S.Y. Crushed Aggregate Base Course; 6,805 Ton Bituminous Surface Course; 44,205 S.Y. Bituminous Pavement Milling; 5,175 S.Y. Remove Bituminous Pavement; 30,950 S.Y. 15" PCC Pavement; 10,980 Gal. Bituminous Prime Coat; 15,899 S.F. Pavement Marking-Waterborne; 60,968 S.Y. Soil Guard; 218 Each Retrofit Existing MITL; 3 Each Adjust MALSR Tower; 12.6 Acre Seeding  
Pre-Bid meeting: N/A  
(DBE 12.0%)